



3131 SW 13<sup>th</sup> Drive  
Deerfield Beach, FL 33442  
Phone: 954-427-0705  
Fax: 954-360-9879  
License: EC13010770

03/26/2024

**To: City of Hollywood - Department of Design & Construction Management  
2600 Hollywood Blvd.  
Hollywood, FL 33020**

**Attn: Karyn Sashi**

**Proposal for: The Villas of Positano – Light Pole Replacement**

Pomeroy Electric Incorporated will furnish labor & misc. electrical materials to remove (19) existing light poles and install (21) new light poles and light fixture heads as per electrical drawing sheets E-001; E-011; E-012; E-101; E-102; E-502 & E-711 by OSBORN Engineering. Our intent is to work on multiple light poles within the daylight hours and ensuring these are energized before nightfall. Refer to scope below:

**Included Scope:**

1. Disconnect, removal and disposal of existing concrete light pole and fixture head. The fixture heads will be turned over to the client for attic stock.
2. Rework existing underground electrical to allow for the new light pole installation.
3. Furnish and install new concrete bases; cast aluminum light poles and light fixture heads.
4. Furnish and install new pull boxes, ground rods and misc. electrical materials at the base of each light pole.
5. We've included (2) month rental of 19' scissor lift for the installation of the fixture heads.
6. The existing wiring, raceways and panels were found to be in good working order, therefore, these are to remain as is and use for the new installation.
7. All work is to be performed during regular working hours. (No night; OT or weekend work is included)

**Items Not Included:**

- a) All or any items not listed above.
- b) Engineered drawings, wind load calculations, permits and permit fees.
- c) Overtime, shift work or accelerated schedule costs.
- d) Employee parking and all associated fees.
- e) Any items requested by the Authority Having Jurisdiction or existing code violations/upgrades.



3131 SW 13<sup>th</sup> Drive  
Deerfield Beach, FL 33442  
Phone: 954-427-0705  
Fax: 954-360-9879  
License: EC13010770

*Pomeroy Electric Incorporated proposes to furnish & install all labor & materials for a complete working system in accordance with the above electrical drawing sheets and scope of work for the amount listed below:*

**Total per above: ..... \$ 256,750.00**

**Breakouts included in proposal (for accounting purposes only):**

Disconnect, removal and disposal:..... **\$ 31,110.00**  
Allowed (10) light pole deliveries:..... **\$ 5,915.00**  
Installation of light poles & heads:..... **\$ 46,620.00**  
(2) month of scissor lift rental:..... **\$ 2,200.00**  
Concrete bases & lighting fixtures (Taxes & Mark-up):..... **\$ 22,217.00**

**Allowance breakouts included in proposal:**

Unforeseen conditions:..... **\$ 5,000.00**  
Site restoration after pole installation:..... **\$ 8,000.00**  
Owner contingency:..... **\$ 5,000.00**

**Breakouts included in proposal for Direct Purchase Option:**

Concrete Bases:..... **\$ 15,188.00**  
Light Poles & Light Fixtures:..... **\$ 115,500.00**

**Estimated Lead-Times (from the date the factory receives the order):**

Concrete Bases: **4-5 weeks**  
Light Poles & Light Fixtures: **12-14 weeks**

Authorized Signature of Pomeroy Electric Incorporated

Raul Cordero  
Raul Cordero – 03/26/2024

Date of Acceptance \_\_\_\_\_ of Proposal \_\_\_\_\_

**This proposal is void if not accepted in writing within (30) 30 days after this date.**

**Commodity escalation note: Not applicable for this project.**

*Pomeroy Electric Inc., shall not be liable or responsible for any delays or damages caused by material delivery delays or limited quantities/backorders as a result of shortages, rationing or unavailability.  
Subcontractor shall not proceed with Changes until scope, time and additional cost are stated and signed by Contractor.  
Project labor rate for additional work inclusive of all burden overhead and profit shall be \$85.00 per man-hour, Premium time adder for overtime shall be \$42.50 per man-hour.*