
# **EROSION AND SEDIMENT CONTROL NOTES**


- 1. THE CONTRACTOR IS RESPONSIBLE FOR FOLLOWING THE BEST EROSION AND SEDIMENT CONTROL PRACTICES AS OUTLINED IN THE PLANS, SPECIFICATIONS AND APPLICABLE WATER MANAGEMENT DISTRICT PERMIT(S) FOR THIS PROJECT.
- 2. FOR ADDITIONAL INFORMATION ON SEDIMENT AND EROSION CONTROL REFER TO "THE STATE OF FLORIDA EROSION AND SEDIMENT CONTROL DESIGNER AND REVIEWERS MANUAL" FROM THE STATE OF FLORIDA DEPARTMENT OF ENVIRONMENTAL REGULATION (FDER).
- 3. THIS PLAN INDICATES THE MINIMUM EROSION AND SEDIMENT CONTROL MEASURES REQUIRED FOR THTS PROJECT THE CONTRACTOR IS RESPONSIBLE FOR MEETING ALL APPLICABLE RULES, REGULATIONS AND WATER QUALITY GUIDELINES AND MAY NEED TO INSTALL ADDITIONAL CONTROLS.
- 4. ALL EXCAVATIONS AND EARTHWORK SHALL BE DONE IN A MANNER TO MINIMIZE WATER TURBIDITY AND POLLUTION. DISCHARGE SHALL BE CONTROLLED AND REROUTED THROUGH FILTERS, SILTATION DIAPERS AND SUMPS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PREVENTION, CORRECTION, CONTROL AND ABATEMENT OF EROSION AND WATER POLLUTION IN ACCORDANCE WITH CHAPTER 62-302, FLORIDA ADMINISTRATIVE CODE.
- 5. THE CONTRACTOR SHALL PAY FOR ANY WATER QUALITY CONTROL VIOLATIONS FROM ANY AGENCY THAT RESULTS IN FINES BEING ASSESSED TO THE OWNER BECAUSE OF THE CONTRACTOR'S FAILURE TO ELIMINATE TURBID RUNOFF FROM LEAVING THE SITE AND RAISING BACKGROUND LEVELS ABOVE EXISTING BACKGROUND LEVEL.
- 6. THE SITE CONTRACTOR IS RESPONSIBLE FOR REMOVING THE TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES AFTER COMPLETION OF CONSTRUCTION AND ONLY WHEN AREAS HAVE BEEN STABLIZED.
- 7. ADDITIONAL PROTECTION ON-SITE PROTECTION MUST BE PROVIDED THAT WILL NOT PERMIT SILT TO LEAVE THE PROJECT CONFINES DO TO UNFORSEEN CONDITIONS OR ACCIDENTS.
- 8. SILT FENCES SHALL BE USED ALONG THE PROPERTY LINES TO MINIMIZE OFFSITE SILTATION MITGRATION.
- 9. SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEASE DAILY DURING PROLONGED RAINFALL. ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY.
- 10. SHOULD THE FABRIC ON A SILT FENCE DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER IS STILL NECESSARY, THE FABRIC SHALL BE REPLACED PROMPTLY.
- 11. FILER FABRIC SHALL BE INSTALL UNDER INLET GRATES AND EXTEND A MINIMUM OF 1 FOOT BEYOND EACH SIDE OF THE INLET STRUCTURE. IF MORE THAN ONE STRIP OF FABRIC IS NECESSARY, THE STRIPS SHALL BE OVERLAPPED 1 FOOT.
- 12. SEDIMENT DEPOSITS SHOULD BE REMOVED AFTER EACH RAINFALL AND AS NEEDED.
- 13. ANY DISCHARGE FROM DEWATERING ACTIVITY SHALL BE FILTERED AND CONVEYED TO THE OUTFALL IN A MANNER WHICH PREVENTS EROSION AND TRANSPORTATION OF SUSPENDED SOLIDS TO THE RECEIVING OUTFALL.
- 14. DEWATERING PUMPS SHALL NOT EXCEED THE CAPACITY OF THAT WHICH REQUIRES A CONSUMPTIVE USE PERMIT FROM THE APPLICABLE WATER MANAGEMENT DISTRICT.
- 15. ALL DISTURBED AREAS SHALL BE GRASSED, FERTILIZED, MULCHED AND MAINTAINED UNTIL A PERMAMENT VEGETATIVE COVER IS ESTABLISHED.
- 16. SOD SHALL BE PLACED IN AREAS WHICH MAY REQUIRE IMMEDIATE EROSION PROTECTION TO ENSURE WATER QUALITY STANDARDS ARE MAINTAINED.
- 17. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER BARRIER ARE NO LONGER REQUIRED SHALL BE DRESSED TO CONFROM TO THE EXISTING GRADE, PREPARED AND SEEDED.
- 18. CONTRACTOR SHALL INSURE THAT ALL DRAINAGE STRUCTURES, PIPES, ETC. ARE CLEANED OUT AND WORKING PROPERLY AT TIME OF ACCEPTANCE.
- 19. FLOATING TURBIDITY BARRIERS WILL BE PLACED OFF SET FROM THE SEAWALL ADJACENT TO THE PROPERTY. IF SEAGRASSES ARE PRESENT BARRIERS WILL NOT BE PLACED OVER THEM. THE FLOATING TURBIDITY BARRIERS SHALL ALSO BE INSTALLED IN A MANNER TO PREVENT MANATEE ENTANGLEMENT.
- 20. ALL DEATERING, EROSION, AND SEDIMENT CONTROL SHALL REMAIN IN PLACE UNTIL AFTER COMPLETION OF CONSTRUCTION AND SHALL BE REMOVED WHEN AREAS HAVE BEEN STABILIZED.


Regina Bobo-Jackson, State of Florida, Professional Engineer, License No. 38550

This item has been digitally signed and sealed by Regina Bobo-Jackson, P.E. on the date adjacent to the seal.

Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.









NOTE: INSTALL FILTER FABRIC UNDER ALL GRATES TO PREVENT SILT AND CONSTRUCTION DEBRIS FROM ENTERING THE SYSTEM.


INLET PROTECTION














0







# LEGAL DESCRIPTION

LOT 8, BOOK 4 OF BEVERLY PARK, AS RECORDED IN PLAT BOOK 25, PAGE 44 OF THE PUBLIC RECORDS OF BROWARD COUNTY, FLORIDA.

# GENERAL NOTES:

- 1. BASE SURVEY WAS PROVIDED BY JOHNSTON & JOHNSTON LAND SURVEYING SERVICES, INC.
- 2. ELEVATIONS ARE NOT PROVIDED ON THIS SURVEY.
- 3. HORIZONTAL AND VERTICAL CONTROL SHALL BE PROVIDED BY THE CONTRACTOR'S SURVEYOR, IF REQUIRED. LAYOUT IS THE RESPONSIBILITY OF THE CONTRACTOR.
- 4. IT IS THE INTENT OF THESE DRAWINGS TO BE IN ACCORDANCE WITH APPLICABLE CODES AND AUTHORITIES HAVING JURISDICTION. ANY DISCREPANCIES BETWEEN THESE DRAWINGS AND APPLICABLE CODES SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE ENGINEER AND OWNER REPRESENTATIVE.
- 5. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO HAVE ALL UNDERGROUND UTILITIES VERIFIED AND LOCATED PRIOR TO THE START OF CONSTRUCTION. ALL TRENCH EXCAVATION SHALL PROCEED WITH EXTREME CAUTION. IN THE EVENT THAT EXISTING UTILITIES ARE DAMAGED, IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO REPAIR OR REPLACE SUCH DAMAGES.
- 6. CONTRACTOR SHALL BE RESPONSIBLE FOR RESETTING ANY DISTURBED EXISTING MANHOLES, VALVE BOXES, BLOW— OFF RISERS OR ANY OTHER POINT OF ACCESSIBILITY TO UTILITIES, AND TO MATCH ASPHALT GRADES, AS REQUIRED, WHETHER SPECIFICALLY SHOWN ON THE DRAWINGS OR NOT.

# SPECIFIC NOTES:

1. ALL STORM WATER RUNOFF MUST REMAIN ONSITE DURING CONSTRUCTION. THE NEW CONSTRUCTION SHALL HAVE NO DRAINAGE IMPACTS TO ADJACENT PROPERTIES, SURROUNDING RIGHT OF WAYS OR STORM WATER FACILITIES. FILTER FABRIC SHALL BE INSTALLED IN INLETS PRIOR TO THE START OF CONSTRUCTION. BEST MANAGEMENT PRACTICES MUST BE USED FOR EROSION AND SEDIMENT CONTROL.


- 2. PROPERTY WILL BE SLOPED AWAY FROM PROPERTY LINE AT THE BEGINNING OF CONSTRUCTION TO MAINTAIN ALL DIRT AND DEBRIS ON SITE.
- 3. DRAINAGE SYSTEM AND SWALES SHALL BE INSTALLED AS DETAILED.
- 4. COORDINATE THE GRADING AND DRAINAGE ON THIS PLAN WITH THE LANDSCAPE PLANS.
- 5. CONCRETE DRIVEWAYS ON PRIVATE PROPERTY SHALL BE 5-INCH THICK, 3,000 PSI WITH FIBER MESH WHILE THE PORTION OF THE DRIVEWAY LOCATED WITHIN THE ROW (OUTSIDE OF THE PROPERTY LINES) SHALL BE A MINIMUM OF 6 INCHES THICK, 3,000 PSI, WITH NO METAL OR FIBER MESH AND WILL BE CONSTRUCTED FLUSH WITH THE EXISTING ROADWAY AND SIDEWALK. THE ENTIRE DRIVEWAY SHALL MAINTAIN CONTROL JOINTS LOCATED EVERY 250 SQ.FT AND THE EXISTING ASPHALT IN THE CITY ROW WILL BE SAWCUT FOR A CLEAN STRAIGHT EDGE.
- 6. A NEW WATER SERVICES CONNECTIONS SHALL BE INSTALLED, COORDINATE WITH BROWARD COUNTY WATER AND WASTEWATER SERVICES (BCWWS). THE NEW SERVICE AND METER SHALL BE IN ACCORDANCE WITH BCWWS STANDARDS.
- 7. FROM 1/4" BUT NOT GREATER THAN 1/2" WILL BE BEVELED TO MEET ADA REQUIREMENTS FOR ADA ACCESSIBLE ROUTES BETWEEN THE ADA ACCESSIBLE PARKING AND BUILDING ACCESS AND ACCESSIBLE ROUTE TO THE PUBLIC RIGHTS—OF—WAY ANY LIP.
- . ALL ROADS AND ALLEYS ADJACENT TO THE PROPERTY ARE TO BE MILLED AND RESURFACED.


# SITE CALCULATIONS:

	EXISTING	PROPOSED
BUILDING FOOTPRINT	0 SQ FT	2,040 SQ FT
DRIVEWAY & WALKWAYS	4,375 SQ FT	2,145 SQ FT
LANDSCAPE AREA	925 SQ FT	1,115 SQ FT
TOTAL AREA	5,300 SQ FT	5,300 SQ FT
TOTAL PERVIOUS AREA	925 SQ FT	1,115 SQ FT
TOTAL IMPERVIOUS AREA	4,375 SQ FT	4,185 SQ FT


# DEMAND TABLE

Type Demand	Type Unit	Demand /Unit	Unit	No. of Units	Demand
Prior Water Demand	Parking Lot	0	ea.	1	0 gpd
Prior Wastewater Demand	Parking Lot	0	ea.	1	0 gpd
Proposed Water Demand	Warehouse	26 gpd/unit	ea.	2,040 sf/1	53.04 gpd
Proposed Wastewater Demand	Warehouse	26 gpd/unit	ea.	2,040 sf/1	53.04 gpd





# NAREHOUSE MEDAL BUILL 6013 RODMAN STREET HOLLYWOOD, FLORIDA 330




GEA PROJECT NO.: 23004
DATE: 02-02-2023
SCALE: AS SHOWN
DESIGNED BY: R.B.J.
DRAWN BY: L.B.
CHECKED BY: R.B.J
APPROVED BY: R.B.J

SHEET TITLE

CIVIL PLAN

C2 of 5



SECTION D-D

NTS

6.25' 3.00'


4:1MAX 4:1MAX

SECTION E-E

NTS

SWALE C

PARKING LO



- 1. STABILIZED SUBGRADE SHALL HAVE A MINIMUM LIMEROCK BEARING RATIO (LBR) OF 40 AND IS REQUIRED FOR ALL NEW PAVEMENT CONSTRUCTION, ALL STABILIZED SUBGRADE SHALL BE STRING LINED FOR GRADE AND PASS ALL REQUIRED DENSITY TESTING PRIOR TO PLACEMENT OF THE CONCRETE
- 5-INCH THICK, 3,000 PSI WITH FIBER MESH WHILE THE PORTION OF THE DRIVEWAY LOCATED WITHIN THE ROW (OUTSIDE OF THE PROPERTY LINES) SHALL BE A MINIMUM OF 6 INCHES THICK, 3,000 PSI, WITH NO METAL OR FIBER MESH AND SHALL BE CONSTRUCTED FLUSH WITH THE EXISTING ROADWAY AND SIDEWALK.
- 3. THE ENTIRE PARKING AREA AND DRIVEWAY SHALL MAINTAIN CONTROL JOINTS LOCATED EVERY 250 SQ.FT.


CONRETE PAVEMENT DETAIL

N.T.S.

FRENCH DRAIN


LONGITUDE SECTION

4. THE EXISTING ASPHALT IN THE CITY ROW SHALL BE SAWCUT FOR A CLEAN STRAIGHT EDGE CONNECTION.




PRECAST DRAINAGE CATCH BASIN

# N,T,S,



POLLUTION RETARDENT BAFFLE (PRB) N,T,S,


Regina Bobo-Jackson, State of Florida, Professional Engineer, License No. 38550 This item has been digitally signed and sealed by Regina Bobo-Jackson, P.E. on the date adjacent to the seal. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.




1. FILTER FABRIC PER F.D.O.T. STD. INDEX #199 SHALL BE USED AT EACH SIDE AND ON TOP, AND AT EACH END OF FRENCH DRAIN TRENCH.


- 2. THE DEPTH OF THE EXFILTRATION TRENCH SHALL BE 9.50 FEET.
- 3. AFTER THE BALLAST ROCK HAS BEEN PLACED TO THE PROPER ELEVATION IT SHALL BE CAREFULLY VIBRATED OR COMPACTED IN ORDER TO ALLOW FOR INITIAL SETTLEMENT THAT MAY OCCUR. IF IT DOES TAKE PLACE, ADDITIONAL BALLAST ROCK WILL BE ADDED TO RESTORE THE BALLAST ROCK TO THE PROPER ELÉVATION SO THAT THE EXFILTRATION TRENCH CAN BE COMPLETED IN ACCORDANCE WITH THE


TYPICAL DETAIL — EXFILTRATION TRENCH





3302 AL, HOUSE MEDA 113 RODMAN S LYWOOD, FLOF WAREHOU 6013 F HOLL







































NAREHOUSE MEDAL BUILDII 6013 RODMAN STREET HOLLYWOOD, FLORIDA 33023











 THE CLEAN OUT SHALL BE INSTALLED IN THE MIDDLE OF THE SIDEWALK. THIS DIMENSION WILL VARY DEPENDING UPON THE WIDTH OF THE SIDEWALK. 2.5' APPLIES TO 5' SIDEWALK WIDTH. IF SIDEWALKS DO NOT

EXIST, THE CLEAN OUT SHALL BE INSTALLED 2.5' FROM THE RIGHT OF

WAY LINE.

2. A NEW SECTION OF SIDEWALK SHALL BE POURED AROUND THE CLEAN-OUT BOX WHEN WORKING IN AN AREA WITH EXISTING

SIDEWALKS.
3. IN GRASS AREA USE 24"x24" OR 24" DIAMETER CONCRETE COLLAR.

SEWER SERVICE

CONNECTION AT PROPERTY

LINE OR EASEMENT LINE


**PROFILE** 

REVISED


7/7/2021


**FIGURE** 






REHOUSE MEDAL BUILDING 6013 RODMAN STREET OLLYWOOD, FLORIDA 33023







seal #LA.0001111

signature revision/date 1. Revised site plan 4-2-24

. Revised site plan 6-12-2

Z Z

SC AND!

5/11/23

6013 RODMAN S Hollywood, Florid

sheet no.

1. 3" of clean mulch in a 5' diameter ring with a 3" high continuous water earth berm. Keep mulch 3" from trunk and stems of all vegetation. The use of Cypress or red mulch is prohibited.

2. Planting hole shall be twice as wide at the root ball and no deeper than the height of the root ball. The top of the root ball shall be approximately 1' above the finish grade. The trunk flair or first order roots must be visible above grade.

3. Finish grade.

4. Existing undisturbed soil.

5. 3 strands of 3/4" diameter biodegradable rope tied to each tree and supported in the ground with 3 - 1" x 2" x 1' buried so top is 1" below grade.

6. Till and loosen soil to a depth of 8" with a radius of 3' from trunk of tree.

7. Place soil amendments (ie. "Terrasorb," fertilizer tablets) in the top 8" of the planting hole.

8. Remove top 1/3 third of the natural burlap and wire basket completely. If wire baskets cannot be removed due to root ball stability, slice the basket to the bottom of the root ball on a minimum of 4 sides.

9. Back fill to 50% sand and 50% muck mixed with 50% existing soil unless

10. Single dominant leader, good structure, Florida #1 or better.

11. Till and loosen existing soil to a depth of 8" in all planting beds then till in 4" of planting soil throughout.

not soil. -

12. Root barrier system as indicated on the plans if applicable.

13.1. Veitchia - Prune only dead and weak lower fronds. Do Not Prune Higher than Paralel to Ground. Tie Fronds With Biodegradable Twine or Equal.

13.2. Remove All Fronds. Leave 12" of Bud Minimum. Do Not Damage Bud.

14. 5 Layers of Burlap Minimum.


15. 2" x 4" x 16" Wood Battens Connected With 3/4" Steel Bands. 2 Bands Minimum. Bands shall be Approved Compression Bands or Shall be Nailed to each Batten with Galvanized 1 1/4" Roofing Nails.

16. 2" x 4" x 8' Pine Brace. Min. of 3. Nail Braces to Battens with a min. of 2 #20d Galvanized Nails Bury Braces in Undisturbed Soil to a minimum depth of 8-12". 17. Bright Colored Flagging Each Brace or Guy. 18. Brace at 45-60 Degrees.

Palm Detail

19. Contractor shall assure percolation of all planting pits.


ALL BACKFILL TO BE WATER JETTED DURING PLANTING FOR MAXIMUM STABILITY



Shade Tree Planting Detail.

Shrub Spacing - Beds

Triangular Spacing



# Specifications:

1. Contractor shall provide and install plants in accordance with plans and specifications. 2. "Final Acceptance" shall mean that point in time when all requirements of project drawings and specifications are completed, including any punchlist items, to the satisfaction of the owner's representative. The contractor shall be notified in writing of final acceptance by the owner's representative. 3. "Warranty Period" shall be a twelve (12) month period beginning at Final Acceptance. 4. "Maintenance Period" shall begin when plant material is installed and

continue until notification of Final Acceptance. 5. "Final Inspection" shall occur upon the Contractor's completion of the given phase of the project and notification of the owner. 6. The installation shall be by a single firm. Plants shall be provided

by the contractor as specified. 7. Plant names indicated shall comply with "Standardized Plant Names" as adopted by the latest edition of the American Joint Committee of Horticultural Nomenclature. Names of varieties not listed shall conform generally with names accepted by the nursery trade. Provide stock true to botanical name and legibly tagged.

8. Contractor shall provide photographs of plant material prior to

9. Plant selection shall comply with sizing and grading standards of the latest edition of American Standard for Nursery Stock and Florida Grades and Standards for Nursery Plants. All plant material shall be Florida Number One.

10. Substitutions will not be accepted.

11. The owner's representative shall inspect for quality assurance and approve or reject plant material at time of final inspection.

12. The owner reserves the right to reject any and all plant material. 13. The contractor must submit certificates of inspection, analyses for soil amendments, and labels for herbicides, insecticides and fertilizer materials.

14. The contractor must submit the following material samples: a. Mulch

b. Topsoil c. Preemergent herbicide

d. Fertilizer

e. Photographs of typical plant material 15. The owner's representative will provide "notice to proceed" to the

15.1. The Contractor shall not obstruct or cause any hazard to traffic during the performance of their work. The Contractor shall assign one of their employees the responsibility of maintaining sufficient warning devices

and barriers to protect the public and workers. 16. Contractor shall be liable for damages to and is responsible for protecting utilities, paving and other facilities, buildings, structures, or irrigation from damage during installation. Contractor shall notify "Call Sunshine" (800-638-4097) 48 hours prior to beginning work. 17. Contractor shall protect plant material from dessication during

18. Contractor must familiarize himself with existing project conditions, eg., utilities, soil strata, drainage, and sightlines prior to installation. Conflicts shall be addressed with the owner's

transport and installation period. In most instances this means daily

representative. 19. Contractor shall be substantially completed with each phase of the project within twenty (20) days from the notice to proceed.

20. Contractor shall provide tree protection within the scope of

21. Nursery stock shall meet the minimum dimensions for height, spread, caliper and rootball as described within the plans and specifications. 22. All plants must be healthy, vigorous and full with good branch

23. Palm trunks must be straight with girth in proportion to height and free of constriction, defects, and injuries. Palm foliage must be healthy, dense, free of disease, and insect infestation. 24. Rootballs must be intact, protected from dessication and evenly rooted throughout media. Plants with rootballs that have bound or girdled roots shall be rejected.

25. Refer to drawings and other parts of specifications for accessories


specifically used on this project. 26. Backfill media shall match textural condition of existing soil with soil reaction (pH) adjusted to 5.5-6.5. Soils with no definitive characteristics may require some amendment.

27. Fertilizer shall be complete, Slow-Release with the following analysis and source 10% nitrogen derived from ammonium nitrate. 2% phosphorous derived from super phosphate. 10% potassium derived from potassium sulfate. 4% magnesium derived from magnesium sulfate.

The fertilizer shall contain the essential micro-nutrients (Chelated Fe, Mn, Zn, Mo, Bo, Cu) as sulfates in parts per million (ppm). Slow-Release Fertilizer shall be applied at 2-4 pounds/1000 sf/application

for a total of not more than 6 pounds each year. Slow-Release Fertilizer shall be uniformly distributed from the trunk up to the dripline. Slow-Release Fertilizer shall be distributed over the planting pit under and prior to mulch. 28. Mulch shall be Exotic Invader Species and shall be free of viable seed, clean and free from weeds and other debris 29. Pre-emergent herbicide: apply granular Chipco "Ronstar" or approved

equal at label rate. 30. Trees shall be secured as shown in details.



REQUIREMENTS APPLY TO FIRE HYDRANTS. SIAMESE CONNECTIONS AND ANY OTHER FIRE EQUIPMENT FOR UTILIZING A FIRE HOSE, ON PRIVATE OR PUBLIC

7'-6" FROM ALL WORKING SIDES AND 3'-6" FROM REAR. SOD ONLY IN THESE AREAS. THE CLEAR ZONE SHALL BE FREE OF LANDSCAPE, (EXCEPT SOD), MAILBOXES, PARKING SPACES,

EXCEPTIONS: OTHER FIRE FIGHTING EQUIPMENT OR TRAFFIC POSTS TO PREVENT FIRE FIGHTING

LIGHT-POSTS AND ALL OTHER OBJECTS.

Fire Hydrant Clear Zone

31. Palms shall be braced as shown in the details. 32. Contractor will be given access to the owner's water at no charge for maintenance related activity through the completion of the 33. Contractor shall provide and install plants in the areas and spacings indicated in the plans and shall be responsible for his own quantity takeoff. Quantities shown on plans are for convenience only. 34. Commencement of work: Work under this awarded bid shall commence not less than 10 days after notice to proceed and shall be completed in an orderly fashion. Once work has begun, it shall continue on consecutive work days until it has been completed. Sunday, Saturdays, holidays and

stoppages due to inclement weather or delays required by the owner shall

35. Maintenance: The Contractor is responsible for the work through final acceptance. Plant material shall receive water daily.

be excluded.

36. Plant materials are to be installed in accordance with the landscape plan and specifications. Good horticultural practices shall be observed. 37. Contractor shall stake and/or paint planting locations in the field. Upon approval by the owner's representative, these areas shall be sprayed with an approved herbicide and maintained weed free for the duration of the project. 38. Excavate planting holes with vertical sides. Do not disturb soil at bottom of planting holes. Make excavations or till and loosen soil to the width required in planting details and to the depth of of the

39. Set plants on subsoil, plumb, and in center of holes with the top of root mass at same elevation or slightly higher than finished landscape grades. Backfill field soil around sides of root mass at same elevation or slightly higher than finished landscape grades. Backfill soil around sides of root mass and work each layer to settle and eliminate voids and air pockets. Material must be watered in as planted. 40. Provide berm around edge of rootball to form shallow saucer to collect water. Watering saucer, regardless of hole size, is to be at

41. Contractor shall broadcast within the planters at the recommended rate, a broad spectrum Preemergent herbicide prior to

42. Contractor shall incorporate a controlled release fertilizer tablet at the proper rate and analysis prior to mulching. 43. Contractor shall apply a three (3) inch layer of sterilized

44. Trees and palms are to be secured by contractor as shown in the 45. The owner's representative shall inspect plants during installation. Plant material that is in shock or has been damaged during installation

shall be replaced by contractor within five (5) working days from

46. Contractor shall remove from the work site all excess materials (eg., soil, debris and equipment) daily through the duration of the project. Damages resulting from installation shall be repaired by the

47. Inspection to determine acceptance of planted areas will be made by the owner's representative upon contractor's request. Provide notification a minimum of five (5) working days before requesting inspection date. Planted areas will be accepted provided all requirements, including maintenance, have been satisfied and plant materials are in a healthy, vigorous condition. 48. The owner's representative will prepare a "punch list" of those items which must be corrected before reinspection for final acceptance. the representative will determine an appropriate time period for corrections. Contractor shall request reinspection two (2) working davs in advance. 49. Begin maintenance immediately after planting. Maintain all plant

50. Maintenance shall include but is not limited to pruning, cultivating, mowing, weeding, fertilizing, watering, and application of appropriate

pesticides necessary to maintain plants in healthy condition. a. Reset settled plants to proper grade and position.

b. Restore planting saucer and mulch layer. c. Tighten and repair elastic guys or other supports.

d. Correct defective work.

material until final acceptance.

e. Remove and replace rejected material within one (1) day from f. Maintain rootball in moist condition to promote good root development

for duration of project and maintenance period. 51. Upon satisfactory completion of maintenance period as determined by final inspection, the owner will assume maintenance

52. Contractor shall warrant all plant material to be in healthy, vigorous condition for a period of twelve (12) months after final acceptance.

53. Contractor shall replace at own expense and in accordance with specifications, all plant material that are dead or unhealthy as determined by the owner's representative. Contractor shall warrant all replacement plants for twelve (12) months.

54. Warranty shall not include damage or loss of plants caused by fires, floods, freezing rains, lightning storms or winds over 75 miles per hour; winter kill caused by extremely cold tempatures not typical of the area and acts of vandalism.

# Sod:

1. Sod shall be Stenotaphrum secundatum 'Floratam' solid sod. Sod shall be free of weeds, live, fresh and uninjured at the time of planting. Sod shall be 2" thick and have a soil mat adhering to the roots of sufficient thickness to withstand all necessary handling.

2. Sod shall be placed over all areas not covered by planting beds, buildings or structures, paved vehicular use areas, and walkways such that there is no area of uncovered soil.

3. The area over which the sod is to be placed shall be scarified or loosened to a suitable depth and then raked smooth and free from rocks or stones. Where the soil is sufficiently loose and free of rocks, stones or debris ground preparation may be eliminated. Topsoil shall have a min. depth of 2"

4. Sod shall be placed on the prepared surface with edges directly abutting eachother. Sod shall be lightly tamped to ensure firm and smooth embedding. Sod shall be staggered to avoid a continuous seam on slopes or along the flow line of any drainage swale. In order to prevent erosion caused by vertical edges at the edge of sloped areas the sod areas at the edge of sloped areas shall be tamped to produce a smooth and continuous slope. On steep slopes sod shall be prevented from sliding by means of wooden pegs or equivalent driven through the sod blocks into firm soil such that pegs are flush with grade. Pegs shall have no sharp edges which may come into contact with pedestrians.

5. Topsoil shall be 50% Florida Peat and 50% Coarse Sand

**ELECTRICAL HAZARD** 

All work in the vicinity of overhead power lines shall comply with ANSI Z 133.1. Contact FPL before beginning work.

48 HOURS BEFORE DIGGING CALL TOLL FREE

1-800-432-4770 U.N.C.L.E. UNDERGROUND UTILITIES

NOTIFICATION CENTER

**sea** #LA 0001111

signature revision/date

etails and S

comm. no date:

11623 | 5/12/23 checked by 


Ш TR

BUIL

A

Ш  $\overline{\geq}$ RODMAN ST wood, Florida HOUS Hollywood, WARE  $\Im$ 601

sheet no.



NOTE: SEE SHEET I-2, DETAILS 1 AND 2. HEADS SHALL BE ON RISERS IN Irrigation SHRUBS AND GROUNDCOVERS.

Quantity	Symbol	Description	Part Number	Pres
5		Rain Bird 15CST 1806	15CST	30
6		Rain Bird 15EST 1806	15EST	30
1	¥	Rain Bird HE-VAN-10-180 1806-PRS		30
4	$\hookrightarrow$	Rain Bird HE-VAN-10-90 1806-PRS		30
1	45° ▼	Rain Bird HE-VAN-15-45 1806-PRS		30
2	$\Leftrightarrow$	Rain Bird HE-VAN-8-45 1806-PRS		30
11	$\Diamond$	Rain Bird HE-VAN-8-90 1806-PRS		30
1	M	5/8 inch meter		
1		Watts 009M3QT - 3/4" RPZ BACKFLOW	/ PREVENTER	
2		Rain Bird 075-DV	075-DV	
1		Rain Bird ESP-TM2-4 stations controller	- locate per own	er
1		1" brass gate valve		
1		Rain Bird RSD-BEx RAIN SENSOR		
527.64		Class 200 3/4" Lateral		
85.07		Schedule 40 1 1/2" Lateral Sleeve		
113.15		Schedule 40 1" Mainline		
9.55		Schedule 40 2" Mainline Sleeve		
		Schedule 40 PVC sleeve (2 x pipe diameter)		
		VALVE NUMBER		
	8 1 1/2"	■—VALVE SIZE		
	31.97 GPM	GPM		
	WIRE			
	12 Gauge	12 Gauge UL listed direct burial wire - ground		


# Notes:

1. Installation shall comply with all local codes

14 Gauge

2. In case of discrepancy between the plan and the materials list or specifications, the plan shall take precedence. The contractor is responsible for his own quantity takeoff. Quantities provided are approximate to be verified prior to bid.

- 3. The landscape contractor shall be aware of locations of all easements and utilities above and below ground and coordinate plant locations before digging operations begin.
- 4. Irrigation shall have a rainswitch, provide 100% coverage with head to head overlap.
- 5. Location of irrigation equipment is diagramatic. Piping and fixtures shall be located in landscape areas.
- 6. Heads located in groundcover or shrubs shall be on risers. See sheets L-1 and I-2.



14 Gauge UL listed direct burial wire - control

48 HOURS BEFORE DIGGING CALL TOLL FREE 1-800-432-4770 U.N.C.L.E. UNDERGROUND UTILITIES NOTIFICATION CENTER

**ELECTRICAL HAZARD** All work in the vicinity of overhead power lines shall comply with ANSI Z 133.1. Contact FPL before beginning work.

signature revision/date

Flow Radius

1.21

0.61

0.89 10

0.45 10

0.47 15

0.15 8

0.29

seal #LA 0001111

RRIGATION


11623 6/3/24

BUILDING METAL 6013 RODMAN STI Hollywood, Florida

sheet no.

PROVIDE A MINIMUM OF 12" BETWEEN SPRINKLERS AND BUILDINGS OR OTHER VERTICAL STRUCTURES.






PROVIDE A MINIMUM OF 12" BETWEEN SPRINKLERS AND BUILDINGS OR OTHER VERTICAL STRUCTURES.

SPRINKLER HEAD ON RISER


SHRUBS AND GROUNDCOVER



PROVIDE A MINIMUM OF 12" BETWEEN SPRINKLERS AND BUILDINGS OR OTHER VERTICAL STRUCTURES.

ROTOR POP-UP SPRINKLER





 $\left(\begin{array}{c} 5 \\ \hline 1-2 \end{array}\right)$ 

IRRIGATION SLEEVING


# **GENERAL NOTES:**


- The irrigation materials and installation shall
  meet all the standards of the Standards and Specifications for
  Turf and Landscape Irrigation Systems, lastest edition.
  published by the Florida Irrigation Society, the National Electric Code,
  and Appendix F of the Florida Building Code and such shall be
  incorporated herein by reference.
- 2. All mainline and lateral line piping and control wires under paving shall be installed in separate sleeves. Main and lateral line sleeves shall be a minimum twice (2x) the diameter of the pipe to be sleeved. Control wire sleeves shall be of sufficient size for the required number of wires under paving.
- 3. Pipe routed under pavement and sidewalks shall be sleeved in SCH 40 PVC. Contractor shall verify the size, depth and location of all existing sleeves. Pipe shall be installed so backfill depths are maintained at 18" for the main line and for laterals which are routed under pavement, and at 12" for all other laterals.
- Install all piping to the water meter per local codes.
- 5. Final location of the rain sensor and automatic controller shall be approved by the owner's authorized representative.
- 6. Electrical power source at pump and controller location shall be provided by others. The irrigation contractor shall make the final connection from the electrical source to the controller.
- 7. All sprinkler heads shall be set perpendicular to finish grade unless otherwise specified.
- 8. The irrigation contractor shall flush and adjust all sprinkler heads and valves for optimum coverage with minimal overspray onto walks, streets, walls, etc.
- 9. This design is diagrammatic. All piping, valves, etc., shown within paved areas is for design clarification only and shall be installed in planting areas wherever possible. The contractor shall locate all valves in shrub areas where possible.
- 10. It is the responsibility of the irrigation contractor to familiarize himself with all grade differences, location of walls, retaining walls, structures and utilities. The irrigation contractor shall repair or replace all items damaged by his work. He shall coordinate his work with other contractors for the location and installation of pipe sleeves through walls, under roadways, and paving, etc.
- 11. The contractor shall erect and maintain barricades, guards, warning signs and lights as required for the protection of the public and workmen. All work shall be performed in a safe manner. All regulations, all OSHA requirements and other authoritive agencies shall be followed.
- 12. The sprinkler system design is based upon on minimum system static pressure of 60 psi and a maximum flow of 19 gpm. The irrigation contractor shall verify water pressure and GPM. Report any difference between the water pressure indicated on the drawings and the actual pressure reading at the irrigation point of connection to the owner's authorized representative. The contractor shall pressure test the main line per the Standards and Specifications for Turf and Landscape Irrigation Systems, latest

13. Do not willfully install the sprinkler system as shown on the drawings when it is obvious in the field that unknown obstructions, grade differences or differences in the area dimensions exist that might not have been considered in the design. Such obstructions or differences shall be brought to the attention of the owner's authorized representative. In the event this notification is not performed the irrigation contractor shall assume full responsibility for any revisions necessary.

- 14. All sprinkler equipment not otherwise detailed or specified shall be installed as per manufacturer's recommendations and specifications.
- 15. Control lines from automatic controller to automatic valves shall be #14 AWG direct burial underground feed type with #12 ground which shall be (1) installed per local codes, (2) routed in the trench for mainline, (3) sleeved when routed under pavement, (4) buried to a minimum of 18 inches, and (5) color coded to facilitate troubleshooting.
- 16. The contractor shall provide pressure regulation as necessary to reduce or eliminate overspray onto streets, walks or other areas as directed by the owner's authorized representative.
- 17. All remote control valves, gate valves, quick couplers, contol wire and computer cable pull points shall be installed in approved valve boxes with locking covers. All shall be marked indicating controller and station numbers for control valve boxes and/or titled in the equipment legend with 1" white heat braided letters.
- 18. The contractor shall clean-up the site daily and as the work progresses.

  Any damage to the work of others shall be repaired to original conditions.
- The contractor shall guarantee for 1 year all irrigation materials and installation.





The controller shall be equipped to provide up to 22 stations

48 HOURS BEFORE DIGGING
CALL TOLL FREE

1-800-432-4770

U.N.C.L.E. UNDERGROUND UTILITIES
NOTIFICATION CENTER

6013 Rodman Street Hollywood, Florida

Copyright © 2024 by Peter DeWick. All Rights Reserved.

seal #LA 0001111

signature revision/date

gnature vision/date

ION DETAILS

tes | IRRIGATION

el. (954) 792-4023

socia

S

Wick

De

5 SW 23 Street -auderale, Florida

Dete:

our www.land-pl

12024 6/17/24

drawn by: checked by: phd

D
0


E METAL BUILD
IN STREET

orida

WAREHOUSE M 6013 RODMAN ST Hollywood, Florida


sheet no.

1-2



# TREE PRESERVATION NOTES:


- 1. These drawings are not valid without the signature and the original raised seal of the
- 2. This drawing is the property of Peter DeWick & Associates, RLA 0001111, and shall not be used or reproduced in whole or in part without written
- 4. All locations of existing trees are approximate and are to be used for the sole purpose of the proposed tree removal and preservation.
- 5. The Contractor shall comply with all regulations of the City of Hollywood regarding the disposal of debris resulting from the clearing and grubbing operation and any illegally dumped material. The contractor shall have the property line staked by a licensed professional land surveyor at appropriate stations to delineate the limits of work under this project. The Contractor shall obtain a tree removal permit prior to the work. 6. Any species located at the site which are considered an unprotected species by the City of Hollywood may be removed from the site.
  7. Property obstructions which are to remain in place, such as sewers, trees, drains, water, sewer, gas, or other utility pipes, cables, lawns, walks, pavements, and structures are
- to be carefully protected from injury and are not to be displaced. Any damage to these items will be repaired by the contractor at no cost to the owner.
- 8. Standard clearing and grubbing procedures shall be used and shall consist of the chipping, loading for removal of undesirable trees, shrubs, timber, brush, stumps, roots, grass weeds, sawdust, rubbish and other obstructions resting on or protruding through the surface of existing ground.
- 9. Any surplus materials shall be removed from the site and disposed of as directed by the owner at no cost.
- 10. Damage to remaining trees caused by the contractor shall be mitigated by the contractor at no cost to the owner.
- 11. Contractor shall protect trees listed to remain.
- 12. Trees to be removed shall be removed in full compliance with ANSI A300 and ANSI Z133.1. Trees or palms to be relocated shall be transplanted in compliance with ANSI A300 (part 6) Transplanting and shall be planted according to the details and specfications shown on sheet L-2. The minimum size of rootballs of palms to be relocated shall be in compliance with the Florida Number One Grade according to the Grades and Standards for Nursery Plants. 13. All trees and palms to remain shall be pruned in compliance with ANSI A300 (part1). Dead palm fronds shall be removed. The leaf bases (boots) of all Sabal Palms shall be trimmed to provide a neat appearance.
- 14. Stumps shall be removed to a depth of 12" minimum.
- 15. The applicant for a tree removal permit shall at the time of application designate an on-site representative who will be responsible for the installation and maintenance of vegetation protective barriers. The representative shall be responsible for supervising the removal of all existing vegetation permitted to be removed. The representative shall be on site at all times during the vegetation clearing operations. All land clearing and tree removal shall comply with the code of the City of Hollywood.




# **Tree Protection Detail**

Notes: Barricade existing trees adjacent to new construction. The contractor shall protect existing trees. Tree protection fence shall be installed no closer than the dripline of any tree to remain. Tree protection fences shall be erected prior to beginning clearing and grubbing and shall be maintained in a taut upright condition until the completion of the project and then removed at time of completion. Damage to existing trees caused by the contractor shall be mitigated by the contractor at no cost to the owner.

### TREE SYMBOL KEY



Tree Number	Scientific Name	Common Name	Inches DBH		Feet Spr.	Condition Rating	Proposed Disposition	Inches DBF Removed
1 2	Ficus aurea Swietenia mahogani	Strangler Fig Mahogany	48 23	50 40	58 40	good fair-poor	remain remove	23
					Tota	al inches remov	ed	23
						nopy replacements @ 12' ht., 2" I		12
					pro	placement trees vided @ 12' ht., noon Holly	2" DBH	4
					Re	placement trees vided to tree tru		8



48 HOURS BEFORE DIGGING CALL TOLL FREE 1-800-432-4770

U.N.C.L.E. UNDERGROUND UTILITIES NOTIFICATION CENTER

All work in the vicinity of overhead power lines shall comply with ANSI Z 133.1. Contact FPL before beginning work.

**ELECTRICAL HAZARD** 

project no.

sea....#ĽA 0,001111 STATE signature revision/date

> SITION O DISP

11623 5/11/23

BUILDING


WAREHOUSE META 6013 RODMAN STREET

sheet no.



CALCULATION SUMMARY										
Scenario: PARKING & DRIVEWAY	Scenario: PARKING & DRIVEWAY									
LABEL	CALC TYPE	UNITS	SPACING L-R (FT)	SPACING T-B (FT)	HEIGHT (FT)	AVG	MAX	MIN	AVG/MIN	MAX/MIN
NORTH EXIT	Illuminance	Fc	3	3	0	1.70	2.2	1.1	1.55	2.00
PARKING & DRIVEWAY	Illuminance	Fc	6	6	0	3.77	7.3	1.2	3.14	6.08
PROP_LINE	Illuminance	Fc	8	N.A.	N.A.	0.09	0.4	0.0	N.A.	N.A.
WALKWAY	Illuminance	Fc	3	3	0	2.39	5.9	1.0	2.39	5.90






	Туре	Manufacturer	Model#	Wattage	Voltage	Dimming	Accessories	Mounting	Comments
1	SURFACE MOUNTED LED SCONCE	BROWNLEE	7110-15-x-H16-40K	INTEGRAL 16W	120V / 277V	0-10V		SURFACE	*ADVISE FINISH
	SURFACE MOUNTED LED FLOOD	LITHONIA	WDGE1 LED P1 40K 80CRI VW MVOLT SRM PE *	INTEGRAL 10w LED	120V / 277V	0-10V		SURFACE	*ADVISE FINISH
	LED HIGHBAY	LITHONIA	CPHB 24000LM SEF GCL MD MVOLT GZ10 40K 80CRI LSXR6 ADC DWH	INTEGRAL 175W	120V / 277V	0-10V		SUSPENDED	
	LED HIGHBAY	LITHONIA	CPHB 9000LM SEF GCL MD MVOLT GZ10 40K 80CRI LSXR6 ADC DWH	INTEGRAL 61W	120V / 277V	0-10V		SUSPENDED	
	RECESSED 4-IN DIAM. ROUND LED DOWNLIGHT	LITHONIA	LDN4 35/15 LO4AR LSS MVOLT GZ10	INTEGRAL 18W	120V / 277V	0-10V		RECESSED	
	THERMOPLASTIC LED EXIT SIGN	LITHONIA	LHQM***	INTEGRAL 3.4W LED	120V / 277V	N/A		SELECT	*** = SELECT FINISH, RED OR GREEN, MOUNTING
SITE									5
	Туре	Manufacturer	Model#	Wattage	Voltage	Dimming	Accessories	Mounting	Comments
	LED POLE TOP MH: 20FT	LITHONIA	DSX1 LED P2 40K 80CRI T3LG	INTEGRAL 68w LED	120V / 277V	0-10V			
) owner / archite ) include remote ) include all elec ) length in inche	oltage transformer / ballast / power supply - contractor to verify compatibility with dimming lect to verify trim finish e power supply - contractor to verify compatibility with dimming system lectrical and mounting accessories, connectors, etc. es per plan re nominal: contractor to verify exact size prior to fabrication E ALL LIGHTING WITH POWER & LIGHTING SYSTEMS, INC.	system			,				Power & Syste Manufacturers Specific Innovative Specific 392 St Deerfield Bear phone (9) fax. (9)

4 SITE PHOTOMETRIC SCALE: 1"= 10'-0"




REVISION

8/1/24




METAL BUILDING WAREHOUSE


6013 RODMAN STREET HOLLYWOOD, FL 33023





CHECKED D.J.A. DATE **JULY, 2022** SCALE AS NOTED JOB. NO. **22-005** 


D.J.A.





















AISY J. ACEVEDO, CO Architect 2072 SW 72ND AVE DAVIE FL 33317 (954) 473-5252




WAREHOUSE METAL BUILDING

REET 33023

MA 00

RO ¥

6013 HOLL



DRAWN
D.J.A.

CHECKED
D.J.A.

DATE JULY, 2022

SCALE AS NOTED

JOB. NO. 22-005

PH-7

Page 1 of 13



May 15, 2024

Anthony Harrison 5250 Northwest 75 Avenue Lauderhill, Florida 33319 Via Email Only

Dear Mr. Harrison:

Re: Platting requirements for a parcel legally described as Lot 8, Block 4, "Beverly Park," according to the Plat thereof, as recorded in Plat Book 25, Page 44, of the Public Records of Broward County, Florida. This parcel is generally located on the north side of Rodman Street, between State Road 7/U.S. 441 and South 61 Avenue, in the City of Hollywood.

This letter is in response to your correspondence regarding the Broward County Land Use Plan's platting requirements for a proposed non-residential development on the above referenced parcel.

Planning Council staff has determined that replatting <u>would not be required</u> by Policy 2.13.1 of the Broward County Land Use Plan (BCLUP) for the proposed development, subject to compliance with any applicable Broward County Trafficways Plan requirement.

As per the criteria of Policy 2.13.1, replatting is required for the issuance of building permits when constructing a non-residential or unified residential development, unless all of the following conditions are met:

- a. The lot or parcel is smaller than 10 acres and is unrelated to any adjacent development;
- b. A majority of the lot or parcel has been specifically delineated in a recorded plat;
- c. All land within the lot or parcel which is necessary to comply with the County Trafficways Plan has been conveyed to the public by deed or easement; and
- d. The proposed development is in compliance with the applicable land development regulations.

The subject parcel is less than 10 acres (approximately 0.12 acres) and meets the specifically delineated requirement. This platting interpretation is subject to the municipality finding that the proposed development is unrelated to any adjacent development, as noted in "a." above.

Some jurisdictions may be more restrictive and require platting in more situations than the BCLUP. The City of Hollywood's platting requirements should be investigated.

#### Anthony Harrison May 15, 2024 Page Two

The contents of this letter are not a judgment as to whether this development proposal complies with State or local vehicular access provisions, the Broward County Trafficways Plan, permitted uses and densities, local zoning, the land development regulations of the municipality or the development review requirements of the BCLUP, including concurrency requirements.

If you have any additional questions concerning the BCLUP's platting requirements, please contact Huda Ashwas at your convenience.

Respectfully,

Barbara Blake Boy Executive Director

BBB:HHA

cc/email: George R. Keller, Jr., CPPT, City Manager

City of Hollywood

Andria Wingett, Director, Development Services

City of Hollywood





#### **Coastal Waste (Hollywood Service Area)**

**Derek DeMello** <a href="mailto:com/demello@coastalwasteinc.com/">demello@coastalwasteinc.com/</a>
To: "hnthony18@gmail.com" <a href="mailto:hnthony18@gmail.com/">hnthony18@gmail.com/</a>

Mon, Jul 8, 2024 at 4:55 PM

Hey Anthony,

As mentioned before, we are an authorize hauler for the city of Hollywood for both front end service and construction.

Our smallest container for residential/commercial are our 96 gal containers and for construction is our 10 YD roll off boxes.

Let me know if there is anything else I can do for you.

Thanks

# **Derek DeMello**Sales Executive



**P:** 954-947-4000 **M:** 954-422-7239 www.coastalwasteinc.com 1840 NW 33rd St, Pompano Beach, FL 33064





Notice: The information transmitted by this email is intended only for the person or entity to which it is addressed and may contain proprietary, business-confidential, and/or privileged material. If you are not the intended recipient of this email, please contact the sender, delete the email and do not disclose its contents.



#### **Coastal Waste (Hollywood Service Area)**

**Derek DeMello** <ddemello@coastalwasteinc.com>
To: "hnthony18@gmail.com" <hnthony18@gmail.com>

Mon, Jul 8, 2024 at 5:23 PM

Hey Anthony,

As mentioned before, we are an authorize hauler for the city of Hollywood for both front end service and construction.

Service Address: 6013 Rodman street Hollywood FL 33023.

[Quoted text hidden]



#### 6013 Rodman street architect adjusted plans

Chris Clinton < CClinton@hollywoodfl.org>
To: Anthony Harrison < anthony11317@gmail.com>
Cc: Marcy Hofle < MHofle@hollywoodfl.org>

Mon, Jul 8, 2024 at 12:03 PM

Good morning Mr. Harrison,

Thank you for your patience.

With (2) remote means of egress (both from the mezzanine and the building itself), the 50' common path of travel restriction is eliminated as it is only required when utilizing a single means of egress.

The way your building is presented above, I believe you will be in compliance with the NFPA Life Safety Code.

Thank you,

**Chris Clinton, CFPE** 

Fire Marshal/Division Chief

Hollywood Fire Rescue and Beach Safety

2741 Stirling Rd. (3<sup>rd</sup> floor)

Hollywood, FL 33312

Office: 954-967-4404

From: Anthony Harrison <anthony11317@gmail.com>

Sent: Monday, July 8, 2024 11:42 AM

To: Chris Clinton < CClinton@hollywoodfl.org>

Subject: [EXT]6013 Rodman street architect adjusted plans

You don't often get email from anthony11317@gmail.com. Learn why this is important

[Quoted text hidden]

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize

the sender and know the content is safe.

#### **Chris Clinton**

Fire Marshal/Division Chief City of Hollywood Fire Rescue and Beach Safety 2741 Stirling Rd.

P.O. Box 229045 Hollywood, FL 33312 Office: 954-967-4404

E-mail: CClinton@hollywoodfl.org



Notice: Florida has a broad public records law. All correspondence sent to the City of Hollywood via e-mail may be subject to disclosure as a matter of public record.

#### 2 attachments



METAL BLDG RODMAN ST.pdf 4568K



Fire comments tac meeting.pdf 147K



BOARD OF COUNTY COMMISSIONERS Public Works Department WATER AND WASTEWATER SERVICES (WWS) 2555 W. COPANS RD., POMPANO BEACH FL 33069 (954) 831-3250 FAX (954) 831-0789

#### HYDRANT FLOW AND PRESSURE TEST RESULTS

DATE: 05/28/2024 WORK ORDER: ----- Attn: Regina Bobo-Jackson

CUSTOMER NAME: Gator Engineering Associates, Inc.

ADDRESS: 11390 Temple Street Cooper City Florida 33330

PHONE #: 954-434-5905 FAX# 954-434-5904

LOCATION: 1130 South State Road 7, Southside Building on Rodman Street

Press. HYDRANT #1: PHR 35904901 LOGGER SN# 14209054 Flow HYDRANT #2: PHR 35904301 LOGGER SN# 14209053

HYDRANT #1	DATE	TIME	PRESSURE
STATIC	05/28/2024	10:28:35 AM	74.359 PSI
RESIDUAL	05/28/2024	10:40:10 AM	69.573 PSI

HYDRANT # 2	DATE	TIME	FLOW
FLOW One	05/28/2024	10:40:10 AM	414 GPM


Flow calculated with a discharge coefficient of .90

#### EQUIPMENT USED:

TELOGER model HPR-31 (Serial numbers listed above)

POLLARD DIFFUSER 2.5 in

A Service of Broward County Board of County Commissioners www.broward.org





#### Channel Plot 1:

		14209054 Pressure
	Time	Avg
602	5/28/2024 10:27:00 AM	72.137
603	5/28/2024 10:27:05 AM	72.845
604	5/28/2024 10:27:10 AM	74.042
605	5/28/2024 10:27:15 AM	73.651
606	5/28/2024 10:27:20 AM	74.09
607	5/28/2024 10:27:25 AM	72.967
608	5/28/2024 10:27:30 AM	74.237
609	5/28/2024 10:27:35 AM	74.188
610	5/28/2024 10:27:40 AM	73.455
611	5/28/2024 10:27:45 AM	73.846
612	5/28/2024 10:27:50 AM	74.115
613	5/28/2024 10:27:55 AM	73.504
614	5/28/2024 10:28:00 AM	73.7
615	5/28/2024 10:28:05 AM	72.967
616	5/28/2024 10:28:10 AM	75.018
617	5/28/2024 10:28:15 AM	73.919
618	5/28/2024 10:28:20 AM	73.358
619	5/28/2024 10:28:25 AM	73.114
620	5/28/2024 10:28:30 AM	74.53
621	5/28/2024 10:28:35 AM	74.359
622	5/28/2024 10:28:40 AM	74.164
623	5/28/2024 10:28:45 AM	74.774
624	5/28/2024 10:28:50 AM	74.481
625	5/28/2024 10:28:55 AM	73.504
626	5/28/2024 10:29:00 AM	73.48
627	5/28/2024 10:29:05 AM	73.431
628	5/28/2024 10:29:10 AM	73.651
629	5/28/2024 10:29:15 AM	73.895
630	5/28/2024 10:29:20 AM	74.017
631	5/28/2024 10:29:25 AM	74.481
632	5/28/2024 10:29:30 AM	74.921
633	5/28/2024 10:29:35 AM	74.261
634	5/28/2024 10:29:40 AM	74.212
635	5/28/2024 10:29:45 AM	74.53

#### Channel Plot 1:

	Time	14209054 Pressure
		Avg
744	5/28/2024 10:38:50 AM	68.23
745	5/28/2024 10:38:55 AM	68.4
746	5/28/2024 10:39:00 AM	68.816
747	5/28/2024 10:39:05 AM	68.376
748	5/28/2024 10:39:10 AM	68.62
749	5/28/2024 10:39:15 AM	68.498
750	5/28/2024 10:39:20 AM	68.962
751	5/28/2024 10:39:25 AM	68.718
752	5/28/2024 10:39:30 AM	68.376
753	5/28/2024 10:39:35 AM	68.571
754	5/28/2024 10:39:40 AM	68.571
755	5/28/2024 10:39:45 AM	68.498
756	5/28/2024 10:39:50 AM	67.79
757	5/28/2024 10:39:55 AM	69.768
758	5/28/2024 10:40:00 AM	69.402
759	5/28/2024 10:40:05 AM	68.547
760	5/28/2024 10:40:10 AM	69.573
761	5/28/2024 10:40:15 AM	69.524
762	5/28/2024 10:40:20 AM	68.987
763	5/28/2024 10:40:25 AM	69.109
764	5/28/2024 10:40:30 AM	69.939
765	5/28/2024 10:40:35 AM	70.061
766	5/28/2024 10:40:40 AM	70.501
767	5/28/2024 10:40:45 AM	68.889
768	5/28/2024 10:40:50 AM	68.938
769	5/28/2024 10:40:55 AM	68.767
770	5/28/2024 10:41:00 AM	69.182
771	5/28/2024 10:41:05 AM	69.451
772	5/28/2024 10:41:10 AM	68.156
773	5/28/2024 10:41:15 AM	68.718
774	5/28/2024 10:41:20 AM	68.767
775	5/28/2024 10:41:25 AM	68.962
776	5/28/2024 10:41:30 AM	68.352
777	5/28/2024 10:41:35 AM	68.474
	·	





#### Channel Plot 1:

	Time	14209053 Pressure Flow Rate
712	5/28/2024 10:38:50 AM	412.4
713	5/28/2024 10:38:55 AM	339.4
714	5/28/2024 10:39:00 AM	372.2
715	5/28/2024 10:39:05 AM	370.5
716	5/28/2024 10:39:10 AM	314.0
717	5/28/2024 10:39:15 AM	367.7
718	5/28/2024 10:39:20 AM	377.2
719	5/28/2024 10:39:25 AM	373.8
720	5/28/2024 10:39:30 AM	408.4
721	5/28/2024 10:39:35 AM	388.6
722	5/28/2024 10:39:40 AM	401.7
723	5/28/2024 10:39:45 AM	348.5
724	5/28/2024 10:39:50 AM	389.1
725	5/28/2024 10:39:55 AM	281.9
726	5/28/2024 10:40:00 AM	404.8
727	5/28/2024 10:40:05 AM	405.3
728	5/28/2024 10:40:10 AM	414.0
729	5/28/2024 10:40:15 AM	373.3
730	5/28/2024 10:40:20 AM	340.6
731	5/28/2024 10:40:25 AM	381.0
732	5/28/2024 10:40:30 AM	408.9
733	5/28/2024 10:40:35 AM	382.6
734	5/28/2024 10:40:40 AM	369.9
735	5/28/2024 10:40:45 AM	359.1
736	5/28/2024 10:40:50 AM	359.7
737	5/28/2024 10:40:55 AM	387.5
738	5/28/2024 10:41:00 AM	389.6
739	5/28/2024 10:41:05 AM	372.2
740	5/28/2024 10:41:10 AM	418.0
741	5/28/2024 10:41:15 AM	389.1
742	5/28/2024 10:41:20 AM	410.9
743	5/28/2024 10:41:25 AM	352.1
744	5/28/2024 10:41:30 AM	373.3
745	5/28/2024 10:41:35 AM	379.9



royd by: Date received

MAY 2 2 2024




Public Works Department
Water and Wastewater Services/Fiscal Operations
2555 West Copans Road • Pompano Beach, Florida 33069 • 954-831-3250 • FAX 954-831-0789

# FIRE HYDRANT/PRESSURE & FLOW TEST APPLICATION Instructions:

Complete the following and indicate service required by placing a check mark in the appropriate square. Sign, date, and return to WWS along with payment.

(1) APPLICATION FOR:	
24-Hour Pressure Test with Chart Reading\$15	0.00
Pressure and Flow Test including 24 hour chart recording\$20	0.00
Tapping into Main (if necessary to accomplish any of the above, in addition to all o	other
charges)\$300.00	
(2) APPLICANT NAME: Regina Bobo-Jackson	_
Contact Person	
(3) COMPANY NAME: Gator Engineering Associates, Inc.	<u> </u>
(4) MAILING ADDRESS: 11390 Temple Street, Cooper City, FL 33330	
Number and Street	
(5) LOCATION ADDRESS: 1130 S State Road 7. southside of building on Rodman Street	· <del></del>
Necessary in order to process accurately	
(6) PHONE NO: (954) 434-5905 FAX NO: (954) 434-5904	_
(7) E-MAIL ADDRESS: gator_ec@bellsouth.net  (8) SIGNATURE:	
(8) SIGNATURE: DATE:	
Allow a maximum of ten (10) working days to be notified of results of test(s).  Customer is contacted by phone.  PLEASE MAIL CHECK AND APPLICATION TO:	RCV'D BY:
WWS PO Box 669300 Pompano Beach, FL 33066-9300  MAKE CHECKS PAYABLE TO: WWS	DATE RECEIVED

MAY 23 2024



100ft