



Greenfields Outdoor Fitness, Inc

2617 West Woodland Drive

Anaheim, CA 92801

Phone: 888-315-9037

Fax: 866-308-9719

Email: orders@greenfieldsfitness.com

Estimate

Order #	Date
S30702	09/28/2025

**Bill To:**

FL - Hollywood - Young Circle Arts Park
City of Hollywood
1405 S. 28th Ave
Hollywood, FL 33020

Customer: FL - Hollywood - Young Circle Arts Park

Ship To:

FL - Hollywood - Young Circle Arts Park
City of Hollywood
Young Circle Arts Park
1 N Young Circle
Hollywood, FL 33020

Contact: FL - Hollywood - Young Circle

Sales Rep	Payment Terms	FOB Point	Carrier	Date Scheduled
SM	50% Deposit/ Balance	Origin	Freight	09/28/2025

Item

#	Number	Description	Color	Unit Price	Qty	Total Price
1	Sourcewell Contract #	Sourcewell Contract# 010721-GRN City of Hollywood FL Sourcewell Member ID#39548		\$0.00	1 ea	\$ 0.00
2		SURFACE MOUNT INSTALLATION METHOD DESIGN V7 Rev1 - 2025-09-25 With Colored Concrete Pad				
3	Shade	Custom Sails consisting of (8) columns and (6) fabric canopies per attached drawing dated 10/11/2023 - Pier Mounted Columns Florida Professional Engineer Sealed Drawings & Calculations - INCLUDED Shipping / Handling Charge to Hollywood, FL 33020 - INCLUCED		\$69,861.00	1 ea	\$ 69,861.00



Estimate

Greenfields Outdoor Fitness, Inc

2617 West Woodland Drive
 Anaheim, CA 92801
 Phone: 888-315-9037
 Fax: 866-308-9719
 Email: orders@greenfieldsfitness.com

Order #	Date
S30702	09/28/2025



Item

#	Number	Description	Color	Unit Price	Qty	Total Price
4	Installation	Installation Scope of Wok - PIP over Concrete - SM installation with Color Concrete Pad GENERAL (\$22,903.40) - Permitting Process - Structural Engineering for Concrete Slab and Fitness Equipment - Portable Toilet - Construction Fence - Dumpsters - Off-loading and staging at the site - Sod Restoration at the end of the project SITE WORK (\$118,583.40) - Site prep 6" dispose and haul off (1440 sq/ft) - Site Prep 8" Dispose and Haul off (1446 sq/ft) - Concrete Curb 8x6 with Fiber Mesh - PIP surfacing 4" Thick 1446 sq/ft, PIP Surfacing 2" Thick 1440 s/f - 50% Black/50% Beige - Sod Restoration - Concrete Sidewalk 4" Thick (100 sq/ft) - 4" 57 Aggregate over Geotextile Fabric SHADE INSTALL (\$30,498.00) - Erect Shade Sails & Columns (8) - Crane CONCRETE FOUNDATIONS (\$62,461.10): - Concrete foundations excavation - Concrete 3000 psi - Rebar Cages - Anchor Bolts FITNESS EQUIPMENT (\$55,298.50) - Surface Mout installation of 10 units + very large Functional Fitness Rig - Assembly at the site as needed - Disposal of all packaging & crates EXCLUDED: - Tree & Stump Removal - Site Survey - Irrigation relocation - De-Mucking - All testing	N/A	\$289,744.40	1 ea	\$ 289,744.40
5		Subtotal				\$ 359,605.40



Greenfields Outdoor Fitness, Inc

2617 West Woodland Drive

Anaheim, CA 92801

Phone: 888-315-9037

Fax: 866-308-9719

Email: orders@greenfieldsfitness.com

Estimate

Order #	Date
S30702	09/28/2025



Item

#	Number	Description	Color	Unit Price	Qty	Total Price
6	Sourcewell Member Discount	Sourcewell Member Discount 7%; Sourcewell Members Discount applies to members direct purchases only and will not be extended to third parties				-\$ 25,172.38

CUSTOMER APPROVAL: I hereby declare that I am authorized to approve this order. By signing below, I approve the items selection, color selection and quantities. I understand that the units listed here are made specifically for this order and cannot be returned or cancel once production begins. I agree that should collection of this agreement become necessary, I will cover all collection costs and legal fees. I authorize Greenfields to ship this order and process payment as outlined on this confirmation.

Approval signature: _____ Date: _____

Print Name: _____

Subtotal:	\$334,433.02
Sales Tax:	\$0.00
Total:	\$334,433.02