



PROPOSAL

City of Hollywood WWTP
1621 N. 14th Avenue
Hollywood, FL 33022-9045
Attn: Steve Farrell

DATE: 7/19/2018
DELIVERY: 32-34 weeks ARO
FREIGHT TERMS: Prepaid
PAYMENT TERMS: Net 30
VALIDITY: 30 days from date
TERMS AND CONDITIONS: Solutionwerks' standard terms of Sale will apply.

Proposal Number: Q316-18200
Heat Exchanger

Ite...	Qty	UOM	Description	Unit Cost	Total
1	1	Each	<p>Furnish Reboiler-Condenser Heat Exchanger for cryogenic oxygen plant</p> <p>Brazed aluminum construction</p> <p>Cleaned for oxygen service</p> <p>Number of passages: one each for oxygen and nitrogen (two total)</p> <p>Size: 25" x 41" x 62"</p> <p>The equipment and pricing quoted above are based on the following:</p> <p>A. This exchanger will be designed and constructed to the ASME Code Section VIII Div. 1 by Chart Industries.</p> <p>B. This exchanger will be manufactured according to Chart standards, as well as the standards set forth by ALPEMA. This exchanger will be pneumatically testing (1.1 x design pressure) as required by Chart standards and the current ASME Code.</p> <p>C. This is replacement equipment. The original design will be updated using Chart's current manufacturing standards and unified fins/components. The equipment will meet or exceed the thermal and hydraulic performance of the original equipment. In addition, all original connection and support locations will be maintained.</p> <p>D. This exchanger will be charged with dry air for shipping.</p>	105,570.00	105,570.00
2	1	Lot	Freight	8,107.50	8,107.50
Subtotal:			\$113,677.50	Sales Tax: (0.0%)	\$0.00
Total:					\$113,677.50