



900 Broken Sound Pkwy  
Suite 175  
Boca Raton, FL 33487  
(561) 392-3667

## EXHIBIT 1

City of Hollywood

Project Name: Petroleum Independence and Lower Emission with E85

Project Scope:

Convert 2 of the 4 existing dispensers currently on the fuel island to dispense Flex Fuel/E85 fuel. Convert existing tank to handle and store Flex Fuel/E85 fuel. Program existing pedestal and fuel management system to include Flex Fuel/E85 Fuel as a fuel option.

2) Convert existing Bennett dispensers to Flex Fuel/E85 Fuel compliance.

- 1) Clean and inspect existing tank for introduction of E85 fuel application
- 1) Clean and purge fuel pipe lines for introduction of E85 fuel application
- 1) 3/4HP STP motor in tank
- 1) Mechanical Leak Detector
- 1) Install new tank probe
- 1) STP controller relay switch
- 1) 32" STP sump
- 1) Overfill Drop Tube
- 1) Fill Pipe cover for fuel identification
- 4) Hoses, nozzles, swivels, breakaways for E85 fuel
- 4) Decals for Dispenser labeling and identification
- 1) Start up equipment and test
- 1) Clean up site from debris

Protec Fuel will be using certified PEI (Petroleum Equipment Licensed) sub-contractors for this project.

Petro Solutions

5200 NW 77<sup>th</sup> Court, Doral, FL 33166

Petro Solutions will convert and install components needed for tank, pump, probe and testing of equipment.

Petro Solutions is the preferred contractor for Protec Fuel in Southern Florida. Together, Petro Solutions and Protec Fuel have completed 100+ station site projects handling Flex Fuel/E85 Fuel on similar scope projects. From Sunoco, UGas, Orion, Marathon, Texaco, Petro Solutions has managed very similar project scopes.

Action Petroleum Inc.

211 SW 77<sup>th</sup> Way, Pembroke Pines, FL 33024

Action Petroleum is the local Bennett certified distributor in South Florida. Action Petroleum just completed a similar project with Protec Fuel and will coordinate conversion and testing the completed dispenser installations.

There will be a 1 year warranty of parts and equipment installed for Flex Fuel/E85 Fuel used in this project application. Approximately 3 weeks after project is completed, Petro Solutions will return to the station site to re-inspect and check the Flex Fuel/E85 fueling system and conversion. Additionally, new filters will be installed in each dispenser as precautionary measure.

