



MBF Industries, Inc.

210 Tech Drive
Sanford, FL 32771

www.MBFIndustries.com

P:407-323-9414
F:407-330-2068

Quote# Q-2025-35

Customer	Hollywood PD (1125/09)	Date Issued	9/9/2025	Quote Expires	30DAYS	P-1	
Issue / Work to be Done	Engineering	Labor	Materials	Total	Qty	Materials required	
Take pictures of entire truck. Remove, test and catalog all equipment / items in truck before work begins. Then box / palletize those items.	\$0.00	\$1,050.00	\$0.00	\$1,050.00	1 1 1	Take pictures of entire truck Test all / Take notes of what doesn't work Box up / Palletize any reused or items going back to the client	
Remove all countertops Install new countertops (Hard surface) Remove all interior electrical (switches/outlets) Install new interior outlets (USB outlets where needed) Remove all cabinets Build / Install new cabinets w/ whiteboard doors Remove/ rebuild conference table with Pop-up outlets/ Data	\$0.00	\$26,700.00	\$16,335.00	\$43,035.00	3 4 1 1 1 1 1 1 2	Remove countertops Install new (Hard Surface) countertops (Add new where bathroom is) Remove interior electrical (Outlets/ switches) Install new interior electrical (Outlets/ switches) Remove all cabinets Install new cabinets w/whiteboard faces Remove/ rebuild conference table Power/ Data pop-ups	
Remove all old wood trim Install new upholstery trim Remove all carpet Install new carpet Remove all wall/ ceiling panels Install wall/ new ceiling panels	\$0.00	\$33,000.00	\$7,256.25	\$40,256.25	1 1 1 1	Remove old trim- wood trim/ Install new trim Remove/ Install new carpet Remove/ Install new ceiling Remove/ Install new wall panels	
Remove all flooring Fix any/ all soft floor issues Install new flooring	\$0.00	\$7,200.00	\$3,982.50	\$11,182.50	1 1 1	Remove old flooring/ Prep for new Install new flooring Fix any floor issues	
Remove old Rack Install new style Rack w/Door	\$0.00	\$1,800.00	\$3,375.00	\$5,175.00	1 1	Remove old Rack Install (1) new style Rack	
Remove Fridge - Microwave - Coffee maker Install new Fridge - Microwave - Coffee maker	\$0.00	\$600.00	\$3,375.00	\$3,975.00	1 1 1 1	Remove Fridge - Microwave - Coffee maker Install new Fridge Microwave Coffee Maker	
Remove old electric toilet Remove all bathroom walls and cabinets Patch roof where vent is Build new storage and countertops Install gun locker (36"W X 44"H X 15.25"D)	\$0.00	\$1,200.00	\$2,970.00	\$4,170.00	1 1 1 1	Remove toilet/ Roof vents/ Remove all bathroom walls/ door Patch roof at vents SECURELT TACTICAL Install lockable gun safe for hand guns and rifles	
Remove all Awnings Install new body and slide-out awnings	\$0.00	\$1,800.00	\$3,915.00	\$5,715.00	1 1 1 2	Remove old Awning (Body- Slide-outs) Install new Awning Body (145") Slide-out (145")	
Remove all heaters	\$0.00	\$150.00	\$0.00	\$150.00	2 2	Remove all wall/ toe kick heaters Remove AC power	
Remove old Loadcenter panel / Install new Loadcenter panel Remove/ Install new Loadcenter breakers - Meter - Transfer switch	\$450.00	\$2,700.00	\$6,015.60	\$9,165.60	1 1 38 1 1	Remove Loadcenter Panel (pictures/ labels) Install new Loadcenter panel (New design) Breakers Meter Transfer switch (80A)	
	Engineering P.1 @ \$225 Hr.		2	\$450.00			**NOTES:** - If payment is made with a credit card, a 3% surcharge will be added to the total. - If you will be using a Purchase Order (PO) or Work Order (WO), please provide that information. - A 3% surcharge will also be applied to the total for any work done at MBF for miscellaneous shop supplies. - If applicable, please provide a tax-exempt form. - Please note that the quote may need to be adjusted if any unforeseen paint, body, or electrical issues are discovered after MBF receives the vehicle. - Shipping prices are subject to change after the item has shipped.
	Labor P.1 @ \$150 Hr.		508	\$76,200.00			
	Materials P.1			\$47,224.35			
	Total P.1			\$123,874.35			
				\$0.00			
				\$0.00			
				\$0.00			
	QUOTE TOTAL PAGE 1			\$123,874.35			

SIGNATURE _____ DATE _____



MBF Industries, Inc.

210 Tech Drive
Sanford, FL 32771

www.MBFIndustries.com

P:407-323-9414
F:407-330-2068

Quote# Q-2025-35

Customer	Hollywood PD		Date Issued	9/9/2025	Quote Expires	30DAYS	P-2	
Issue / Work to be Done	Engineering	Labor	Materials	Total	Qty	Materials required		
Remove all exterior Gaskets Doors - Slide-outs gaskets Install all new Gaskets Doors - Slide-outs gaskets	\$0.00	\$8,100.00	\$2,281.50	\$10,381.50	1 290 240	Remove all Gaskets- Clean old glue off and prep for new Install new Door Gasket (Jamb/ Door) (Per foot) Install new Slide-out gaskets (Inner/ Outer/ Exterior) (Per foot)		
Remove old Jack System/ Install new Jack system Install new Slide out system Add Jack Pads	\$0.00	\$6,750.00	\$8,505.00	\$15,255.00	1 1 4 2	Remove old Jacks Install new Jack system -Quadra Manufacturing 17,000lb legs & Pumps New holes may/will need to be drilled Jack pads (sold in pairs) Hoses/ ATF		
Remove all old exterior lights Scenes- Emergency - Lightbar- Marker lights/ Tail lights w/ new housings/ Siren/Emergency light controller Install all new exterior lights Delete lightbar, install ION light on front antenna mount(used as a lightbar) ALL WHELEN	\$0.00	\$5,850.00	\$13,506.75	\$19,356.75	1 1 8 16 1 10 9 2	Shipping Remove old scene Lights/ Emergency Lights/ Lightbar/ Siren-Emerg. Control Install new scene light (new wires needed) Install new Emergency Lights (RED-BLUE) Install LED Beacon on Mast (Green) Install new ION on front antenna box (Delete lightbar/fill holes) Marker lights Tail light w/ housing		
Remove old Back-up camera system Install new 360 camera system	\$0.00	\$1,350.00	\$2,565.00	\$3,915.00	1 1	Siren- Light control/ Siren Speaker Remove old Back-up Camera system Install new 360 camera system		
Remove old AC's Install new AC's Add(1) AC to rear room (non-ducted) Build install branch breakers for AC's	\$0.00	\$7,500.00	\$9,450.00	\$16,950.00	3 4 4 4	Remove old AC's Install new AC's Dometic 15,000 BTU New TSTAT-ceiling packs One AC is a new added to rear room-cut/ modify ceiling/ roof -This unit is not ducted Build/ Install branch breakers		
Remove all old interior lighting Install new 8" 3" round 12vdc led interior lighting Add light switches/ Dimmers where needed	\$0.00	\$4,950.00	\$2,592.00	\$7,542.00	1 1 8 14	Remove old Interior lights Install new interior lights/ Run new wires/ add wall switches & dimmers 3" LED lights 8" LED lights		
Remove old Slide-out cylinders (4-Rear) Install new Slide-out cylinders Replace Slide-out air control system NOTE= This isn't needed if Slide-out are working properly, older one will start leaking at some point.	\$0.00	\$2,700.00	\$15,390.00	\$18,090.00	1 2 2 1	Remove old cylinders/ Install new 24" Travel 38" Travel Remove old Slide-out controls/ Install new controls		
Remove all old compartment door struts Install new struts Install dampers on Flip-step Remove old compartment lights/ Install new LED lights Remove/ Replace all compartment door switches	\$0.00	\$1,050.00	\$864.00	\$1,914.00	18 2 1 11	Remove old struts/ Install new Install Dampers on Flip-down step Remove old compartment lights Install new LED compartment lights		
Build/ Paint/ Install a Ladder cover	\$0.00	\$750.00	\$1,518.75	\$2,268.75	1	Build/ Install a Ladder cover Paint		
Build/ Paint/ Install new Mast head for a 2 Camera system	\$225.00	\$1,800.00	\$1,417.50	\$3,442.50	1	Design/ Build/ Install new Mast head Paint		
	Engineering P.2 @\$225 Hr.		1	\$225.00		**NOTES:** - If payment is made with a credit card, a 3% surcharge will be added to the total. - If you will be using a Purchase Order (PO) or Work Order (WO), please provide that information. - A 3% surcharge will also be applied to the total for any work done at MBF for miscellaneous shop supplies. - If applicable, please provide a tax-exempt form. - Please note that the quote may need to be adjusted if any unforeseen paint, body, or electrical issues are discovered after MBF receives the vehicle. - Shipping prices are subject to change after the item has shipped.		
	Labor P.2 @\$150 Hr.		272	\$40,800.00				
	Materials P.2			\$58,090.50				
	Total P.2			\$99,115.50				
				\$0.00				
				\$0.00				
				\$0.00				
	QUOTE TOTAL PAGE 2			\$99,115.50				

SIGNATURE _____ DATE _____



MBF Industries, Inc.

210 Tech Drive
Sanford, FL 32771

www.MBFIndustries.com

P:407-323-9414
F:407-330-2068

Quote# Q-2025-35

Customer	Hollywood PD		Date Issued	9/9/2025	Quote Expires	30DAYS	P-3	
Issue / Work to be Done	Engineering	Labor	Materials	Total	Qty	Materials required		
BATTERY COMPARTMENT Remove Breakers Battery Separator, AUX Battery, Battery Charger Install all new components	\$0.00	\$1,950.00	\$3,240.00	\$5,190.00	1 8 1 1 1 1	Remove all 12vdc components in exterior battery compartment Install new components/ wires where needed Breakers Battery Separator AUX. Battery (One 8DAGM like new truck) Batter Charger (Only need one) AUX. Battery disconnect switch AUX. Switch at cab dash (like new truck)		
Remove old Generator Install new 20kw Generator Install new battery cables Install new fuel lines Add door fan (1)	\$0.00	\$3,600.00	\$27,303.75	\$30,903.75	1 1	Remove old Generator Install new Generator New feed/ return fuel lines New battery cables Add door fan/ relay/ wire/ breaker		
Remove old Lighttower Install new Lighttower	\$0.00	\$2,100.00	\$25,650.00	\$27,750.00	1 1	Remove old Lighttower Install new Lighttower Command Light KL415A-W2-BL		
Remove old Shore Cord Install new Shore power cord Remove old Surge protector Install new Surge protector	\$0.00	\$1,800.00	\$1,890.00	\$3,690.00	1 1 1 1	Remove old shore cord/ connector Install new Shore cord Male connector Remove old Surge Protector Install new Surge Protector		
Install Ground lights	\$0.00	\$2,100.00	\$945.00	\$3,045.00	10 10	Install Whelen 3" round LED Ground Lights Brackets Wires/ Switch/ Relay		
Remove/ Install new Stainless steel trim on exterior of truck Add front corner Stone Guards	\$0.00	\$1,950.00	\$351.00	\$2,301.00	1 1 2	Remove all S/S trim Cut/ Install new trim Add front Stone Guards		
Replace all exterior outlets Replace all interior outlets Remove all interior 12vdc outlets	\$0.00	\$750.00	\$810.00	\$1,560.00	1 4 8	Remove all (4) exterior outlets/ (2) 20A twist locks Install new exterior outlets/ 20A twist lock USB charging outlets Remove interior 12VDC outlets (not needed)		
Remove old Mast Install new Mast Remove all old Mast controls Install new Mast controls Build new Mast head for 2 cameras	\$0.00	\$10,050.00	\$27,405.00	\$37,455.00	1 1 1 1 1 1 1	Remove Mast Install new Mast Wil-Burt 42' Mast w/Shipping 3- Way valve Wil-Burt Mast compressor system/ run new air lines Build Mast Head Paint- Mast mounts/ Mast head Nycoil		
Add grab handle to the entry door Install new smaller grab handle Make new flip-step handrail Install new threshold and non-skid at entry door	\$0.00	\$900.00	\$364.50	\$1,264.50	1 1 1 1	Add (1q) grab handle to entry door (add plate in door) Install new (sm) handle to entry door Make new flip-step removable handrail Remove old entry door threshold/ install new w/ non-skid		
Remove old & pin trailer connector Install new 7 pin	\$0.00	\$300.00	\$20.25	\$320.25	1 1	Remove old damaged 7 pin trailer hook-up Install new 7 pin (mount into body)		
Engineering P.3 @ \$225 Hr.			0	\$0.00	**NOTES:** - If payment is made with a credit card, a 3% surcharge will be added to the total. - If you will be using a Purchase Order (PO) or Work Order (WO), please provide that information. - A 3% surcharge will also be applied to the total for any work done at MBF for miscellaneous shop supplies. - If applicable, please provide a tax-exempt form. - Please note that the quote may need to be adjusted if any unforeseen paint, body, or electrical issues are discovered after MBF receives the vehicle. - Shipping prices are subject to change after the item has shipped.			
Labor P.3 @ \$150 Hr.			170	\$25,500.00				
Materials P.3				\$87,979.50				
Total P.3				\$113,479.50				
				\$0.00				
				\$0.00				
QUOTE TOTAL PAGE 3				\$113,479.50				

SIGNATURE _____ DATE _____



MBF Industries, Inc.

210 Tech Drive
Sanford, FL 32771

www.MBFIndustries.com

P:407-323-9414
F:407-330-2068

Quote# Q-2025-35

Customer	Hollywood PD		Date Issued	9/9/2025	Quote Expires	30DAYS	P-4	
Issue / Work to be Done	Engineering	Labor	Materials	Total	Qty	Materials required		
Remove old Trac Star antenna Install SuperGIG antenna NOTE =Removal/ Install only- SuperGIG costing is in the Integration package	\$0.00	\$450.00	\$0.00	\$450.00	1 1	Remove old Trac Star antenna Install SuperGIG antenna		
Remove old Dash radio/ speakers Install new Radio/ speakers Add (3) cameras to look at Jacks/ Height clearance to be viewed on radio	\$0.00	\$2,100.00	\$2,416.50	\$4,516.50	1 1 1 1	Install new cab radio with GPS -Kenwood DNX997XR -install new dash speakers -add roof /jack cameras (3 cameras) Install mount Antenna adaptor Wire harness		
Remove/ Replace rear bumper diamond plate with new Spray bed liner type non-skid on flip-down steps/ cab steps	\$0.00	\$3,000.00	\$337.50	\$3,337.50	1 1 1	Remove rear DP bumper cover Install new DP bumper cover Spray Flip-down steps/ cab steps		
New roll chairs	\$0.00	\$300.00	\$1,856.25	\$2,156.25	11	New roll chairs (no arms)		
	\$0.00	\$0.00	\$0.00	\$0.00				
	\$0.00	\$0.00	\$0.00	\$0.00				
Take to Freightliner to install new LED headlights/ new Air ride seats(2)	\$0.00	\$300.00	\$7,250.00	\$7,550.00	1 1 1	Take to/ from Freightliner Quote from Freightliner to do the work Add (2) new Airride seats (\$3,650) Install LED head lights (\$3,100)		
Integration Items See line items list	\$1,800.00	\$48,000.00	\$112,494.89	\$162,294.89	1 1	Integration items Labor		
Page 1-2-3 total with labor	\$0.00	\$0.00	\$336,469.35	\$336,469.35	1 1 1	Page 1= (\$123,874.35) Page 2= (\$99,115.50) Page 3= (\$113,479.50)		
10% of total for unknown issues, price increases and added items	\$0.00	\$0.00	\$51,677.45	\$51,677.45	1	Unknown issues, price increases and added items		

Engineering P.4 @\$225 Hr.	8	\$1,800.00
Labor P.4 @\$150 Hr.	361	\$54,150.00
Materials P.4		\$176,032.59
Total P.4		\$231,982.59
2% Misc. Shop supplies/Clean-up		\$11,369.04
TAX		\$0.00
3% Credit Card Fee		\$0.00
QUOTE TOTAL ALL PAGES		\$579,820.98

****NOTES****

- If payment is made with a credit card, a 3% surcharge will be added to the total.
- If you will be using a Purchase Order (PO) or Work Order (WO), please provide that information.
- A 3% surcharge will also be applied to the total for any work done at MBF for miscellaneous shop supplies.
- If applicable, please provide a tax-exempt form.
- Please note that the quote may need to be adjusted if any unforeseen paint, body, or electrical issues are discovered after MBF receives the vehicle.
- Shipping prices are subject to change after the item has shipped.

SIGNATURE _____ DATE _____