

City of Hollywood
Polk Street Boat Ramp
On-Site Improvements
19-0005-001-01

GMP Proposal
September 5, 2019



TABLE OF CONTENTS:



Section 1: Introduction

Section 2: Qualifications

Section 3: GMP Proposal

Section 4: Phasing/Staging Plan

Section 5: Project Schedule

Section 6: Contract Drawings

Section 7: Bidders List and Bid Advertisement

Section 8: Clarifications and Addenda



Introduction:

SCEC has compiled our GMP for the following project:

City of Hollywood
Polk Street Boat Ramp
On-Site Improvements
19-0005-001-01

Our overall GMP cost is included in Section 2.

The GMP is based on schedule shown in Section 5. This includes revisions to project that remove structural components and seawall restoration.



SECTION 2: QUALIFICATIONS



Qualifications:

The following outlines the documents and general qualifications of our GMP proposal.

Bid Documents as follows:

Permit Plans prepared by Craven Thompson and Associates, Inc. Qualifications and exclusions expressed or stated by SCEC in this document take precedence over the documents.

Division 01- GENERAL:

1. Cost proposal is based on one mobilization.
2. Cost estimate does not include Builders Risk or Professional Liability Insurance.
3. Cost estimate does not include any permit fees, capital improvement fees, connection fees or impact fees.
4. No ADA improvements outside the scope of work shown on the plans are included, including modification of handrails, doors, hardware, etc.
5. SCEC will utilize water and power sources on the existing park with no sub-metering or utility consumption fees.

Pricing:

1. Pricing is based on plan revision 6 which eliminates all seawall work. (structural plans)
2. Pricing includes dewatering but excludes well point if required.
3. Pricing excludes bonding of trees – noted on plan sheet TD.
4. City of Hollywood will be responsible for all temporary water for establishment of new landscape and relocated trees.
5. Boat Ramp mats is based on detail provided by manufacturer – attached within.



GMP Proposal:

See attached documents as follows:

1. GMP Estimate Summary
2. General Conditions Detail
3. Bid Tabulation by CSI Division

City of Hollywood Boat Ramp

ESTIMATE NO./REF. SCEC2019.07.19
 TIME TO COMPLETE (days): 150
 PROJECT NUMBER: 19-0003-001-01
 LOCATION/OWNER: Broward County
 BID DATE: 7.19.2019

1	2	3	4	5	6	7	8	9	10
Div. No.	CSI Cost Code	Bid Package	Description of Work	Bid Amount	Name of Bidder	Number Bids	% Low	Cost Per SF	MWBE
Division 01 - General Requirements									
01	01 00 00	01100	✓ General Conditions	98,035	SCEC	-	-	-	-
01	-	01450	✓ Testing Services	1	In GC	-	-	-	-
01	-	00360	✓ Permits	1	by City	-	-	-	-
01	-	02210	✓ GPR Survey	1,600	Blood Hound	1	-	-	-
Division 02 - Existing Conditions									
02	02 40 00	02220	✓ Site Demolition/Tree Clearing	1	w/Earthwork	1	-	-	-
02	-	-	✓ Misc Patching / Site Restoration	2,795	SCEC	1	-	-	-
02	-	-	✓ Protection/Pedestrian Control/MOT	1,800	SCEC	1	-	-	-
Division 03 - Concrete									
03	03 30 00	03300	✓ Concrete Retaining Wall	1	w/Boat Ramp	1	-	-	-
Division 10 - Specialties									
10	10 14 00	10400	✓ Signage	14,500	Allowance	1	-	-	-
Division 12 - Furnishings									
12	12 61 00	12710	✓ Benches	1	None	1	-	-	-
Division 26 - Electrical									
26	26 00 00	16050	✓ Electrical	81,858	Just Electric	2	40.60%	-	-
Division 31 - Earthwork									
31	31 00 00	02300	✓ Earthwork, Paving, Striping, Drainage	177,816	Stanford	2	4.71%	-	-
31	31 10 00	02370	✓ Erosion & Sedimentation Controls	10,576	Estimate	3	2.53%	-	-
31	31 00 00	02360	✓ Termite Control - Soil Treatment	1	None	1	-	-	-
Division 32 - Exterior Improvements									
32	32 10 00	02370	✓ Concrete Paving	34,807	Cobra	4	11.72%	-	-
32	32 00 00	02780	✓ Brick Unit Pavers	1	None	1	-	-	-
32	32 00 00	02820	✓ Fence & Gate	7,450	Tropic	2	3.87%	-	-
32	32 80 00	02810	✓ Irrigation - Establish	1	by City	1	-	-	-
32	32 90 00	02945	✓ Landscape Plants	74,755	Tindall	2	16.45%	-	-
32	32 00 00	02920	✓ Sodding	1	w/Landscape	1	-	-	-
32	32 00 00	02905	✓ Transplanting	1	w/Landscape	1	-	-	-
Division 33 - Utilities									
33	33 00 00	02500	✓ Drainage Utilities	75,281	Stanford	2	0.07%	-	-
Division 35 - Coastal Construction									
35	33 00 00	02500	✓ New Boat Ramp - Articulating Mats	120,641	Case	2	0.07%	-	-
Estimate Sub Total Direct Cost =				701,924					
OWNER'S CONTINGENCY				5.000%	35,096				
GENERAL LIABILITY INSURANCE				1.200%	8,844				
BUILDERS RISK INSURANCE				-	0	Not Required			
SUB TOTAL WITH INSURANCE					745,864				
BOND				1.125%	8,393				
SUB TOTAL WITH BOND					754,257				
CM FEE					60,341				
SUB TOTAL WITH FEE					814,597				
Estimate Grand Total =				814,597					



General Conditions

City of Hollywood Boat Ramp

ESTIMATE NO./REF. SCEC2019.07.19
 TIME TO COMPLETE (days): 150
 PROJECT NUMBER: 19-0003-001-01
 LOCATION/OWNER: City Of Hollywood

1	2	3	4	5	6	7	8	9	10	11
Div. No.	CSI Cost Code	Enter Quantity	Unit	Description of Work	Unit Cost		not used	not used	Total Unit w/Tax & Burden	TOTAL
Construction Phase Fee (CM Staff)										
01	01 30 00	1	Week	Project Executive	4,160.00				4,160.00	\$ 4,160
01	01 30 05	6	Week	Project Manager	2,520.00				2,520.00	\$ 15,120
01	01 30 15		Week	APM/Project Engineer	2,360.00				2,360.00	\$ -
01	01 30 20	18	Week	Superintendent	2,640.00				2,640.00	\$ 47,520
01	01 30 25		Week	Assistant Superintendent	1,880.00				1,880.00	\$ -
01	01 30 30	3	Week	Project Coordinator	1,600.00				1,600.00	\$ 4,800
01	01 30 35	1	Week	Project Accountant	2,440.00				2,440.00	\$ 2,440
01	01 30 40		Week	Safety/Quality Control	2,000.00				2,000.00	\$ -
01	01 30 50		Week	LEED Coordinator	1,880.00				1,880.00	\$ -
									-	\$ -
Subtotal Direct Supervision CM Staff										\$ 74,040

Div. No.	CSI Cost Code	Enter Quantity	Unit Measure	Description of Work	Unit Cost				Total Unit w/Tax	TOTAL
General Conditions										
01	01 52 20		Month	Field Office Rental	500.00				500.00	\$ -
01	01 52 21		LS	Field Office Setup	800.00				800.00	\$ -
01	01 31 02	4	Month	Postage & Courier	50.00				50.00	\$ 200
01	01 31 01	4	Month	Office Supplies	106.00				106.00	\$ 424
01	01 51 40	9	Weeks	Water, Ice and Cups	124.00				124.00	\$ 1,116
01	01 35 02	4	Month	Safety Supplies	79.50				79.50	\$ 318
01	01 52 16	4	Month	First Aid Supplies	79.50				79.50	\$ 318
01	01 35 03	1	Each	Fire Extinguishers	88.50				88.50	\$ 89
01	01 30 03	1	LS	Blueprints & Copies	300.00				300.00	\$ 300
01	01 74 13	4	Week	Daily Cleanup	1,305.00				1,305.00	\$ 5,220
01	01 56 26	600	LF	Temporary Fencing	3.50				3.50	\$ 2,100
01	01 56 29	-	LF	Temporary Wind Screen	3.00				3.00	\$ -
01	01 51 19	4	Month	Portable Toilets	140.00				140.00	\$ 560
01	01 74 19	6	Load	Trash Dumpsters & Fees	600.00				600.00	\$ 3,600
01	01 95 01	1	LS	Misc. GC Expense	1,000.00				1,000.00	\$ 1,000
01	01 74 23	1	LS	Final Cleaning	2,000.00				2,000.00	\$ 2,000
01	01 32 23	1.00	LS	Survey & Layout	3000.00				3,000.00	\$ 3,000
01	01 45 23	1.50	LS	Testing Fees	2500.00				2,500.00	\$ 3,750
Subtotal General Requirements										\$ 23,995
TOTAL										98,035

City of Hollywood Boat Ramp

SCEC

SUBCONTRACTOR BID EVALUATION

Date of Bid: 7.19.2019
Scope of Work: GPR Survey
Bid Package Number: 02210
Cost Code: -
Division: 01

SCEC Estimate No/Ref: SCEC2019.07.19
Project Number: 19-0003-001-01
Cost per SF: -

SCOPE OF WORK		SUBCONTRACTOR:						
Description	Quantity	Blood Hound	Bidder 2	Bidder 3	Bidder 4	Bidder 5	Bidder 6	*Estimate*
One day of GPR Survey		1,600						
Bond Premium Adjustment								
Final Price Adjustment								
MWBE Participation (A,W,H,O)								
TOTALS:		1,600	0	0	0	0	0	0
BEST COMBINATION:		1,600 Blood Hound						

SELECTED SUBCONTRACTOR: Blood Hound

Estimate Prepared by: PAC
Estimate Reviewed by: BT

- Notes:**
- 1)
 - 2)
 - 3)
 - 4)
 - 5)

City of Hollywood Boat Ramp



SUBCONTRACTOR BID EVALUATION

Date of Bid: 7.19.2019
 Scope of Work: **Misc Patching / Site Restoration**
 Bid Package Number: -
 Cost Code: -
 Division: 02

SCEC Estimate No/Ref: SCEC2019.07.19
 Project Number: 19-0003-001-01
 Cost per SF: -

SCOPE OF WORK		SUBCONTRACTOR:					
Description	Quantity	Measure	Unit	SCEC			
<u>RESTORATION</u>							
Concrete Paving	0	SF	8.50	0			
Sod (At Staging Compound Only)	0	SF	0.45	0			
Sod (At trenching)	1200	SF	0.75	900			
New Concrete Curbing	0	LF	30.00	0			
Irrigation	0	LS	1,500.00	0			
Asphalt 1.5" S-1	0	SY	21.00	0			
Limerock base	0	SY	25.00	0			
Seal Coating	0	SF	0.16	0			
New Striping	0	LS	800.00	0			
Dumpsters	0	loads	450.00	0			
Patching - Materials (stucco, paint)	1	LS	300.00	300			
<u>CREW & EQUIPMENT</u>							
Skilled Labor	1	Weeks	1,595.00	1,595			
Labor	0	Weeks	1,305.00	0			
Bobcat	0	Months	1,100.00	0			
Concrete Buggy	0	Months	600.00	0			
Fuel	0	LS	200.00	0			
Pressure Cleaner (job Duration)	0	Lump Sum		w/GC			
Concrete Saw Cuttign - Sub	0	Days	650	0			
Asphalt Saw	0	Days	150	0			
Bond Premium Adjustment							
Final Price Adjustment							
MWBE Participation (A,W,H,O)							
TOTALS:				2,795	0	0	0
BEST COMBINATION:		2,795 SCEC					

SELECTED SUBCONTRACTOR: SCEC Estimate Prepared by: PAC Estimate Reviewed by: BT	Notes:
	1)
	2)
	3)
	4)
	5)

City of Hollywood Boat Ramp



SUBCONTRACTOR BID EVALUATION

Date of Bid: 7.19.2019
 Scope of Work: Protection/Pedestrian Control/M
 Bid Package Number: -
 Cost Code: -
 Division: 02

SCEC Estimate No/Ref: SCEC2019.07.19
 Project Number: 19-0003-001-01
 Cost per SF: -

SCOPE OF WORK		SUBCONTRACTOR:						
Description	Quantity	Unit	Unit Cost	SCEC				
Scope of Work:								
Pedestrian controls, MOT devices,								
MATERIALS								
Cautin tape & Signs	1	LS	1,800.00	1,800				
MOT Devices Rental	0	LS	9,548.00	0	See attached Backup			
CREW & EQUIPMENT (Erect and relocate)								
Skilled Labor	0	Weeks	1,595.00	0				
Labor	0	Weeks	1,305.00	0				
Bond Premium Adjustment								
Final Price Adjustment								
MWBE Participation (A,W,H,O)								
TOTALS:				1,800	0	0	0	0
BEST COMBINATION:		1,800 SCEC						
SELECTED SUBCONTRACTOR:				SCEC			Notes:	
Estimate Prepared by: PAC							1)	
Estimate Reviewed by: BT							2)	
							3)	
							4)	
							5)	

City of Hollywood Boat Ramp



SUBCONTRACTOR BID EVALUATION

Date of Bid: 7.19.2019
 Scope of Work: Concrete Retaining Wall
 Bid Package Number: 03300
 Cost Code: 03 30 00
 Division: 03

SCEC Estimate No/Ref: SCEC2019.07.19
 Project Number: 19-0003-001-01
 Cost per SF: -

SCOPE OF WORK		SUBCONTRACTOR:						
Description	Quantity	Allowance		Bidder 3	Bidder 4	Bidder 5	Bidder 6	*Estimate*
Subcontractor Bid Proposal								
Bond Premium		n/a	n/a	n/a	n/a	n/a	n/a	n/a
Retaining Wall	55 LF	33,000						
Bond Premium Adjustment								
Final Price Adjustment								
MWBE Participation (A,W,H,O)		-	-	-	-	-	-	-
TOTALS:		33,000	0	0	0	0	0	0
BEST COMBINATION:		33,000 Allowance						

<p>SELECTED SUBCONTRACTOR:</p> <p>Estimate Prepared by: PAC Estimate Reviewed by: BT</p>	Allowance	Notes:
		1)
		2)
		3)
		4)
		5)

City of Hollywood Boat Ramp



SUBCONTRACTOR BID EVALUATION

Date of Bid: 7.19.2019
 Scope of Work: Signage
 Bid Package Number: 10400
 Cost Code: 10 14 00
 Division: 10

SCEC Estimate No/Ref: SCEC2019.07.19
 Project Number: 19-0003-001-01
 Cost per SF: -

SCOPE OF WORK		SUBCONTRACTOR:						
Description	Quantity	Allowance	Bidder 2	Bidder 3	Bidder 4	Bidder 5	Bidder 6	*Estimate*
Subcontractor Bid Proposal	1 LS							
Bond Premium		n/a	n/a	n/a	n/a	n/a	n/a	n/a
Relocate & Adjust Existing Signs		6,500						
Install new Sign		8,000						
Bond Premium Adjustment								
Final Price Adjustment								
MWBE Participation (A,W,H,O)		-	-	-	-	-	-	-
TOTALS:		14,500	0	0	0	0	0	0
BEST COMBINATION:		14,500 Allowance						

SELECTED SUBCONTRACTOR: Allowance Estimate Prepared by: PAC Estimate Reviewed by: BT	Notes:
	1)
	2)
	3)
	4)
	5)

City of Hollywood Boat Ramp



SUBCONTRACTOR BID EVALUATION

Date of Bid: 7.19.2019
 Scope of Work: **Electrical**
 Bid Package Number: 16050
 Cost Code: 26 00 00
 Division: 26

SCEC Estimate No/Ref: SCEC2019.07.19
 Project Number: 19-0003-001-01
 Cost per SF: -

SCOPE OF WORK		SUBCONTRACTOR:						
Description	Quantity	Just Electric	Superior	C&F				
Subcontractor Bid Proposal	1 LS	81,858	NO BID	137,800				
Bond Premium		n/a	n/a	n/a				
New Lights				Includes				
Bond Premium Adjustment								
Final Price Adjustment								
MWBE Participation (A,W,H,O)		-	-	-	-	-	-	-
TOTALS:		81,858	0	137,800	0	0	0	0
BEST COMBINATION:		81,858 Just Electric						
SELECTED SUBCONTRACTOR:					Just Electric			
Estimate Prepared by: PAC Estimate Reviewed by: BT					Notes:			
					1)			
					2)			
					3)			
					4)			
					5)			



08/09/19

State Contracting
Polk Street Boat Ramp
Between Eight and Ninth Ave on Polk Street
Hollywood, Florida 33019

Pricing will remain the same with concrete poles due to cost of crane to offload poles.

PROPOSAL

Just Electric and Solar LLC is pleased to provide the following proposal to furnish materials and labor to comply with the projects submitted specifications and customer approval. Based on the scope of work we will include installation and materials along with labor.

SCOPE OF WORK

Polk Street Boat Ramp: Provide installation and labor and required misc. components for a complete and functional electrical system, as specified on the drawings (as provided through State Contracting) and in accordance with the National Electrical Code®, the Florida Building Code, and standard electrical practices.

PRICING

Total Cost for Equipment and Labor: \$81,858.85

Notes: ~~A. We are quoting aluminum poles as a substitute in lieu of concrete.~~

Payment Terms and Conditions and Scheduling to be negotiated at time of contract signing.

Any work above and beyond the listed scope of work will be written as time and material, and approved by owner prior to any additional work being performed. Owner agrees to pay for additional materials not foreseen in scope.

Just Electric and Solar LLC Will warranty materials for a period of one year from date of acceptance, however, items furnished or installed by others, persons altering items without the prior approval of Just Electric and Solar LLC , or damages due to improper care or maintenance are not included. (Individual parts warranty is to be covered by equipment manufacturer.)

The above proposal is accepted and Just Electric and Solar LLC, is authorized to proceed with the above stated work. This proposal becomes a binding contractual agreement when signed by both parties.

Date: _____ Signature: _____ Title: _____

Note: This proposal is subject to revocation if not accepted within 30 days. Just Electric and Solar LLC reserves the right to reject this contract if any major discrepancies between the drawings as reviewed and the actual installation are found to be considerably different at the time of installation.

Just Electric and Solar LLC looks forward to the opportunity to work with you!

Regards,

**Aaron T. Just
Owner
Just Electric and Solar LLC
EC#13005282**



July 15, 2019

**ELECTRICAL BID & SCOPE SHEET FOR
City of Hollywood Polk Street Boat Ramp**

Base Bid: \$ 137,800.00

- Per plans and specifications we received - Norm Bray Engineering. Site visit noted.
- All material, labor and temporary power included.
- All patching, restoration and painting excluded from base bid.
- Lightning protection system and lightning prediction system excluded.
- Siemens fire alarm system upgrades included as shown per contract documents.
- Specified light fixture package included with pre-stressed concrete poles.
- Electrical permit fees excluded from base bid.
- Electrical bond fees excluded from base bid. We are bondable at 1.4%.
- All Irrigation controls, Voice/Data Cabling, AV/ Security / Intrusion / CCTV Systems excluded.

City of Hollywood Boat Ramp

SCEC

SUBCONTRACTOR BID EVALUATION

Date of Bid: 7.19.2019
 Scope of Work: Earthwork, Paving, Striping, Drainage
 Bid Package Number: 02300
 Cost Code: 31 00 00
 Division: 31

SCEC Estimate No/Ref: SCEC2019.07.19
 Project Number: 19-0003-001-01
 Cost per SF: -

SCOPE OF WORK		SUBCONTRACTOR:					
Description	Quantity	Stanford	R&D Trans				
Subcontractor Bid Proposal	1 LS						
Bond Premium		add below					
Mobilization		8,600	8,000				
Erosion Control (line item)		0					
Survey & As Builts		16,225	16,000				
Tree Removal		8,255					
Demolition and Grubbing		20,485	32,738				
Earthwork & limerock base work		43,400	77,903				
Asphalt Paving		67,124	35,496				
MOT		by CM	by CM				
Striping & Signage		3,740	6,305				
Excavate & Backfil for Retaining Wall		6,500	6,500				
Bond Premium Adjustment		3,487	3,659				
Final Price Adjustment							
MWBE Participation (A,W,H,O)		-	-	-	-	-	-
TOTALS:		177,816	186,601	0	0	0	0

BEST COMBINATION: 177,816 Stanford

SELECTED SUBCONTRACTOR:

Stanford

Estimate Prepared by: PAC
 Estimate Reviewed by: BT

Notes:

- 1)
- 2)
- 3)
- 4)
- 5)



**STANFORD
CONSTRUCTION CO.**

Broward Office: 1081 NW 12th Terrace,
Pompano Beach, FL, 33069
Tel: (954) 783-6922/ Fax: (954) 783-6925
Miami Office: 99 NW 183rd, Suite # 239B (1),
Miami Gardens, FL, 33169
Tel: (305) 778-1476

PALM BEACH COUNTY ACROOL BOARD CERTIFIED SBE - STATE OF FLORIDA CERTIFIED MBE - BROWARD COUNTY CERTIFIED DBE
BROWARD COUNTY SCHOOL BOARD M/WBE - MIAMI-DADE COUNTY SCHOOL BOARD M/WBE - PALM BEACH COUNTY SCHOOL BOARD M/WBE

BID PROPOSAL

TO: SCEC STATE CONTRACTING & ENGINEERING CORPORATION
5391 NORTH NOB HILL ROAD
SUNRISE, FL, 33351

7/11/2019

TEL: 954-923-4747
FAX: (954) 922-3755

ATTN: PAUL CARTY - LEED AP, VICE PRESIDENT

PROJECT: POLK STREET BOAT RAMP
LOCATION: CITY OF HOLLYWOOD BEACH, FL

PLANS & SPECIFICATIONS:

AS PER PLANS BY: CRAVEN THOMPSON

PLAN SHEETS	
SHEETS	DATE
C-1	4/17/2019
C-2 THROUGH	5/7/2019
TD-1	6/30/2019

PER GEOTECHNICAL SOILS REPORT BY TIERRA SOUTH FLORIDA, DATED MAY 7, 2019

MOBILIZATION: \$ 8,600.00 ✓

- INCLUDES: - MOBILIZATION AND DEMOBILIZATION OF CREWS AND EQUIPMENT FOR OUR SCOPE OF THE PROJECT
- EXCLUDES: - ANY ADDITIONAL MOBILIZATIONS NOT LISTED ABOVE

EROSION CONTROL: \$ 10,851.00 ✓

- INCLUDES: - 700 +/- OF SILT FENCE W/ WIRE MESH
- 1,000 SF +/- OF TEMPORARY CONSTRUCTION ENTRANCE
- 338 +/- OF FLOATING TURBIDITY BARRIER
- FILTER FABRIC AND/ OR HAY BALE PROTECTION FOR EXISTING STORM INLETS TO REMAIN
- MAINTENANCE AND REMOVAL OF THE SILT FENCE AROUND THE PROJECT'S PERIMETER
- MAINTENANCE AND REMOVAL OF THE TEMPORARY GRAVEL CONSTRUCTION ENTRANCE
- MAINTENANCE AND REMOVAL OF THE FLOATING TURBIDITY BARRIER
- NOI FEE

MAINTENANCE OF TRAFFIC: BY OTHERS

- MAINTENANCE OF TRAFFIC FOR STANFORD CONSTRUCTION'S SCOPE OF WORK

SURVEY LAYOUT & ASBUILTS: \$ 16,225.00 ✓

- SURVEY LAYOUT FOR STANFORD CONSTRUCTION'S SCOPE OF WORK
- ASBUILTS FOR STANFORD CONSTRUCTION'S SCOPE OF WORK

TREE CLEARING: \$ 8,256.00 ✓

- INCLUDES: - REMOVAL OF THE THREE (3) EXISTING TREES & STUMP GRIND 2" BELOW GRADE
- TREE PROTECTION FOR (2) TREES ONLY PER PLANS
- EXCLUDES: - ANY RELOCATION OR PROTECTION OF ANY EXISTING TREES TO REMAIN ON THE SITE
- ANY PROPOSED LANDSCAPING OR TREES
- ANY REMOVAL OR RELOCATION PERMIT

GRUBBING: \$ 3,973.00 ✓

- INCLUDES: - SURFICIAL STRIPPING FOR UP TO 6" OF EXISTING VEGETATION IN THE PAVEMENT SUBGRADE AREAS AND THE BUILDING PAD

DEMOLITION: \$ 16,512.00 ✓

- INCLUDES THE FOLLOWING:

- 53 LF DEMOLISH THE EXISTING METAL GATE
- 382 LF DEMOLISH THE EXISTING "D" CURB
- 287 LF DEMOLISH THE EXISTING "F" CURB
- 1,774 SY DEMOLISH THE EXISTING ASPHALT PAVEMENT
- 1,559 SF DEMOLISH THE EXISTING CONCRETE SIDEWALK
- 350 LF SAWCUT THE EXISTING ASPHALT AT THE PROPOSED TIE INS
- 85 EA DEMOLISH THE EXISTING WOODEN POSTS
- 1 EA DEMOLISH EXISTING CONCRETE MONUMENT SIGN
- 96 SY DEMOLISH THE EXISTING ASPHALT PAVEMENT WALKWAY

- EXCLUDES: - ANY REMOVAL OF ANY EXISTING UTILITIES NOT LISTED BELOW
- ANY REMOVAL OF THE EXISTING LIGHTING
- ANY REMOVAL OF THE EXISTING CONCRETE MASONRY WALL
- ANY REMOVAL OF THE EXISTING GALVANIZED FENCING
- ANY REMOVAL OF THE EXISTING BUILDINGS
- ANY REMOVAL OF THE EXISTING DUMPSTER ENCLOSURE WALLS
- ANY REMOVAL OF THE EXISTING SEAWALL

DRAINAGE: \$ 75,281.00 ✓

- 1 - PLUG OF EXISTING 18" PIPE INVERT
- 1 - TYPE "D" DITCH BOTTOM W/ USF 6607
- 3 - 48" SQUARE CATCH BASIN W/ USF 4155-6210
- 7 - 24" FULL ANGLE ALUMINUM BAFFLES

- INCLUDES: - GROUT EXISTING 15" PIPE PVC IN PLACE
- REMOVAL OF THE TWO (2) EXISTING STORM CATCH BASINS AND MANHOLES

- EXCLUDES: - ANY CONNECTION OF HDPE TO EXISTING CATCH BASIN AT ROW SHEET C-4 (APPEARS TO BE EXISTING)

EARTHWORK:

\$ 43,400.00

- PROOF ROLLING OF THE SITE
- CUT, BALANCE, BACKFILL, AND FINE GRADE THE ASPHALT PAVEMENTS' SUBGRADE WITH THE EXISTING BASE AND SITE MATERIAL
- CUT, BALANCE, BACKFILL, AND FINE GRADE THE SIDEWALK'S SUBGRADE WITH THE EXISTING SITE MATERIAL
- CUT, BALANCE, BACKFILL, AND ROUGH GRADE THE GREEN AREA'S SUBGRADE WITH THE EXISTING SITE MATERIAL
- CUT, BALANCE, BACKFILL, AND ROUGH GRADE THE PERIMETER RETENTION AREA'S SUBGRADE WITH THE EXISTING SITE MATERIAL
- BACKFILL THE PLANTER ISLANDS WITH THE EXISTING SITE MATERIAL
- REMOVAL OF ANY SUITABLE EXCESS EXISTING MATERIAL GENERATED BY OUR SCOPE OF WORK

- INCLUDES THE FOLLOWING FOR QUANTITIES:

- 2,178 SY ASPHALT PAVEMENT SUBGRADE W/ GEOGRID MATERIAL
- 3,256 SF SIDEWALK SUBGRADE W/ LBR
- 20,033 SF BUILDING GREEN AREAS
- 1,812 SF RETENTION AREAS
- 244 CY EXCAVATE / CUT THE EXISTING SITE MATERIAL
- 244 CY BACKFILL WITH EXISTING SITE MATERIAL
- 1,183 CY BACKFILL WITH IMPORTED CLEAN FILL

- INCLUDES: - GEOGRID MATERIAL PER GEOTECHNICAL REPORT (QUALIFY EQUAL ACF BX12)

- EXCLUDES: - ANY PROCESSED TOPSOIL OR SODDING FOR THE PLANTER ISLANDS OR LANDSCAPED AREAS

ASPHALT PAVEMENT:

\$ 67,124.00

- INCLUDES THE FOLLOWING FOR QUANTITIES:

- 2,076 SY HEAVY DUTY 8" LIMEROCK BASE
- 88 SY 4" LIMEROCK PAD FOR CURBING
- 1,876 SY 2" HEAVY DUTY ASPHALT W/ 1st LIFT: 1" SP 9.5 2nd LIFT: 1" SP-9.5
- 67 SY 2" ASPHALT PATCH ABUTTING CURB

- INCLUDES: - PRICING ABOVE FOR THE ASPHALT IS BASED ON TWO (2) MOBILIZATIONS FOR THE PAVING

CONCRETE:

\$ 38,427.00

- INCLUDES THE FOLLOWING FOR QUANTITIES:

- 627 LF 6' X 18" TYPE "D" CURBING
- 160 LF 24" WIDE TYPE "F" CURBING
- 102 LF 24" WIDE VALLEY GUTTER
- 3,267 SF 6" CONCRETE SIDEWALK (NON REINFORCED)
- 60 SF HANDICAPPED RAMPS W/ ADA WARNING STRIP

- EXCLUDES: - ANY BOLLARDS, ENCLOSURE BLOCK WALLS, ENCLOSURE FENCING, OR ENCLOSURE GATES FOR THE DUMPSTER AREAS

STRIPING & SIGNAGE:

\$ 3,740.00

- INCLUDES: - STRIPING, SIGNAGE, AND CAR STOPS AS SHOWN ON THE PLANS

GENERAL SITE INCLUSIONS:

- INCLUDES DUST CONTROL MEASURES WITH WATER TRUCK
- INCLUDES TRENCH DEWATERING AND TRENCH SHORING AS REQUIRED FOR OUR SCOPE OF WORK

GENERAL SITE EXCLUSIONS:

- EXCLUDES ANY PUBLIC WORKS PERMIT FEES REQUIRED
- EXCLUDES ANY OVERLAY OR MILLING OF THE EXISTING ASPHALT FOR THE RESTORATION IN THE RIGHT OF WAY
- EXCLUDES ANY PROCESSED TOPSOIL OR SODDING FOR THE LANDSCAPED AREAS
- EXCLUDES ANY SOILS OR DENSITY TESTING
- EXCLUDES ANY DERM OR FDOT PERMIT FEES (TO BE FURNISHED BY THE OWNER)
- EXCLUDES ANY BOND FOR ANY MUNICIPAL

TWO HUNDRED & NINETY THREE THOUSAND THREE HUNDRED & EIGHTY EIGHT DOLLARS

BASE BID TOTAL:

\$ 293,388.00

TERMS AND CONDITIONS OF AGREEMENT TO PROPOSAL

All prices quoted are subject to Florida sales tax where applicable. This quotation is subject to acceptance within thirty (30) days.

Our terms are net, no discount. Invoices will be submitted as work progresses, based upon approximate quantities of work completed. Statements will be submitted by the 25th and will be due and payable by the 10th of the following month. If account remains unpaid after thirty (30) days from date of statement, Customer agrees to pay the maximum interest rate allowed by law on the unpaid monies, and further agrees to pay all court cost and/or reasonable attorney fees incurred in collection of the account.

AUTHORIZED SIGNATURE:

STANFORD AMRITT

DATE

ALTERNATES

PAYMENT & PERFORMANCE BOND ADD

ADD 2%

- ADD 2% TO THE BASE BID AND ANY ALTERNATES TAKEN IF A PAYMENT & PERFORMANCE BOND IS REQUIRED

Revised



S/WBE - M/WBE

400 EXECUTIVE CENTER DR. STE 210

WEST PALM BEACH, FL 33401

(561) 588-6681

Fax (561) 284-6541

PROPOSAL

July 15, 2019

TO: State Contracting & Engineering Corp.
5391 N. Nob Hill Road
Sunrise, FL 33351

Project: Polk Street Boat Ramp
600 Polk St.
Hollywood, FL 33019

ITEM #	BID ITEM: FURNISH AND INSTALL	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	Mobilization/Supervision	1	LS		\$8,000.00
2	Silt Fence	765	LF	\$1.80	\$1,377.00
3	Construction Entrance	1	EA	\$3,500.00	\$3,500.00
4	Grass Strippings	15111	SF	\$0.10	\$1,511.10
5	Demo Trees(Per Sheet TD-1)	6	EA	\$635.00	\$3,810.00
6	Demo Wood Posts	88	EA	\$30.00	\$2,640.00
7	Demo Asphalt	1	LS		\$10,000.00
8	Demo Concrete Curb	1	LS		\$5,250.00
9	Demo Concrete Sidewalk	1	LS		\$4,650.00
10	Embankment	1536	CY	\$18.75	\$28,800.00
11	12" Stab. Subgrade	1972	SY	\$9.50	\$18,734.00
12	Furnish and Place 8" Local Limestone Fine Grade, Compact, and Prime <i>1996 2078</i>	1972	SY	\$15.40	\$30,368.80
13	Furnish and Place 1" Asphaltic Concrete Wearing Surface Type SP 9.5	1972	SY	\$9.00	\$17,748.00
14	Furnish and Place 1" Asphaltic Concrete Wearing Surface Type SP 9.5	1972	SY	\$9.00	\$17,748.00
15	D Curb <i>627, 680</i>	600	LF	\$13.20	\$7,920.00
16	F Curb(Includes Curb Pad) <i>160, 142</i>	136	LF	\$52.00	\$7,072.00

32,738

27,903

35,586

17	Valley Gutter	115	LF	\$46.00	\$5,290.00
18	Concrete Sidewalk(Included Grading)	1675	SF	\$6.60	\$11,055.00
19	ADA RAMPS	4	EA	\$700.00	\$2,800.00
20	Final Grading	1	LS		\$6,000.00
21	Diamond Grade R1-1 Stop Sign BC Spe	2	EA	\$635.00	\$1,270.00
22	R5-1 Do Not Enter Sign BC Spec	1	EA	\$635.00	\$635.00
23	2 Color Thermo	1	MIN	\$1,650.00	\$1,650.00
24	Relocate Existing Signs and Upgrade Post to Current Spec	5	EA	\$550.00	\$2,750.00
25	Demo Existing Storm Structures	2	EA	\$2,120.00	\$4,240.00
26	18" Perf A2000 Pipe W/ Exfil Trench	201	LF	\$176.00	\$35,376.00
27	18" HDPE Drainage Pipe	58	LF	\$170.00	\$9,860.00
28	48" X 48" Type C Inlet (6-8')	3	EA	\$6,105.00	\$18,315.00
29	Type C Bubble Up Inlet (6-8')	1	EA	\$3,190.00	\$3,190.00
30	Core Existing Inlet & Connect 18" HDPE Drainage Pipe	1	EA	\$1,650.00	\$1,650.00

TOTAL:

\$273,209.90

***SEE SPECIAL CONDITIONAL SHEET**

****PRICE DOES NOT INCLUDE MOT**

*****PRICE DOES NOT INCLUDE DEMO IN AREA OF SEAWALL**

******PRICE DOES NOT INCLUDE EXCAVATION/EMBANKMENT FOR SEAWALL OR RAMP**

*******PRICE DOES NOT INCLUDE REMOVAL/RELOCATION OF MONUMENT SIGN**

Matthew M. Donnell
Estimator

216,132

3555
C 301

72631

RUIZ TRANS DEVELOPMENT

PO BOX 960040
Miami, FL 33296-0040



Price Quote

Date	Price Quote #
7/11/2019	202121

Phone #	Fax #
786-464-9056	786-577-0369

Customer Name / Address
State Contracting 3800 N 29th Avenue Hollywood, FL 33020

Project Name and/or Address
Boat Ramp Improvements - City

Representative
LC

Item	Description	Qty	U/M	Rate	Total
NOTE	PROJECT NAME: Boat Ramp Improvements - City of Hollywood PROJECT ADDRESS: CITY OF HOLLYWOOD MARINA BOAT LAUNCHING AREA, 700 POLK STREET SCOPE OF WORK: DEMO, ASPHALT, CONCRETE, CURBING, SIGNAGE, STRIPING (MAY 8TH, 2019 PLANS)"				
SITE DEV	REMOVE & DISPOSE EXISTING ASPHALT	16,747.4	SF	1.00	16,747.40
SITE DEV	REMOVE AND DISPOSE ON CONCRETE SIDEWALK	1,470.7	SF	2.00	2,941.40
SITE DEV	REMOVE & DISPOSE EXISTING CURB	381.4	LF	6.00	2,288.40
SITE DEV	REMOVE & DISPOSE EXISTING VALLEY GUTTER	101.2	LF	7.00	708.40
SITE DEV	REMOVE & DISPOSE EXISTING CURB & GUTTER	182.4	LF	7.00	1,276.80
SITE DEV	REMOVE & DISPOSE EXISTING DRAINAGE STRUCTURE	2	EA	800.00	1,600.00

Thank you and we look forward to doing business with you!

Total

RUIZ TRANS DEVELOPMENT

PO BOX 960040

Miami, FL 33296-0040



Price Quote

Date	Price Quote #
7/11/2019	202121

Phone #	Fax #
786-464-9056	786-577-0369

Customer Name / Address
State Contracting 3800 N 29th Avenue Hollywood, FL 33020

Project Name and/or Address
Boat Ramp Improvements - City

Representative
LC

Item	Description	Qty	U/M	Rate	Total
SITE DEV	REMOVE & DISPOSE EXISTING SIGN COLUMNS	2	EA	300.00	600.00
SITE DEV	EXISTING SIGN TO BE RELOCATED	3	EA	100.00	300.00
SITE DEV	EXISTING SIGN TO BE ADJUSTED TO PROPOSED GRADE	6	EA	150.00	900.00
SITE DEV	EXISTING DRAINAGE PIPE TO BE PLUGGED & ABANDONED IN PLACE	1	EA	300.00	300.00
SITE DEV	BERM	3,122	SF	2.00	6,244.00
SITE DEV	PROPOSED 2" ASPHALT (2 X 1" LIFTS)	2045 17,701.6	SF (1996 SY)	3.85	68,151.16
SITE DEV	PROPOSED CONCRETE 4", 6" x 6" - W1.4 X W1.4 - WWF	3,257 2,782.4	SF	4.75	13,216.40
SITE DEV	PROPOSED HANDICAP RAMP	57	300.6 SF	5.50	1,653.30
SITE DEV	PROPOSE TYPE "D" CURB	687	680.7 LF	16.00	10,891.20
SITE DEV	PROPOSE TYPE "F" CURB & GUTTER	160	147.1 LF	22.00	3,236.20
SITE DEV	PROPOSE VALLEY GUTTER	102	104 LF	20.00	2,080.00
SITE DEV	DETECTABLE WARNING ADA	4	EA	250.00	1,000.00
SITE DEV	PROPOSED STOP SIGN	2	EA	285.00	570.00

32,026

Thank you and we look forward to doing business with you!

Total

RUIZ TRANS DEVELOPMENT
 PO BOX 960040
 Miami, FL 33296-0040



Price Quote

Date	Price Quote #
7/11/2019	202121

Phone #	Fax #
786-464-9056	786-577-0369

Customer Name / Address
State Contracting 3800 N 29th Avenue Hollywood, FL 33020

Project Name and/or Address
Boat Ramp Improvements - City

Representative
LC

Item	Description	Qty	U/M	Rate	Total
SITE DEV	PROPOSED SIGN (no details East entrance)	1	EA	355.00	355.00
SITE DEV	TYPE P INLET - 48" X 48" CB W/ TOP SLAB AND USF #4155-6210 FRAME AND GRATE	3	EA	4,598.43	13,795.29
SITE DEV	TYPE C INLET - 24" X 37" CB W/ USF #4155-6210 FRAME AND GRATE	1	EA	3,242.43	3,242.43
SITE DEV	18" EXFILTRATION TRENCH	203.1	LF	125.00	25,387.50
SITE DEV	18" SOLID PIPE	61.9	LF	100.00	6,190.00
SITE DEV	STRIPING - <i>grass?</i>	1	LS	1,700.00	1,700.00
SITE DEV	PROPOSED INLET PROTECTION	6	EA	90.00	540.00
SITE DEV	PROPOSED TURBIDITY BARRIER	334	LF	20.00	6,680.00
SITE DEV	SILT FENCE	874.7	LF	2.50	2,186.75
SITE DEV	PROPOSED WASH RACK	1	LS	1,800.00	1,800.00
SITE DEV	MOT	1	LS	2,500.00	2,500.00
SITE DEV	SURVEY	1	LS	6,000.00	6,000.00

118104

11206

Thank you and we look forward to doing business with you!

Total \$205,081.63

City of Hollywood Boat Ramp



SUBCONTRACTOR BID EVALUATION

Date of Bid: 7.19.2019
 Scope of Work: **Erosion & Sedimentation Controls**
 Bid Package Number: 02370
 Cost Code: 31 10 00
 Division: 31

SCEC Estimate No/Ref: SCEC2019.07.19
 Project Number: 19-0003-001-01
 Cost per SF: -

SCOPE OF WORK		SUBCONTRACTOR:						
Description	Quantity	Estimate	Stanford	Ruiz Transport	Bidder 4	Bidder 5	Bidder 6	*Estimate*
Subcontractor Bid Proposal	1 LS	1						
Bond Premium		n/a	n/a	n/a	n/a	n/a	n/a	n/a
Silt Fence	880	2,200						
Turbidity Barrier	335	8,375						
			10,851	11,206				
Bond Premium Adjustment								
Final Price Adjustment								
MWBE Participation (A,W,H,O)		-	-	-	-	-	-	-
TOTALS:		10,576	10,851	11,206	0	0	0	0

BEST COMBINATION: 10,576 Estimate

SELECTED SUBCONTRACTOR: Estimate

Estimate Prepared by: PAC
 Estimate Reviewed by: BT

- Notes:
- 1)
 - 2)
 - 3)
 - 4)
 - 5)

City of Hollywood Boat Ramp



SUBCONTRACTOR BID EVALUATION

Date of Bid: 7.19.2019
 Scope of Work: **Concrete Paving**
 Bid Package Number: 02370
 Cost Code: 32 10 00
 Division: 32

SCEC Estimate No/Ref: SCEC2019.07.19
 Project Number: 19-0003-001-01
 Cost per SF: -

SCOPE OF WORK		SUBCONTRACTOR:						
Description	Quantity	R&D	Stanford	Homestead	Cobra			
Subcontractor Bid Proposal	1 LS	40,137	39,427	42,964	31,307	0		
Bond Premium								
Sidewalks		incl	incl	incl	incl	incl		
Curbs		incl	incl	incl	incl	incl		
Warning Mats		incl	incl	incl	incl	incl		
Valley		incl	incl	incl	incl	incl		
Allowance for price escalation					3,500			
Bond Premium Adjustment								
Final Price Adjustment								
MWBE Participation (A,W,H,O)		-	-	-	-	-	-	-
TOTALS:		40,137	39,427	42,964	34,807	0	0	0

BEST COMBINATION: 34,807 Cobra

SELECTED SUBCONTRACTOR:

Cobra

Estimate Prepared by: PAC
 Estimate Reviewed by: BT

Notes:

- 1)
- 2)
- 3)
- 4)
- 5)



Cobra Construction, Inc.

FL License: 96-1435-E

Date 7/11/2019

South Florida Office:

4010 Thor Drive
 Boynton Beach, FL 33426
 Tel: (561) 276-3820
 Fax: (561) 276-6067

1-888-642-6272

www.cobrapavers.com

Proposal

Customer

Name STATE CONTRACTING AND ENGINEERING
 Address 5391 N. NOB HILL ROAD
 City SUNRISE St FL ZIP 33351
 Phone 954-923-4747 CEL 954-802-6578
 Contact PENNY HARDING

Job Location

Name **POLK STREET BOAT RAMP**
 Address 700 POLK STREET
 City HOLLYWOOD St FL ZIP 33019
 Phone _____ Fax _____
 Email parding@statecontracting.com

Qty	Unit	Description	Price	Total
SCOPE OF WORK:				
SUPPLY AND INSTALL: FORM ,POUR , AND BROOM FINISH 3,000 PSI BROOM FINISH - NATURAL COLOR . (ALL WORK ON GRADE) SEE LINE ITEMS FOR DESCRIPTION .				
CONCRETE SIDEWALK AND CURBING OFF SITE				
1,769	SF +/-	PLAIN CONCRETE SIDEWALK 4" THICK NON REINFORCED	\$ 3.75	\$6,633.75
595	LF +/-	CONCRETE TYPE D- CURB EXTRUDED 6" X 18"	\$ 13.75	\$8,181.25
163	LF +/-	CONCRETE TYPE F- CURB AND GUTTER HAND FORMED	\$ 21.95	\$3,577.85
93	LF +/-	CONCRETE 2' WIDE VALLEY GUTTER HAND FORMED	\$ 20.95	\$1,948.35
50	SF +/-	DETECTABLE WARNING ACCESS TILE MFG. 2' TRAVEL ACCESS TILE . AMOUNT OF RAMPS 4 EACH	\$ 27.50	\$1,375.00
CONCRETE SIDEWALK ON SITE				
1,189	SF +/-	PLAIN CONCRETE SIDEWALK 4" THICK W/ 6X6 W1.4 X W1.4 WWM GALVANIZED .	\$ 4.75	\$5,647.75
248	LF +/-	CONCRETE THICKENED EDGE 8" X 8" W/ 1 # 5 REBAR GALVANIZED	\$ 12.85	\$3,186.80
850	SF +/-	MOVEMENT OF CONCRETE	\$ 0.89	\$756.50
Based on Plan Page: CIVILS			Dated/Revised: 5/7/2019	TOTAL \$31,307.25

Your Salesperson: **JOE SPADA 561- 436-1121**

Continued on Page 2

FOA



Cobra Construction, Inc.

FL License: 96-1435-E

Date 7/11/2019

South Florida Office:
4010 Thor Drive
Boynton Beach, FL 33426
Tel: (561) 276-3820
Fax: (561) 276-6067

1-888-642-6272

www.cobrapavers.com

Proposal

Customer		Job Location	
Name	STATE CONTRACTING AND ENGINEERING	Name	POLK STREET BOAT RAMP
Address	5391 N. NOB HILL ROAD	Address	700 POLK STREET
City	SUNRISE St FL ZIP 33351	City	HOLLYWOOD St FL ZIP 33019
Phone	- Fax -	Phone	- Fax -
Contact	PENNY HARDING	Email	pharding@statecontracting.com

PRICE IS GOOD THROUGH: 12/30/2019
CONTRACT TOTAL: \$31,307.25

TERMS AND CONDITIONS

1. All material and labor is guaranteed for a period of 1 year.
2. Customer is responsible for providing acceptable sub-base of 3-1/2" below finished grade for pavers or within +/- 1" to workable subgrade.
3. Quantities will be billed according to final field measurement.
4. All work changing the scope of this contract must be preceded by a signed Change Order / Extra work Order before any material can be ordered or work can be scheduled.
5. Customer / Contractor is required to carry sufficient levels of insurance coverage for property, theft, liability, fire, wind and other necessary insurance.
6. Title to all materials supplied is retained by Cobra Construction Inc. until paid in full.
7. Cobra Construction Inc. reserves the right to remove sufficient materials, whether in place or not, to satisfy the unpaid balance due.
8. Cobra is not responsible for delays created by other trades, material suppliers, labor strikes or acts of God.
9. Cobra is not responsible for damage to underground sprinklers or utilities, sod or landscaping, dust removal, painting or stucco, during the normal course of construction.
10. Unless otherwise stated in proposal, Cobra is not responsible for permits, inspections, base material, vapor barrier, soil treatment, densities, testing, engineering, surveys, grade stakes, grading, clean-up, traffic control or M.O.T.
11. Past due accounts, 30 days or over, are subject to finance charges of 1.5% per month (18% annum). It is further understood and agreed that in the event it becomes necessary to engage the services of any collection agency or attorney to collect payment for services rendered or related charges, the customer agrees to pay reasonable attorney fees and all collection costs in both pre-judgement and post-judgement collection actions.
12. Venue for all actions arising out of this contract and or proposal or any transactions with Cobra Construction Inc., and or Cobra Pavers & Engineering Inc., or any of its affiliates is exclusively in Palm Beach County.
13. Cobra will not be responsible for the supply or installation of electrical grounding or bonding systems at pool decks or any other required areas.
14. Bonding is not included in proposal unless otherwise stated.

The proposal, price, specifications and conditions are satisfactory and are accepted.

15. Exclusions : Raised Platforms and Steps, Dowells and Tie- Bars , Curb Pads, Sidewalk Bases , Signage and Striping , All Testing , QC Plan, Excavation/Grading, Surveying M.O.T Barricades, Back Fill , Road Rock Base.

COBRA SIGNATURE: _____ CUSTOMER SIGNATURE: _____

DATE: _____ DATE: _____



Homestead Paving, Co.

14550 Mable Street, Naranja, FL 33032
 Phone: 305-258-1972, Fax: 305-258-2267

Project: Polk Street Boat Ramp
 City of Hollywood, FL

Revised 2

Company: State Contracting
Phone: 786.201.5028
Fax:

Attn: Estimating

Date : July 12, 2019

By: Matt Rhodes

Prepared by: Kenny Rhodes

Bid Item	Description	Quantity	Unit	Unit Price	Amount
1	6"x18" Type 'D' Curb - Trenched 545	600 <i>✓</i>	LF	12.10	7,260.00
2	Type 'F' Curb and Gutter 263	250 <i>✓</i>	LF	27.10	6,775.00
3	6" Concrete Sidewalk - Reinforced with 6x6 10/10 Galvanized WWM, as per General Notes 7 & 10 sheet S-2.00N 298	3035 <i>✓</i>	SF	7.55	22,914.25
4	ADA Detectable Warning Pad 50	45 <i>✓</i>	SF	37.00	1,665.00
5	8"x8" Concrete Thickened Edge - Reinforced with 1 #5 Galvanized bar, as per Framing Schedule sheet S-2.00N	255 <i>✓</i>	LF	16.00	4,080.00
TOTAL					\$ 42,694.25

Plans Dated: _____

Prices good through: December 2019

Specs provided?: _____

Through Adden, #: _____

Initial: _____



Homestead Paving, Co.
14550 Mable Street, Naranja, FL 33032
Phone: 305-258-1972, Fax: 305-258-2267

Terms and Conditions

- 1 All Layout, Surveying and Engineering are not included
- 2 Unless otherwise stated, concrete is 3000 psi
- 3 All testing to be provided by others.
- 4 Grading, subbase compaction completed by others
- 5 Utility locates to be the responsibility of the contractor.
- 6 Permits and inspections are the responsibility of the contractor.
- 7 Class V finished, reflectors and maintenance of traffic is the contractor's responsibility.
- 8 Unless otherwise stated, excavation (unless trench is specified), waterproofing, demolition, and backfill are excluded.
- 9 General Contractor/Owner must provide a concrete truck washout area on site.
- 10 ID Badges, biometrics, background checks and special pay wages are not included
- 11 Unless included as a line item, bond in not included.
- 12 Unless included as a line item, joint sealant is not included.
- 13 The General Contractor will incur additional costs for night or weekend work unless otherwise mentioned in the quote.
- 14 Any quote given without plans and/or specs are subject to changes once plans and/or specs are made available.
- 15 Unless mentioned as a line item, any decorative treatment (stamp, scoring, etc.) are excluded.
- 16 Curb Pad are not included.
- 17 Unless specified in quote, reinforcement does not include galvanized or epoxy coated.
- 18 Lift or walkway behind traffic railing to finish is to be supplied by others.
- 19 Proposal must be included as an attachment to the contract documents.
- 20 Any alteration or deviation from the above specifications involving extra cost of labor will only be executed upon written orders of the same and will become an extra charge over the sum mention in this contract. All agreements must be made in writing.
- 21 Payments are to be made within 45 days of billing date, thereafter a 1.5% interest rate will be charge to your account, on a monthly basis. If payment is not received by 60 days after date billed, we will Lien/Notice of non-payment on that job. Any Legal Fees will also be paid by Contractor.
- 22 On site mock-ups not included, unless stated on proposal.

APPROVED BY: _____

DATE: _____

Note: Please sign and return back to us in order to begin process of submittal and scheduling

City of Hollywood Boat Ramp

SCEC

SUBCONTRACTOR BID EVALUATION

Date of Bid: 7.19.2019
 Scope of Work: Fence & Gate
 Bid Package Number: 02820
 Cost Code: 32 00 00
 Division: 32

SCEC Estimate No/Ref: SCEC2019.07.19
 Project Number: 19-0003-001-01
 Cost per SF: -

SCOPE OF WORK		SUBCONTRACTOR:					
Description	Quantity	Tropic	Carlson	S. Custom			
Subcontractor Bid Proposal	1 LS	5,850	NO BID	7,000			
Bond Premium		n/a		n/a			
2 Swing Gates		incl		incl			
Install		incl		incl			
Painted Yellow		incl					
6" Posts		850		incl			
Engineered Drawings		750		750			
Bond Premium Adjustment							
Final Price Adjustment							
MWBE Participation (A,W,H,O)		-	-	-	-	-	-
TOTALS:		7,450	0	7,750	0	0	0
BEST COMBINATION:		7,450	Tropic				

SELECTED SUBCONTRACTOR: Tropic
 Estimate Prepared by: PAC
 Estimate Reviewed by: BT

- Notes:
- 1) Based on replacemed of what is currently at park site. No detail provided on plan
 - 2)
 - 3)
 - 4)
 - 5)

Southern Custom Iron & Art
 210 SE 12th Ave Unit 5
 Boynton Beach, FL 33435
 561-557-9542
 ashleigh@southerncustomiron.com
 http://www.southerncustomiron.com



State Contracting
 5391 Nob Hill Rd
 Sunrise, FL 33351

Estimate # 2572
Purchase Order #
 City of Hollywood Polk Street Boat Ramp
 Renovations - Gates
Prepared On July 11, 2019
Expiration Date July 18, 2019
Estimate Total USD \$7,000.00

Description	Rate	Quantity	Tax	Line Total
2 Gates - 6" dia. Galv Pipe with casters, Material, Fabrication, and Install	\$7,000.00	1		\$7,000.00
Shop Drawings Included	\$0.00	1		\$0.00

Estimate Notes:
 See Terms and Conditions.

Estimate Total USD \$7,000.00



Tropic Fence, Inc.

"The only fence company you'll ever need"
1864 NW 21st Street, Pompano Beach, FL 33069
Phone 954-978-1250 Fax 954-960-1432
tropicfence@bellsouth.net

SALES QUOTE

July 10, 2019
PAGE: 1 OF 2

TO: STATE CONTRACTING
PENNY HARDING
PHARDING@STATECONTRACTING.COM

FOR: POLK STREET BOAT RAMP RENOVATIONS
HOLLYWOOD, FL
BID DATE: JULY 10, 2019

MATERIAL LIST

1) PIPE FRAME GATES

TWO 24' OPENING PIPE FRAME GATES WITH GROUND WHEELS
SIMILAR TO THE EXISTING.

4" OD SCH 40 PIPE FRAME SLID OVE 3 1/2" OD POST SET INTO
CONCRETE. *galvanized*
GATE WILL BE PAINTED SAFETY YELLOW.

TOTAL COST \$5,850.00 PLUS COST OF PERMIT IF
REQUIRED. *850*

~~\$6,700~~
REMOVAL OF EXISTING GATES BY OTHERS.

IF ENGINEERED DRAWINGS ARE REQUIRED ADD \$750.00

*425.00 x 2
6" Key*

NOTES & QUALIFICATIONS; SEE PAGE 2 OF 2 ADDENDUM _0_ OF _0_ SEEN.

DUE TO THE IMPENDING TARRIFS, PRICING CAN BE HELD FOR ONLY 15 DAYS

Tropic Fence, Inc. hereby proposes to furnish all labor, trucks, concrete, equipment and insurance necessary to install the above described materials as per ground plan herewith. Quotation is subject to the attached applicable Terms & Conditions located on page 2 of 2. Title to the above property shall remain in the name of Tropic Fence, Inc. until payment in full is received. In the event the money due or any portion has to be collected on demand by an Attorney or by lawsuit, the purchaser agrees to pay all costs of collection including interest at the highest legal rate and a reasonable attorney's fee. This is a retain title contract.

QUOTATION PREPARED BY: JIM ALLGIRE
TROPIC FENCE, INC 219 688-6354 CELL
TITLE: PROJECT MANAGER
DATE: JULY 10, 2019

ACCEPTED:
BY: _____
TITLE: _____
DATE: _____

THANK YOU FOR YOUR BUSINESS!

TROPIC FENCE IS A STATE CERTIFIED MINORITY & BROWARD COUNTY CERTIFIED CBE COMPANY

TERMS & CONDITIONS

July 10, 2019

PAGE: 2 OF 2

1. **LEAD TIMES:** TROPIC FENCE WILL PROCEED WITHIN 2-3 WEEKS AFTER RECEIPT OF A NOTICE TO COMMENCE WORK, APPROVED SHOP DRAWINGS AND PERMITS ARE OBTAINED. PLEASE ALLOW 2-3 WEEKS FOR PREPARATION OF SHOP DRAWINGS AND DESIGN CALCULATIONS AFTER RECEIPT OF PURCHASE ORDER OR EXECUTED SUBCONTRACT AGREEMENT. PLEASE ALLOW 2 WEEKS FOR REVISIONS TO SHOP DRAWINGS FOR RE-SUBMITTAL. MANUFACTURING LEAD TIMES ARE SUBJECT TO CHANGE DUE TO WORKLOAD AT TIME OF PRODUCTION.
2. PRICES ARE GOOD FOR **15 DAYS** FROM THE DATE OF THE PROPOSAL
3. MATERIALS WILL NOT BE ORDERED UNTIL THE PERMIT IS OBTAINED
4. GC TO LOCATE AND MARK BOTH NEW AND EXISTING UTILITY & IRRIGATION LINES THAT ARE **NOT** THE RESPONSIBILITY OF UNCLE AND/OR SUNSHINE LOCATORS. TROPIC FENCE WILL **NOT** ASSUME RESPONSIBILITY FOR ANY AND ALL DAMAGE TO UNDERGROUND LINES, PIPES, WIRE, ETC. THAT ARE NOT CLEARLY MARKED.
5. GC TO ESTABLISH LAYOUT POINTS, CLEAR FENCE LINES, AND FINISH GRADE FOR FENCE LINES PRIOR TO INSTALLATION.
6. TROPIC FENCE IS TO BE PAID FOR ANY REPAIRS/REPLACEMENTS DUE TO THIRD PARTY DAMAGE.
7. CONTRACTOR TO PROVIDE SCHEDULE UPON EXECUTION OF SUBCONTRACT AGREEMENT.
8. WHERE THE DELIVERY OF SPECIAL ORDER MATERIALS IS DELAYED THROUGH NO FAULT OF TROPIC FENCE, THE CONTRACTOR SHALL NOT HOLD TROPIC FENCE LIABLE FOR COSTS ASSOCIATED WITH SUCH DELAY.
9. PRICE PREDICATED ON MOBILIZING TWICE FOR ALL REQUIRED WORK, FENCE INSTALLATION PRIOR TO LANDSCAPE AND SPRINKLER INSTALLATION, AND THE AVAILABILITY OF READY MIXED CONCRETE
10. IF BONDS ARE REQUIRED, ALL COSTS AND PROCESSING FEES FOR THE BONDS WILL BE REIMBURSED TO TROPIC FENCE, INC. AT THE RATE OF 2.5% OF THE TOTAL JOB INCLUDING CHANGE ORDERS
11. IF ENGINEERED DRAWINGS AND CALCULATIONS ARE NECESSARY, ALL COSTS AND PROCESSING FEES WILL BE REIMBURSED TO TROPIC FENCE, INC.
12. IF A PERMIT IS REQUIRED, ALL COSTS OF THE PERMIT AND PROCESSING FEES TO OBTAIN THE PERMIT WILL BE REIMBURSED TO TROPIC FENCE, INC.
13. **EXCLUSIONS:** ELECTRIC GROUNDS, SURVEYS, TEMPORARY FENCING AND FENCE REMOVAL ARE EXCLUDED EXCEPT WHEN SPECIFICALLY STATED DIFFERENTLY ON THE PROPOSAL.
14. SPECIAL ORDER OF SHOP FABRICATED ORDERS ARE TO BE PRODUCED AS A SINGLE RELEASE. IF REQUIRED, PARTIAL RELEASES OR DEDICATED SHIPMENTS CAN BE INCLUDED FOR AN ADDITIONAL COST.
15. NO RETAINAGE WILL BE HELD ON CONTRACT AMOUNTS \$10,000.00 OR LESS.
16. TROPIC FENCE INC SHALL HAVE NO DEALINGS WITH ANY PARTY OTHER THAN GENERAL CONTRACTOR IN REGARD TO PERFORMANCE, CHANGES, ADDITIONS OR OMISSIONS ASSOCIATED WITH THIS WORK. THE SUBCONTRACT CANNOT BE CHANGED EXCEPT BY A PROPERLY EXECUTED WRITTEN CHANGE ORDER. NO WORK SHALL BE COMMENCED BY TROPIC FENCE IN CONNECTIONS WITH ANY CHANGES OR ADDITIONS TO THE WORK OR CHANGES IN THE CONTRACT REQUIREMENTS UNTIL TROPIC FENCE INC RECEIVES A WRITTEN ORDER FROM THE UNDERSIGNED OFFICER OR HIS SUCCESSOR OF THE GENERAL CONTRACTOR. UPON SUCH ORDER, TROPIC FENCE INC SHALL PERFORM THE EXTRA WORK, MAKE SUBSTITUTIONS IN THE WORK, OR DELETE SUCH WORK AS THE GENERAL CONTRACTOR MAY DIRECT. IN NO EVENT SHALL ANY CHANGE ORDER EXCEED THE PROPORTIONATE ADJUSTMENT MADE TO THE GENERAL CONTRACT BY THE OWNER, AND THE WRITTEN ORDER COVERING THE CHANGE SHALL STATE THE SPECIFIC AMOUNTS TO BE ADDED OR DEDUCTED FROM THE SUBCONTRACT.
17. SUBMITTAL DRAWINGS: INCLUDED IN THIS QUOTATION IS ONE SET OF DRAWINGS IN PORTABLE DOCUMENT FORM (PDF) FOR APPROVAL. IF DESIGN OR SIZE CHANGES DICTATE ADDITIONAL SUBMITTALS ARE REQUIRED, ADDITIONAL CHARGES MAY BE ASSESSED TO THE PROJECT.

SIGNATURE

DATE

City of Hollywood Boat Ramp

SUBCONTRACTOR

Date of Bid: 7.19.2019
 Scope of Work: Landscape Plants
 Bid Package Number: 02945
 Cost Code: 32 90 00
 Division: 32

SCEC Estimate No/Ref:
 Project Number:
 Cost per SF:

SCOPE OF WORK		SUBCONTRACTOR:			
Description	Quantity	Araozoa	Tindall		
Subcontractor Bid Proposal	1 LS	89,476			
Bond Premium		n/a	n/a	n/a	
Gumbo Limbo	18		11,250		
Buttonwood	17		8,500		
Royal Palm	6		4,950		
Cypress	4		1,980		
Relocated Palms	4		4,940		
Silver Bittonwood	40		440		
Sunflower			0		
Regal Mist	267		3,204		
GAMAGRASS	176		2,112		
Tree Removal	3		2,175		
SOD	19000		18,620		
Topsoil	60 cy		2,400		
Plantign Soil	1		4,420		
Mulch	1		2,494		
Relocate Chinese Fan Palms	2		2,500		
Royal Palm Relocates	3		4,770		
Bond Premium Adjustment					
Final Price Adjustment					
MWBE Participation (A,W,H,O)					
TOTALS:		89,476	74,755	0	0

BEST COMBINATION: 74,755 Tindall

SELECTED SUBCONTRACTOR:

Tindall

Estimate Prepared by: PAC
 Estimate Reviewed by: BT

Notes:

- 1)
- 2)
- 3)
- 4)
- 5)

TINDALL GROWERS INC.
5340 SW 64 AVE
DAVIE, FL 33314
954 792 1181

Date:
8/19/2019

Proposal #

Customer:
 State Contracting

REVISED 8-19-2019

Job Name:
Polk street boat ramp

QTY	DESCRIPTION	UNIT	TOTAL
13	Gumbo Limbo 2" dbh 12'	\$ 625.00	\$ 8,125.00
5	Gumbo Limbo 2" dbh 12' street trees	\$ 625.00	\$ 3,125.00
17	Green buttonwood 2" dbh 12'	\$ 500.00	\$ 8,500.00
6	Royal palm 8' gw	\$ 825.00	\$ 4,950.00
4	Bald cypress 2" dbh 12'	\$ 495.00	\$ 1,980.00
2	Coconut palm relocated **90 day guarantee	\$ 990.00	\$ 1,980.00
2	Canary island palm relocated **90 day guarantee	\$ 1,480.00	\$ 2,960.00
40	Silver buttonwood 2'x2' 3gal ***may need to change to 7gal	\$ 11.00	\$ 440.00
267	Muhly grass 3gal 18"x12" regal mist not available/ priced is regular	\$ 12.00	\$ 3,204.00
176	Df fakahatchee grass 24"x12" 3gal	\$ 12.00	\$ 2,112.00
19000	Seashore paspalum (vaginatum) sq ft	\$ 0.98	\$ 18,620.00
65	planting soil c.y.	\$ 68.00	\$ 4,420.00
580	Melealuca mulch (bags)	\$ 4.30	\$ 2,494.00
		TOTAL	\$ 62,910.00
2	Relocate Chinese fan palms not on plan***** **90 day guarantee	\$ 1,250.00	\$ 2,500.00
3	Demolish/remove 3 existing trees	\$ 725.00	\$ 2,175.00
3	Royal palm relocated **90 day guarantee NOT ON LIST	\$ 1,590.00	\$ 4,770.00
1	Watering of new plants for 90 days (55 trips)	\$ 19,800.00	\$ 19,800.00
1	WATER RELOCATED PALMS AFTER TRANSPLANTING (37 trips)		\$ 8,200.00

Due to hurricane Irma, some material may not be available. At the time of planting, the city, owner, and landscape contractor may need to adjust species or sizes. Adjustments in pricing may need to be made.

- 1) Sitework to prep for sod not included.
- 2) Permits are not included.
- 3) All work will be installed on Contractors grade.

- 4) Some material is not available as FL #1 in sizes specified.
- 5) Sod is not included, unless stated.
- 6) Sod, shrub and tree maintenance by others.
- 8) Hand watering of all material is only while install is being done.
- 9) Invasive / exotic plant removal by others, if needed.

*** 2" caliper instead of dbh will lower the price about \$5,500

**Arazoza Bros., Corp.**

P.O. Box 924890, Homestead, FL 33092 - (305) 246-3223 Fax (305) 246-0481

LI 6551-19 Boat Ramp Improvements

Description	Size	Total Qty	Unit Cost	Total Cost
Trees & Palms				
Bursera simaruba/Gumbo Limbo	10' Ht. X 5' Spr., 2" dbh	5	\$450.00	\$2,250.00
Conocarpus erectus/Green Buttonwood	10' Ht. X 5' Sprd., 2" dbh	19	\$450.00	\$8,550.00
Quercus virginiana/Live Oak	10' Ht. X 5' Sprd., 2" dbh, Multi Trunk	8	\$900.00	\$7,200.00
Quercus virginiana/Live Oak- Street Tree	12' Ht. X 6' Sprd., 6' C.T	5	\$800.00	\$4,000.00
Roystonea regia/Royal Palm	12' GW, 18' Ht.	6	\$1,700.00	\$10,200.00
				\$32,200.00
Shrubs				
Chrysobalanus icaco 'Horizontalis'/Horizontal Cocoplum	12" X 12" Sprd., 12" O.C	624	\$20.00	\$12,480.00
Conocarpus erectus 'Sericeus'/Silver Buttonwood	24" Ht. X 24" Sprd., 24" O.C	276	\$25.00	\$6,900.00
Helianthus debilis/Cucumberleaf Sunflower	12" Ht. X 12" Sprd., 12" O.C	220	\$10.00	\$2,200.00
Muhlenbergia capillaris 'Regal Mist' TM/Muhly	18" Ht. X 12' Sprd., 24" O.C	557	\$10.00	\$5,570.00
Tripsacum floridana/Florida Gamagrass	24" Ht. X 12" Sprd., 24" O.C	547	\$8.00	\$4,376.00
				\$31,526.00
Mulch				
Melaleuca Mulch	3" Depth, Cubic Yards	70	\$35.00	\$2,450.00
				\$2,450.00
Sod				
Paspalum notatum/Bahia Grass	Square Feet	9,500	\$0.40	\$3,800.00
				\$3,800.00
Soil				
Planting Soil	6" Depth, Cubic Yards	140	\$40.00	\$5,600.00
Topsoil for Sodded Areas	2" Depth, Cubic Yards	60	\$40.00	\$2,400.00
				\$8,000.00
Relocates				
Cocos nucifera/Coconut Palm	20-22' Ht. X 15' Sprd., 8-10" dbh	2	\$700.00	\$1,400.00
Livistona chinensis/Fan Palm	22-24' Ht. X 10' Sprd., 12" dbh	2	\$700.00	\$1,400.00
Phoenix canariensis/Canary Palm	8-12' Ht. X 20' Sprd., 24" dbh	2	\$3,000.00	\$6,000.00
Roystonea regia/Royal Palm	18-22' Ht. X 8-15' Sprd., 10-15" dbh	3	\$900.00	\$2,700.00
				\$11,500.00
Total Landscape...:				\$89,476.00
Irrigation				\$30,000.00
Total Irrigation:				\$30,000.00
Grand Total				\$119,476.00

Alternate:

Description	Size	Total Qty	Unit Cost	Total Cost
Landscape...				
Landscape				
Root Barrier	Linear Feet	1.	\$20.00	\$20.00

Qualifications:**Landscape...**

* Landscape proposal is based upon drawings TD-1 through LPD last dated 5/30/2019 by Craven Thompson and Associates, Inc.



Arazoza Bros., Corp.

P.O. Box 924890, Homestead, FL 33092 - (305) 246-3223 Fax (305) 246-0481

Qualifications:

Landscape...

- * Excavation of planting areas, soil to finish grade by others. All landscaped areas to be received denuded at +/- 1" of finish grade. Excavation and Backfill of soils is not included in proposal.
- * All work associated with existing trees/plants/lawns to remain (including tree protection), be removed is not included in proposal.
- * Relocate price applies to a single move only for each tree or palm. No guarantee is provided for relocated material. Note that a minimum of 4-8 weeks may be required to properly root-prune trees and palms prior to relocating.
- * Standard 2" x 4" wood bracing for trees and palms is included in proposal.
- * Initial fertilizer is included in proposal.
- * Tree grates, site furnishing, and hardscape items are not included in proposal.
- * Maintenance through acceptance only is included in proposal.
- * Root barrier, weed cloth and filter fabric are not included in proposal.
- * Structural soil (if needed) is not included in proposal.
- * Landscape permit fee is not included in proposal.
- * Mulch is priced as melaleuca, unless specifically detailed.
- * All living material to be provided will be Florida #1 quality according to the Florida Grades & Standards.
- * New installations are guaranteed for 1 year from completion/final acceptance.
- * Reference Sod Quantity: Sod quantity is approximated; actual quantity to be field-verified at time of installation.
- * If there is discrepancy between size of plant material and container size specified, container size supersedes.
- * Protective barriers are not included in the proposal.

Irrigation..

- * Irrigation proposal is based upon drawings LP-1 through LPD last dated 5/30/2019 by Craven Thompson and Associates, Inc.
- * Electrical drop and power hook-up fees for pump stations and controllers is not included in proposal.
- * Trenching through/boring under existing paving/asphalt, or coring through existing concrete, are not included in proposal.
- * Water meter, deposit tapping services, service charges, and/or capital or impact fees are not included in proposal.
- * SFWMD fees are not included in proposal.
- * Pipe hanging is not included in proposal.
- * All sleeves are to be open cut; no bores are included in proposal.
- * No consideration was given to the condition of any existing system herein.
- * Irrigation permit fee is not included in proposal.
- * 'Flowable Fill' (if needed) is not included in proposal.
- * Irrigation well is not included in proposal.
- * Irrigation proposal is strictly budgetary and subject to change based on completed irrigation plans.

General..

- * Any item not specifically listed is excluded from proposal.
- * Bond is not included in proposal.
- * MOT is not included in proposal, unless specifically detailed.
- * Hoisting of material, if needed, is not included in proposal.
- * This proposal shall be valid for ninety (90) days from date of issue.
- * Alternates, if present, are to be added to the cost of proposal.
- * Please read all qualifications carefully, as there could be references to specific materials, quantities, or pricing that pertain to this particular project.

Accepted By: _____ Date: _____



Arazoza Bros., Corp.

P.O. Box 924890, Homestead, FL 33092 - (305) 246-3223 Fax (305) 246-0481

Qualifications:

General:

Submitted By: _____ Date: _____

**Acceptance shall serve as notice that proposal has been reviewed and approved and contract is forthcoming.

City of Hollywood Boat Ramp

SCEC

SUBCONTRACTOR BID EVALUATION

Date of Bid: 7.19.2019
 Scope of Work: Irrigation - Establish
 Bid Package Number: 02810
 Cost Code: 32 80 00
 Division: 32

SCEC Estimate No/Ref: SCEC2019.07.19
 Project Number: 19-0003-001-01
 Cost per SF: -

SCOPE OF WORK		SUBCONTRACTOR:					
Description	Quantity	by City	Tindall				
Subcontractor Bid Proposal	1 LS	1					
Bond Premium							
Watering 90 day new plants							
Watering - Relocated Trees							
Bond Premium Adjustment							
Final Price Adjustment							
MWBE Participation (A,W,H,O)							
TOTALS:		1	0	0	0	0	0

BEST COMBINATION: 1 by City

SELECTED SUBCONTRACTOR: by City

Estimate Prepared by: PAC
 Estimate Reviewed by: BT

Notes:

- 1)
- 2)
- 3)
- 4)
- 5)

City of Hollywood Boat Ramp

SCEC

SUBCONTRACTOR BID EVALUATION

Date of Bid: 7.19.2019
 Scope of Work: Drainage Utilities
 Bid Package Number: 02500
 Cost Code: 33 00 00
 Division: 33

SCEC Estimate No/Ref: SCEC2019.07.19
 Project Number: 19-0003-001-01
 Cost per SF: -

SCOPE OF WORK		SUBCONTRACTOR:							
Description	Quantity	Sunline	Manny & Lou	Stanford	R&D Paving	Ruiz Trans			
Subcontractor Bid Proposal	1 LS	NO BID	NO BID	75,281	72,631	incomplete			
Bond Premium									
Structures				incl	incl				
Pipe				incl	incl				
Baffels				incl	incl				
Bond Premium Adjustment									
Final Price Adjustment					2,700				
MWBE Participation (A,W,H,O)									
TOTALS:		0	0	75,281	75,331	0	0	0	
BEST COMBINATION:			75,281	Stanford					
Notes:									

City of Hollywood Boat Ramp

SCEC

SUBCONTRACTOR BID EVALUATION

Date of Bid: 7.19.2019
 Scope of Work: New Boat Ramp - Articulating Mats
 Bid Package Number:
 Cost Code: 35 31 16
 Division: 35

SCEC Estimate No/Ref: SCEC2019.07.19
 Project Number: 19-0003-001-01
 Cost per SF: -

SCOPE OF WORK		SUBCONTRACTOR:					
Description	Quantity	Case					
Subcontractor Bid Proposal	1 LS	118,275	NO BID	NO BID	NO BID		
Bond Premium							
Mobilization		incl					
Survey & Layout		incl					
Articulating mat at ramps		incl					
Sawcut slabs as needed		incl					
Demolition as needed.		incl					
Bond Premium Adjustment		2,366					
Final Price Adjustment							
MWBE Participation (A,W,H,O)							
TOTALS:		120,641	0	0	0	0	0
BEST COMBINATION:		120,641	Case				

SELECTED SUBCONTRACTOR: Case

Estimate Prepared by: PAC
 Estimate Reviewed by: BT

- Notes:**
- 1) Based on attached detail fro mat anchor
 - 2) Based on articulating mat.
 - 3)
 - 4)
 - 5)



Case Marine Construction Int'l LLC

429 Lenox Avenue • Miami Beach, FL 33139 • Phone: 833.422.7326 • Fax: 833.422.7326

Eileen See
Phone: 954.923.4747
Cell: 954.802.6578

5391 N. Nob Hill Road
Sunrise, FL 33351

Job Address:
700 Polk Street
Hollywood, FL 3019

Print-date: 8-28-2019

Hello ,
We are pleased to submit our proposal for this project. Please see attached scope of work for details.

Scope of Work:

Code	Description
1320 - Equipment Rental	
1340 - Trash Removal	Furnish all trash removal from property
1370 - Mobilization	Move and Deliver all Equipment needed for project
3200 - Concrete	Furnish and Install 4 Articulated concrete mats for 4 boat ramps - total of 3840 sq feet total. M# BD-400-)C with Poly Cable and Alum Fittings and Galvanized Washers. Fill gaps between ACM and existing seawalls with 6000 concrete until seawall end.
3120 - Rebar	Furnish and Install all rebar needed for the Project
3200 - Concrete	Furnish and Install excavation, concrete, rebar and form work for 65' retaining wall
7070 - Labor	Furnish all Labor services for project
8001 - Insurance	Furnish Insurance including the federally required Jones Act and USL&H workmans compensation policies
8002 - Overhead	
8003 - Profit	

Buildertrend
Flat Rate

Total Price: \$118,275.00

We thank you for this opportunity and look forward to working with you on this project.

Sincerely,
Joey Woodworth

Terms:

- 25% Deposit on Signing**
- 15% Mobilization / Start of Job**
- 20% Delivery of Material**
- 25% Rough Inspection**
- 15% Final Inspection**

Exclusions/Notes:

THIS CONTRACT IS SUBJECT TO ALL APPLICABLE LAWS, REGULATIONS, AND ORDINANCES, AND TO THE FOLLOWING TERMS AND CONDITIONS:


1. Case Marine Construction Int'l LLC has the right to stop work, with a 5 (Five) notice to Owner, if any amount owed, including fees and interest specified in this Contract, is not paid by its due date Case Marine Construction Int'l LLC is not required to start work again until amounts owed are paid. Owner agrees to pay all costs and attorney's fees incurred by Case Marine Construction Int'l LLC to enforce any part of this Contract. Should Case Marine Construction Int'l LLC file a mechanic's lien against the property, Owner agrees to pay the cost of preparation, service, and filing of the lien, including attorney's fees.
2. This Contract price includes state required and industry standard insurance coverage at the date of this contract. Any bond, insurance premiums or other costs beyond normal bond and insurance coverage premiums shall be added to the amount of this Contract should they be incurred at Owner's request as a condition of this Contract.
3. Case Marine Construction Int'l LLC is not responsible for delays caused by (i) any action of Owner or their agents, (ii) requested changes in the work, (iii) any work stoppage under Paragraph 3 in this Contract, (iv) acts of God, (v) labor disputes, (vi) fire or other casualty, (vii) delays in material deliveries, (viii) adverse weather conditions, and (ix) other causes that Case Marine Construction Int'l LLC can not control. Case Marine Construction Int'l LLC is not responsible for damages from fire, windstorm or other hazards that are normally covered by Owners' insurance. Owners election to not procure sufficient coverage for their property does not transfer liability to Case Marine Construction Int'l LLC. Case Marine Construction Int'l LLC strongly urges property owners to procure sufficient insurance to protect their property.
4. During the period of any warranty, Case Marine Construction Int'l LLC is not responsible for any damage due to preexisting conditions, excessive wave action (excessive wave action defined as waves that crest above the seawall), or anything covered by a standard insurance policy that would cover the damage.
5. If material must be reordered or restocked because of a cancellation or other action by Owner, there may be fees equal to or exceeding fifteen percent (15%) of the Contract price of which Owner is responsible to pay.
6. Either party may use its legal rights and remedies, in any combination. If either party uses one or more of these rights and remedies, that party does not give up any other rights or remedies that it may have. If a party does not use any right or remedy on one occasion, that party does not give up the right to use the right and remedy on future occasions. Any exhibits to this Contract are a part of this Contract. Captions are provided for convenience and ease of reference only and do not affect or modify the terms of any of the provisions of this Contract. This Contract contains the entire contract of the parties. If any part of this Contract is held invalid or unenforceable, the rest of this Contract shall remain in force.

I confirm that my action here represents my electronic signature and is binding.

Signature

Print Name:

Date:



6 TOP OF DETAIL
NOT TO SCALE

DISCLAIMER:
THE INFORMATION CONTAINED HEREIN HAS BEEN COMPILED BY SHORETEC® LLC AND TO THE BEST OF OUR KNOWLEDGE, ACCURATELY REPRESENTS THE SHOREBLOCK® PRODUCT USE IN THE APPLICATIONS WHICH ARE ILLUSTRATED. FINAL DETERMINATION OF THE SUITABILITY FOR THE USE CONTEMPLATED AND ITS MANNER OF USE ARE THE SOLE RESPONSIBILITY OF THE USER. STRUCTURAL DESIGN AND ANALYSIS SHALL BE PERFORMED BY A QUALIFIED ENGINEER.

THIS DRAWING IS BEING FURNISHED FOR THIS SPECIFIC PROJECT ONLY. ANY PARTY ACCEPTING THIS DOCUMENT DOES SO IN CONFIDENCE AND AGREES THAT IT SHALL NOT BE DUPLICATED IN WHOLE OR IN PART, NOR DISCLOSED TO OTHERS WITHOUT THE CONSENT OF ACF ENVIRONMENTAL.

REVISIONS	
DATE:	DESCRIPTION:

PROJECT NAME:
**STANDARD UNIT
DETAIL**

PREPARED BY:
**McCoy
DRAWING &
DESIGN, LLC**

PREPARED FOR:
**ACF
ENVIRONMENTAL**

2831 Cardwell Road
Richmond, VA 23234
Phone (804) 271-2363
www.acfenvironmental.com

**SHOREBLOCK® BD-400-OC
REVETMENT UNIT**

DATE: **02-22-12**
DRAWING NAME: **TYPICAL DETAILS**
CHECKED BY: **JN**
SCALE: **NOT TO SCALE**

**S
~
1**



SECTION 4: PHASING/STAGING PLAN



Phasing/Staging Plan:

Work will be completed as one phase of work. The entire park will be closed at the start of construction, and re-open once all work is completed. Area of construction will be separated with a temporary construction fence.



SECTION 5: PROJECT SCHEDULE



Project Schedule attached.

Hollywood Boat Ramp				Classic Schedule Layout												19-Aug-19 15:17						
#	Activity ID	Activity Name	Start	Finish	Original Duration	Remaining Duration	Activity % Complete	Total Float	2019												2020	
									Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr
1	Hollywood Boat Ramp		15-Oct-19	21-Apr-20	125	125	0	0													Hollywood Boat Ramp	
2	Milestones		15-Oct-19	21-Apr-20	125	125	0	0													Milestones	
3	Mi1000	NTP	15-Oct-19*		0	0	0%	0													NTP	
4	Mi1010	Sbustantial Completion	25-Mar-20		0	0	0%	0													Sbustantial Completion	
5	Mi1020	Punch List	25-Mar-20	21-Apr-20	20	20	0%	0													Punch List	
6	Mi1030	Final Completion		21-Apr-20	0	0	0%	0													Final Completion	
7	Pre-Construction		15-Oct-19	6-Jan-20	50	50	5	5													Pre-Construction	
8	PCo-1000	Shop Drawings	15-Oct-19*	11-Nov-19	20	20	0%	0													Shop Drawings	
9	PCo-1010	Procurment Wall Panels	12-Nov-19*	6-Jan-20	30	30	0%	0													Procurment Wall Panels	
10	PCo-1020	Procurment Mats	12-Nov-19*	18-Dec-19	25	25	0%	10													Procurment Mats	
11	Construction		12-Nov-19	24-Mar-20	85	85	0	0													Construction	
12	Sea Side		7-Jan-20	13-Feb-20	27	27	28	28													Sea Side	
13	CoS-1000	Prep Slab	7-Jan-20	13-Jan-20	5	5	0%	0													Prep Slab	
14	CoS-1010	Install Articulating Mats	14-Jan-20	11-Feb-20	20	20	0%	0													Install Articulating Mats	
15	CoS-1020	Reset Docs	12-Feb-20	13-Feb-20	2	2	0%	28													Reset Docs	
16	Land Side		12-Nov-19	24-Mar-20	85	85	0	0													Land Side	
17	CoL-1000	Mobilization	12-Nov-19	18-Nov-19	5	5	0%	5													Mobilization	
18	CoL-1010	Demolition	19-Nov-19	25-Nov-19	5	5	0%	5													Demolition	
19	CoL-1020	Drainage/ Piping	26-Nov-19	13-Jan-20	25	25	0%	5													Drainage/ Piping	
20	CoL-1030	Earthwork	14-Jan-20	4-Feb-20	15	15	0%	5													Earthwork	
21	CoL-1040	First lift Paving	12-Feb-20	18-Feb-20	5	5	0%	0													First lift Paving	
22	CoL-1050	Concrete Sidewalks/ Curbs	19-Feb-20	3-Mar-20	10	10	0%	0													Concrete Sidewalks/ Curbs	
23	CoL-1060	Landscapeing	19-Feb-20	3-Mar-20	10	10	0%	0													Landscapeing	
24	CoL-1070	Final Paving	4-Mar-20	17-Mar-20	10	10	0%	0													Final Paving	
25	CoL-1080	Rolling Gates	18-Mar-20	24-Mar-20	5	5	0%	0													Rolling Gates	
26	CoL-1090	Stripe/ Signage	18-Mar-20	24-Mar-20	5	5	0%	0													Stripe/ Signage	

█ Remaining Level of Effort **▼** Summary
█ Actual Work
█ Remaining Work
█ Critical Remaining Work
◆ Milestone

Hollywood Boat Ramp
 Data Date: 19-Aug-19
 Page 1 of 1





SECTION 6: CONTRACT DRAWINGS



Contract Drawings:

See table of drawings below.

No.	Date	Title
C-1	05.30.19	Cover
C-2	08.12.19 – Rev.6	General Notes & Specifications
C-3	08.12.19 – Rev.6	Demolition Plan
C-4	08.12.19 – Rev.6	Paving, Grading & Drainage Plan
C-5	08.12.19 – Rev.6	Pavement Marking & Signage Plan
C-6	08.12.19 – Rev.6	Paving, Grading & Drainage Details
C-7	08.12.19 – Rev.6	Erosion Control Plan
C-8	08.12.19 – Rev.6	Pollution Prevention Notes & Details
C-9	08.12.19 – Rev.6	Pollution Prevention Notes & Details
TD-1	5.30.19	Tree Disposition Plan
LP-1	08.13.19 – City Rev.2	Landscape Plan
LP-2	08.13.19 – City Rev.2	Shrub & Ground Cover Plan
LPN	05.30.19	Landscape Notes
LPD	05.30.19	Landscape Plan Details
S-0.00	05.21.19 – Rev. 2	Boundary & Topographic Survey
S-2.00D	05.21.19 – Rev. 2	Boundary & Topographic Survey
S-2.00N	05.21.19 – Rev. 2	Boundary & Topographic Survey
S-2.01N	05.21.19 – Rev. 2	Boundary & Topographic Survey
S-3.00	05.21.19 – Rev. 2	Boundary & Topographic Survey
E-1	03.21.19	Lighting Plan for Hollywood Boat Ramps
E-2	06.27.19 – Rev.1	Lighting Plan for Hollywood Boat Ramps



Bidder's List and Bid Advertisement:

1. See attached Bidder's List.
2. Copy of advertisement is attached.

Bids Due Thursday, July 11, 2019 by 2:00

City of Hollywood - Polk Street Boat Ramps Renovation

Sub List PreBid : 6.26.19 at 2:00 P.M.

Updated: 7.3.19

? = Contacted but don't know if bidding yet.

B = Will Bid

NB = Not Bidding

BR = Bid Received

NBR = No Bid Received



Bid	Div. No.	Section/Company	Contact	Phone	Email	Cell	
	2	Concrete Sidewalks					
NB		Affordable Sidewalk Solutions	Fred Mahmood	954.232.2548			
BR		Cobra Construction/Cobra Pavers	Ron Spada	561.276.3820 x105	ron@cobrapavers.com	561.2476.6067	
BR		Homestead Paving	Kurt Schilk	305.258.1972	kschilk@homesteadpaving.com	305.258.2267	
NB		Statewide Concrete Finishing	Bill LaRue	561.333.1865			
	2	Drainage					
BR		Stanford & Sons Construction	Stanford Amritt	954-783-6922	a.abdul@stanfordcc.com ; samritt@bellsouth.net		
NB		Sunline Civil Construction, Inc.	Jimmy Bradley/Dave Bradle	772.221.8772	jimmybradley@sunlineinc.com ; davebradley@sunlineinc.com		
BR		R & D Paving	Nancy Rosso	561.588.6681	estimating@randdpaving.com		
BR		Ruiz Trans Development	Rick Ruiz	305.218.4755	les@ruiztransdevelopment.com	305.979.3955	
	5	Miscellaneous Metals - Park Gates					
NB		Bachiller Iron Works	Frank Bachiller	305.751.7773	estimating@biwiron.com ;		osef@biwiron.com
NB		Bostic Steel (misc. metals only)	Guy Cusano	305.592.7276	guyc@bosticsteel.com		
NB		Reimor Industries	Roly Remior	305.883.8722	rolyremior@bellsouth.net	305.883.9534	
BR		Southern Custom Iron & Art, LLC	Ashleigh Hernandez	561.557.9542	info@southerncustomiron.com		
BR		Tropic Fence	Gary Hale/Jim	954.978.1250, x 112	tropicfence.bids@bellsouth.net	954.960.1432	tropicjim@bellsouth.net
	26	Electrical					
BR		C & F Electric, Inc.	Kevin C. Flanagan	954.791.1114	kc@cfelectric.com		
NB		Just Electric	Aaron Just	305.389.0018	info@justelectricandsolar.com		
NB		Kendall Electric	Rey Bardelas	305.238.7033			
NB		Superior Electrical	Reynaldo Madiedo II	305.477.6328	rey@superior-electrical.com		
NB		Universal / Philco Electric of Florida, Inc.	Phillip L. Kroyman Jr.	954.484.5233			954.818.5411
	31	Earthwork & Paving					
NB		All-County Paving	Josh Marfleet	561.588.0949	jmarfleet@allcountypaving.com	561.588.2140	
NB		DirtWorks Inc.	Lonny Bengston	954.981.3478	lonny@dirworksinc.com		
BR		R & D Paving	Nancy Rosso	561.588.6681	estimating@randdpaving.com		
RR		Ruiz Trans Development	Rick Ruiz	305.218.4755	les@ruiztransdevelopment.com	305.979.3955	
BR		Stanford & Sons Construction	Stanford Amritt	954-783-6922	a.abdul@stanfordcc.com ; samritt@bellsouth.net		
	31	Pilings and Seawall					
BR		Case Construction Co.	Joey Woodworth	305.613.4241	joey@caseconstructionco.us		
NB		MidCoast Marine Group, LLC	Tyson Rawson	813.855.7904	trawson@midcoastllc.com		
NB		Pilings Plus, Inc.	David Newmark	954.520.5771	pilingsplusdavid@yahoo.com		Eric Newmark, 954.520.5068
NB		Southeast Marine Construction	Troy Wilson	954.295.4591	troy@semarineconstruction.com		
NB		Shoreline Foundation Co.	Jessica Welch/Ed Williams	954.985.0460	jwelch@shorelinefoundation.com ; ewilliams@shorelinefoundation.com		Will bid if new drawings.
NB		Smitty's Marine Construction	Michael Schmittendorf	954.773.5403	Michael@SmittysMarineConstruction.com	954.773.6690 - office	
	32	Landscaping and Irrigation					
NB		A1 Sod Sand and Soil	Andy Diaz	305.245.4445			
BR		Arazoza Brothers Corp.	Vanessa Ygualada	305.246.3223	vygualada@arazobrothers.com	305.246.0481	
NB		Landscape Service Professionals, Inc.	Karmen Burn	954.721.6920		954.721.6923	info@landscapeservicepros.com
NB		The Billy Goat	Linda	305.666.0111		305.666.0778	
BR		Tindall Growers	Matt Tindall	954.792.1181	Matt@Tindallgrowers.com		
NB		Windmill Sprinklers	Bill Meredith	954.763.3411			
		Striping/Signage					
BR		Fine -Line Striping, Inc.	Art Permenter	561.586.8115	artflstriping@yahoo.com		

Bidding

Licensee: Paul Carty

Project #: 1758877

Reported: 5/13/2019

Updated: 5/14/2019

Project Title	Polk Street Boat Ramp Renovations	
Physical Address	Polk Street & North 8th Avenue Map	
City, State (County)	Hollywood, FL 33019 (Broward County)	
Category(s)	Heavy and Highway	
Sub-Category(s)	Dock/Pier	
Contracting Method	Competitive Bids.	
Project Status	Accepting Qualifications	
Qualifications Due	05/24/2019 to Construction Manager Pre-Qualification for Sub-Bidding	
Estimated Value	\$750,000	
Plans Available from	Construction Manager	
Municipal Agency	<input type="checkbox"/> City of Hollywood - Procurement Website Analysis <i>Mailing Address:</i> PO Box 229045 Hollywood, FL 330229045 <i>Physical Address:</i> 2600 Hollywood Boulevard - Room 303 Hollywood, FL 33022 Procurement@hollywoodfl.org	(954) 921-3299 fax: (954) 921-3086
Construction Manager	<input type="checkbox"/> State Contracting & Engineering Corp (SCEC) Website Analysis 5391 North Nob Hill Road Sunrise, FL 33351 Contact - Eileen See e.see@statecontracting.com	(954) 923-4747 fax: (954) 922-3755
Agency Project #:	19-0003-001-01	
Description	Scope of work consists of renovation of existing boat ramp facility. Includes, but not limited to, mill & resurface asphalt paving, drainage, seawall restoration, concrete boat ramps, curbs, and landscaping.	
Details	Division 03 - Concrete, Concrete Forming, Concrete Reinforcing, Cast-in-Place Concrete, Miscellaneous Cast-in-Place Concrete. Division 05 - Metals, Structural Metal Framing, Steel Joist Framing, Metal Fabrications. Division 06 - Wood, Plastics, and Composites, Rough Carpentry, Finish Carpentry, Millwork, Standard Pattern Wood Trim. Division 07 - Thermal and Moisture Protection, Dampproofing and Waterproofing, Sheet Waterproofing, Thermal Protection. Division 08 - Openings, Doors and Frames, Specialty Doors and Frames, Entrances, Storefronts, Curtain Wall and Glazed Assemblies, Windows, Hardware. Division 26 - Electrical, Instrumentation and Control for Electrical Systems, Lighting, Emergency Lighting, Exit Signs, Exterior Lighting. Division 31 - Earthwork, Site Clearing, Grading, Excavation and Fill. Division 32 - Exterior Improvements, Operation and Maintenance of Exterior Improvements, Curbs, Gutters, Sidewalks, and Driveways, Curbs and Gutters, Cast-In-Place Concrete Curbs and Gutters, Paving Specialties, Parking Bumpers, Fences and Gates, Irrigation, Planting Irrigation, Planting Preparation, Soil Preparation, Landscape Grading. Division 33 - Utilities, Sanitary Sewerage Utilities, Storm Drainage Utilities, Electrical Utilities.	
Bidder's List	Add your Company to our Bidders List	



SECTION 8: CLARIFICATIONS AND ADDENDA



Clarifications and Addenda: None