

ATTACHMENT II

**Planning and Development Board Staff Report and
Backup; October 19, 2017**

CITY OF HOLLYWOOD, FLORIDA
MEMORANDUM
DEPARTMENT OF DEVELOPMENT SERVICES
PLANNING DIVISION

DATE: October 19, 2017 **MEMO NO.:** P 17-19

TO: Planning and Development Board

VIA: Leslie A. Del Monte, Planning Manager 

FROM: Jean-Paul W. Perez, Planning Administrator 

SUBJECT: Revised Staff Report for File No. 17-DP-07 due to a scrivener's error in the Site Data table.

EXPLANATION:

Due to a scrivener's error in the Site Data table on page 2 of the Staff Report for File No. 17-DP-07, a revised Staff Report has been attached hereto for your review. In addition, the Staff Report available on the City's website has also been updated to provide the proper value of the site area.

ATTACHMENTS:

ATTACHMENT A: Revised Staff Report for File No. 17-DP-07

**CITY OF HOLLYWOOD, FLORIDA
DEPARTMENT OF DEVELOPMENT SERVICES
PLANNING DIVISION**

REVISED STAFF REPORT

DATE: October 19, 2017

FILE: 17-DP-07

TO: Planning and Development Board

VIA: Leslie A. Del Monte, Planning Manager 

FROM: Jean-Paul W. Perez, Planning Administrator 

SUBJECT: Cleveland Homes, LLC requests Design and Site Plan for 6 townhouses located at 1604 Cleveland Street (Cleveland Street Townhomes).

REQUEST:

Design and Site Plan for 6 townhouses.

RECOMMENDATION:

Design: Approval.

Site Plan: Approval Design are granted with the following conditions:

- a. Unity of Title or Unity of Control, in a form acceptable to the City Attorney, be submitted prior to the issuance of a Building Permit, and shall be recorded in the Broward County Public Records, by the City of Hollywood, prior to the issuance of a Certificate of Occupancy (C/O) or Certificate of Completion (C/C).
- b. Updated drainage calculations and design shall be provided in a form acceptable to the City Manager or designee prior to the issuance of a Building Permit.

REQUEST

Cleveland Homes, LLC ("Applicant"), owner of the subject properties located at 1604 Cleveland Street ("Property"), is requesting Design and Site Plan approvals for 6 townhouses. The subject site is approximately 17,000 square feet net and 23,000 square feet gross. Currently, the site contains two dwelling units according to Broward County Property Appraiser ("BCPA") records. The subject property is located in the Poinsetta Park area, east of US-1 and north of Johnson Street, and is considered part of the Hollywood Lakes neighborhood according to the City-Wide Master Plan.

Site design incorporates urban principles, such as pedestrian scale, programming the site to the street and locating parking at the rear to enhance walkability of the neighborhood. Yards are located in the front of the townhouses to activate the site as well as encourage interaction between the private and public realms. The building maintains a low profile of two-stories. Structures, such as a four foot privacy wall, stairs leading up to the front door, and various architectural elements, are utilized to provide transition of scale, thus maintaining a relatable structure for pedestrians. To the top portion of the flat roof, the height of the building is 20-feet, however, mechanical equipment, a green roof system, parapet and other architectural elements extend beyond the roof—up to approximately 28-feet from the established grade.

Passive uses, such as parking, are located in the rear, and are screened by the building. Access to the parking in the rear is limited to a single curb cut on Cleveland Street, which will reduce potential conflict of vehicular and pedestrian traffic.

The proposed design is contemporary, effectively a timestamp of the period. Horizontality and projecting volumes are used to create depth, shadow and variation in massing of the façades. Materials include glass railing, smooth stucco finish and a black and white palette. Common areas, such as kitchen, living and dining room and den, are located on the ground floor. The second floor has two bed rooms and a master suite. The master suite accesses a balcony on the front, east side of the building, overlooking the yard and 16th Avenue further emphasizing activity on the street side of the development. However, the yards are intended for private use, and are surrounded by a 4-foot privacy wall.

Because the site consists of multiple lots, Staff recommends a **Unity of Title or Unity of Control, in a form acceptable to the City Attorney, be submitted prior to the issuance of permits and recorded in the Broward County Public Records, by the City of Hollywood, prior to the issuance of Certificate of Occupancy (C/O) or Certificate of Completion (C/C)**.

SITE DATA

Owner/Applicant:	Cleveland Homes, LLC
Address/Location:	1604 Cleveland Street
Net Area of Property:	16,793 sq. ft. (0.38 acres)
Gross Area of Property:	23,126 sq. ft. (0.53 acres)
Land Use:	Medium Residential
Zoning:	Medium Multifamily District (RM-12)
Existing Use of Land:	Two Dwelling Units

ADJACENT LAND USE

North:	Medium Residential
South:	Medium Residential
East:	Medium Residential
West:	Medium Residential

ADJACENT ZONING

North:	Medium Multifamily District (RM-12)
South:	Medium Multifamily District (RM-12)
East:	Medium Multifamily District (RM-12)
West:	Medium Multifamily District (RM-12)

CONSISTENCY WITH THE COMPREHENSIVE PLAN

The proposed project is located in the Medium Residential Land Use area. The goal of the Land Use Element is to *promote a distribution of land uses that will enhance and improve the residential, business, resort, and natural communities while allowing land Applicants to maximize the use of their property*. The surrounding community has a single and multiple family properties. The project is consistent with the Comprehensive Plan based on the following Objectives:

Objective 4: Promote improved architectural and streetscape design standards, code enforcement, economic development, neighborhood planning, and public information dissemination to maintain and enhance neighborhoods, businesses and tourist areas.

Objective 5: Encourage appropriate infill, redevelopment in blighted areas throughout the City and economic development in blighted business and tourist areas.

CONSISTENCY WITH THE CITY-WIDE MASTER PLAN

The site is located in Sub-Area 2, East Hollywood or Hollywood Lakes, which is geographically defined by the Intracoastal Waterway to the east, Dixie Highway to the west, Sheridan Street to the north and Pembroke Road to the south.

The City-Wide Master Plan is a compilation of policy priorities and recommendations designed to improve the appearance, appeal, and economic tax base of the City. It establishes a format for future direction and vision for the City.

The following City-Wide Master Plan Policies are applicable to this project:

Policy 2.46: Preserve stable neighborhoods and encourage rehabilitation initiatives that will revitalize and promote stability of neighborhoods.

The proposed development is consistent with the City-Wide Master Plan as it expands on the availability of market rate housing and provides increased density for property located two blocks east of the US-1 corridor. The proposed development will ameliorate an underutilized site and provide desired growth and density in a neighborhood surrounding a major commercial corridor.

APPLICABLE CRITERIA

Analysis of CRITERIA and Findings for Design as stated in the City of Hollywood's Zoning and Land Development Regulations, Article 5.

CRITERION 1: Architectural and Design components. Architecture refers to the architectural elements of exterior building surfaces. Architectural details should be commensurate with the building mass. The use of traditional materials for new architectural details is recommended. Design of the building(s) shall consider aesthetics and functionality, including the relationship of the pedestrian with the built environment.

ANALYSIS: Contemporary design relies heavily on massing and depth to create depth and shadow, giving buildings form. The proposed design channels these apropos traditions by introducing generous cubic forms to the façade—framing key elements of the building, in this case, the master suite's balconies. In addition, the open cube forms are also use to frame the windows. These architectural elements create depth and contrast in shade to establish difference in massing of the façade. The Applicant purports, “The exterior reflects the interior uses with an inspiration yet residential aesthetic.”

FINDING: Consistent.

CRITERION 2: Compatibility. The relationship between existing architectural styles and proposed construction, including how each building along the street relates to the whole and the pattern created with adjacent structures and the surrounding neighborhood. Buildings should contain architectural details that are characteristic of the surrounding neighborhood.

ANALYSIS: The surrounding neighborhood consists primarily of modest single family homes and older and mostly nonconforming apartment buildings. The proposed townhouses provide for subtle scale and rhythm that address the avenue, and provide for a pedestrian oriented design that is compatible with the envisioned development in neighborhoods surrounding the US-1 corridor.

FINDING: Consistent.

CRITERION 3: Scale/Massing. Buildings shall be proportionate in scale, with a height which is consistent with the surrounding structures. Building mass shall reflect a simple composition of basic architectural details in relation to its length, width, height, lot coverage, and setting of the structure in context with adjacent buildings. Architectural details include, but are not limited to, banding molding, and fenestration.

ANALYSIS: The structure and yards are amassed on the eastern portion of the lot towards the avenue to emphasize the pedestrian oriented design of the residences. Locating the active uses along the avenue encourage for interaction between the public and private realms. In addition, the scale of the structure to the street is kept within a proportion relatable to pedestrians at two stories. Transitional structures for scale, such as the 4 foot privacy wall, the stairs leading up to the front door, and the balconies and other architectural features on the east elevation further add to the intentionality of design allocating a majority of the activities to the street. Passive uses, such as parking, are located in the rear and screened by the building.

FINDING: Consistent.

CRITERION 4: Landscaping. Landscaped areas should contain a variety of native and other compatible plant types and forms, and be carefully integrated with existing buildings and paved areas. Existing mature trees and other significant plants on the site should be preserved.

ANALYSIS: Both native and other tropical plant types are used in the landscape design. The plant types enhance the design of the building while adding visual appeal to the neighborhood. Due to site constraints, the Applicant is proposing a green roof system which will allow the proposed project to meet open space requirements. In addition, the Applicant has worked intimately with the City's Landscape Architect towards a plan that meets the guidelines set forth in the Landscape Manual. Accordingly, all landscape plans shall be in accordance with the Landscape Manual and in a form acceptable to the City's Landscape Architect.

FINDING: Consistent.

SITE PLAN

The Technical Advisory Committee (TAC) found the proposed Site Plan compliant with all regulations as set forth in Article 6 of Zoning and Land Development Regulations on August 16, 2017. Staff recommends approval if Design is granted with the aforementioned conditions.

ATTACHMENTS

Attachment A: Application Package
Attachment B: Land Use & Zoning Map

ATTACHMENT A
Application Package

PLANNING DIVISION



File No. (internal use only): _____

2600 Hollywood Boulevard Room 315
Hollywood, FL 33022

GENERAL APPLICATION



Tel: (954) 921-3471
Fax: (954) 921-3347

This application must be completed in full and submitted with all documents to be placed on a Board or Committee's agenda.

The applicant is responsible for obtaining the appropriate checklist for each type of application.

Applicant(s) or their authorized legal agent must be present at all Board or Committee meetings.

At least one set of the submitted plans for each application must be signed and sealed (i.e. Architect or Engineer).

Documents and forms can be accessed on the City's website at
<http://www.hollywoodfl.org/DocumentCenter/Home/View/21>



APPLICATION TYPE (CHECK ONE):

Technical Advisory Committee Historic Preservation Board
 City Commission Planning and Development Board

Date of Application: 8/22/17

Location Address: 1604 Cleveland Street, Hollywood, FL 33020

Lot(s): 5, 6 + 7 Block(s): 2 Subdivision: NIA

Folio Number(s): 5142-10-20-0160

Zoning Classification: RM-12 Land Use Classification: Multi-Family

Existing Property Use: One-Story Residence Sq Ft/Number of Units: 1,630 / 6 units

Is the request the result of a violation notice? () Yes (X) No If yes, attach a copy of violation.

Has this property been presented to the City before? If yes, check all that apply and provide File Number(s) and Resolution(s): _____

Economic Roundtable Technical Advisory Committee Historic Preservation Board
 City Commission Planning and Development

Explanation of Request: NEW DEVELOPMENT OF 6 TOWNHOUSES.

Number of units/rooms: 6 TOWNHOUSES Sq Ft: 9,780 sqft.

Value of Improvement: _____ Estimated Date of Completion: 2019

Will Project be Phased? () Yes (X) No If Phased, Estimated Completion of Each Phase

Name of Current Property Owner: Cleveland Homes LLC

Address of Property Owner: 2501 S Ocean dr #106 Hollywood, FL 33019

Telephone: _____ Fax: _____ Email Address: _____

Name of Consultant/Representative/Tenant (circle one): _____

Address: _____ Telephone: _____

Fax: _____ Email Address: _____

Date of Purchase: _____ Is there an option to purchase the Property? Yes () No (X)

If Yes, Attach Copy of the Contract.

List Anyone Else Who Should Receive Notice of the Hearing: SKArchitect

Address: 2310 Hollywood Blvd, Hollywood, FL 33020 Email Address: ari@skarchitect.com, info@skarchitect.com, accounting@skarchitect.com

PLANNING DIVISION



File No. (internal use only): _____

2600 Hollywood Boulevard Room 315
Hollywood, FL 33022

GENERAL APPLICATION

CERTIFICATION OF COMPLIANCE WITH APPLICABLE REGULATIONS

The applicant/owner(s) signature certifies that he/she has been made aware of the criteria, regulations and guidelines applicable to the request. This information can be obtained in Room 315 of City Hall or on our website at www.hollywoodfl.org. The owner(s) further certifies that when required by applicable law, including but not limited to the City's Zoning and Land Development Regulations, they will post the site with a sign provided by the Office of Planning and Development Services. The owner(s) will photograph the sign the day of posting and submit photographs to the Office of Planning and Development Services as required by applicable law. Failure to post the sign will result in violation of State and Municipal Notification Requirements and Laws.

(I)(We) certify that (I) (we) understand and will comply with the provisions and regulations of the City's Zoning and Land Development Regulations, Design Guidelines, Design Guidelines for Historic Properties and City's Comprehensive Plan as they apply to this project. (I)(We) further certify that the above statements and drawings made on any paper or plans submitted herewith are true to the best of (my)(our) knowledge. (I)(We) understand that the application and attachments become part of the official public records of the City and are not returnable.

Signature of Current Owner: _____

Date: 8/24/17

PRINT NAME: Gustavo Gamarro

Date: 8/24/17

Signature of Consultant/Representative: _____

Date: 8/23/17

PRINT NAME: Sri Suman, Associate

Date: _____

Signature of Tenant: N/A

Date: _____

PRINT NAME: N/A

Date: _____

Current Owner Power of Attorney

I am the current owner of the described real property and that I am aware of the nature and effect the request for _____ to my property, which is hereby made by me or I am hereby authorizing _____ to be my legal representative before the _____ (Board and/or Committee) relative to all matters concerning this application.

Sworn to and subscribed before me

this _____ day of _____

Signature of Current Owner

Notary Public

Print Name

State of Florida

My Commission Expires: _____ (Check One) _____ Personally known to me; OR _____ Produced Identification _____

LEGAL DESCRIPTION:

**LOT 5 TO 7, BLOCK 2 SUBDIVISION POINSETTA PARK
ACCORDING TO THE PLAT THEREOF AS RECORDED
UN PLAT BOOK 8 AT PAGE 35 OF THE PUBLIC
RECORDS OF BROWARD COUNTY, FLORIDA.**

ID # 5142 10 20 0160



September 5th, 2017

Planning & Development Board
c/o Dept. of Planning & Development Services
2900 Hollywood Blvd, 3rd Floor
Hollywood, FL 33020

ARCHITECTURE
Commercial
& Residential

Interior
Architecture
& Design

Urban
Renovation

Architectural
Design of
Children's
Environments

Development
Consulting

Ref: Cleveland Townhomes Project Narrative - 1604 Cleveland Street, Hollywood, FL 33020

Dear Board Members,

We are proposing a new townhouse development on the corner of Cleveland Street & North 16th Avenue. This project consist of 6 new 2 story townhomes approximately 1,700 sq.ft each, with parking in the rear and a garden in the front. The design is contemporary and is planned to be constructed with typical concrete construction methods. The required finish floor elevation will be 1 ft above FEMA or 6ft NAVD. All 6 townhouses will face N 16th Ave and will help improve the character of the street and improve the neighborhood. The parking drive entrance will be behind the building entered from Cleveland St., there are 13 parking spaces.

Sincerely,

Ari L. Sklar - AIA, NCARB
President

2310 Hollywood Blvd.

Hollywood

Florida 33020

Tel: 954.925.9292

Fax: 954.925.6292

email:
mail@sklarchitect.com

WEBSITE:
www.sklarchitect.com

AA 0002849

IB 0000894


NCARB CERTIFIED



Ari Sklar, A.I.A.
Oscar Sklar, A.I.A.

September 5th, 2017

SKLARchitecture



Planning & Development Board c/o
Department of Planning and Development Services
2900 Hollywood Boulevard, 3rd Floor
Hollywood FL 33020

RE: Criteria Statement
Cleveland homes LLC/Cleveland Townhouses
1604-1606 Cleveland ST

ARCHITECTURE
Commercial
& Residential

Dear Board Members,

Our firm is the architect for the owner of the property. It is our hope that the City and the Planning and Development Board will support this application for the new development of 6 proposed townhouses. These new townhouses will enhance the Property and provide stability and revitalization to this multi-family portion of neighborhood.

Interior
Architecture
& Design

The Subject Property is located at 1604-1606 Cleveland St. is at the corner of Cleveland St. & North 16th Ave East of Federal Highway/US 1, it consists of 16,804 sq.ft. The development will replace a small 2 unit building which otherwise is vacant land. Each townhouse will have approximately 1,700 sq.ft.

Urban
Renovation

The parcel is designated “Medium Residential” under the City’s Comprehensive Plan and is within the RM-12 (Multiple Family Residential District). The subject Property is surrounded by multiple and single Residential development.

Architectural
Design of
Children’s
Environments

The property has only been developed with a small 2 unit building without any parking or landscaping. No variances are being requested with this application. The Subject Property currently lacks landscaping, lighting, proper site grading and drainage.

Development
Consulting

Design Criteria:

2310 Hollywood Blvd.

Hollywood

Florida 33020

Tel: 954.925.9292

Fax: 954.925.6292

email:

mail@sklarchitect.com

WEBSITE:

www.sklarchitect.com

1. Architectural & Design Components:

We feel that we have created a well thought out & exceptional design solution for this townhouse development. The Architecture is all about the consideration of aesthetics & functionality. The exterior reflects the interior uses with an inspirational yet residential aesthetic. The pedestrian is considered from all sides of the proposed design as well.

Architectural elements are present on all facades with interesting materials, shapes & features.

2. Compatibility:

The existing neighborhood consists of single story and 3 story buildings. This new development will fit right in with the existing single & multi-family neighborhood fabric as a 2 story, low scale, structure with a residential feel. A variety of window sizes and pedestrian oriented details & elements are incorporated to connect the new project to the neighborhood.

AA 0002849

IB 0000894

3. Scale Massing:

This new structure is proportionate to the scale of the neighborhood in a variety of ways.
a. Height – consistent with surrounding structures of 1 & 3 stories. Our project is 2 stories.

NCARB CERTIFIED



Ari Sklar, A.I.A.

Oscar Sklar, A.I.A.



- b. Building Mass – Our design reflects a simple rectangular composition with recognizable architectural elements and pleasing proportions in relation to length, width & height, lot coverage & its setting in context with the adjacent buildings. See the street context elevations profile on Sheet A-0.7.
- c. Details – The design provides architectural details throughout the façade including vertical & horizontal elements on the building façade with similar fenestration in the privacy fencing. The railings are metal & glass. The façade is also articulated with elegant moldings at and around the windows & doors. Other architectural details may be discovered throughout the building.

4. Landscaping:

The development plan for the Subject Property provides landscaped areas with green concepts implemented. The landscape palette has been designed to enhance the existing architecture and will be installed in accordance with the City's landscaping design and installation standards. The landscaping includes both native & a variety of other compatible plant types and forms to be enjoyed by residents & which complement the neighborhood. Including a Bio-swale adjacent to the parking lot. A number of mature existing Royal Palms are integrated into the site are incorporated be preserved!

Conclusion:

This new 6 unit development will help to improve the neighborhood and provide the needed living units for all the residents in the area. It is our goal to be good neighbors to those residents living adjacent to and near the Subject Property. We feel that the redevelopment of the site will improve the overall look of the neighborhood and hope that our plans for the area will encourage others to improve and purchase property in the neighborhood.

In closing, we believe that our plans demonstrate commitment to the neighborhood of Cleveland and North 16th Street and the City of Hollywood. We have worked hard to provide a plan that meets the City's Development & design review criteria.

Thank you for your time and consideration.

Sincerely,

Ari L. Sklar, AIA, NCARB

President

NEW TOWNHOUSES FOR:

CLEVELAND HOMES LLC.1604-1606 CLEVELAND ST.
HOLLYWOOD, FL 33020

PRELIMINARY TAC MEETING:
03/20/2017
FINAL TAC MEETING:
04/24/2017
PDB MEETING:
10/19/2017

PERMIT #:

REVISIONS

PROJECT TEAM

PROJECT RENDERING

DRAWING INDEX

ARCHITECT OF RECORD:
SKLARchitecture

2310 HOLLYWOOD BLVD.
HOLLYWOOD, FL 33020
www.skarchitect.com
TEL - (954) 925-9292
FAX - (954) 925-6292

AA 0002849
IB 0000894
NCARB CERTIFIED




LANDSCAPE:

Joaquin Cortada
Cortada Landscape Design
305.321.4350



SCOPE OF WORK

SIX NEW TWO-STORY TOWNHOUSES APPROXIMATELY
10,500 SQ FT.




SCALE: N.T.S.

LEGAL DESCRIPTION

THIS PROPERTY IS DESCRIBED AS:
LOT 5 TO 7, BLOCK 2 SUBDIVISION POINSETTA PARK
ACCORDING TO THE PLAT THEREOF AS RECORDED UN
PLAT BOOK 8 AT PAGE 35 OF THE PUBLIC RECORDS OF
BROWARD COUNTY, FLORIDA.

ID # 5142 10 20 0160



SCALE: N.T.S.

ARCHITECTURAL

A0.0 COVER
A0.6 RENDERINGS
A0.7 STREET PROFILE
A1.0 PROPOSED SITE PLAN
A1.1 SITE PLAN DETAILS
A1.2 SITE PLAN COLOR
A2.0 1ST & 2ND FLOOR PLANS
A2.1 ROOF PLAN
A4.0 BUILDING ELEVATIONS
A6.0 ENLARGED UNITS
A7.0 3D VIEWS

LANDSCAPE

LN-1 COVER SHEET / NOTES / INDEX
L-1 LANDSCAPE PLAN GROUND LEVEL
L-2 LANDSCAPE PLAN ROOF TOP
LD-1 LANDSCAPE DETAILS
TD-1 TREE DISPOSITION PLAN
TD-2 TREE DISPOSITION SCHEDULE/DETAILS
IRR-1 IRRIGATION PLAN GROUND LEVEL
IRR-2 IRRIGATION PLAN ROOF TOP
IRR-3 IRRIGATION DETAILS

PHOTOMETRIC
PH 1.0 PHOTOMETRIC PLAN

CIVIL

C-1 PAVING, GRADING & DRAINAGE
C-2 WATER & SEWER
C-3 NOTES & DETAILS

SURVEY

CODE ANALYSIS / PROJECT DATA

SITE DATA

LEGAL DESCRIPTION:

LOT 5 TO 7, BLOCK 2 SUBDIVISION POINSETTA PARK ACCORDING TO THE PLAT THEREOF AS RECORDED
UN PLAT BOOK 8 AT PAGE 35 OF THE PUBLIC RECORDS OF BROWARD COUNTY, FLORIDA.

ID # 5142 10 20 0160

GENERAL	REQ'D/ALLOWED	PROVIDED/REQUESTED
ZONING:	(MF) RM-12	12 UNITS/ACRE
LAND USE:	MULTIFAMILY	MULTIFAMILY
NET :	16,809 SF	16,809 SF = 0.38 AC
GROSS - W/ PORTION R.O.W.	23,126 SF	23,126 = 0.53 ACRES
DENSITY CALCULATIONS	=12 UNITS X 0.53 ACRES=6.36 =6 TOWNHOUSES ALLOWED	PROVIDED UNITS 6 TOWNHOUSES
OPEN SPACE:	MIN 40% PERVIOUS AREA 16,809 X 0.40 = 6,723.6 SF	GROUND 6,158 SF ROOF 600 SF TOTAL 6,758 SF (40.20%)

MAX HEIGHT (ft.): 3 STORIES 35'-0" FT 2 STORIES 24'-0" FT

MIN UNIT SIZE FOR TOWNHOUSE: 800 SF MIN. 1,695 MIN SF.

SETBACKS REQUIREMENTS

FRONT (N 16TH AVE): 20' FOR STRUCTURES.
5' AT GRADE 20'-0"

SIDE : 20% OF LOT WIDTH .
140' X 2 = 28'(THE SUM)
15' (NORTH SIDE)
13' (SOUTH SIDE)
28' BOTH SIDES

SIDE STREET (CLEVELAND ST.) : 15' FOR STRUCTURES.
5' AT GRADE. 15'-0"

REAR : 2 STORIES OR HIGHER.
15% OF THE LOT
DEPTH 120' X 0.15 = 18' 55'-0"

TOWNHOUSE UNIT BREAKDOWN

UNIT	NUMBER OF DWELLING UNITS	SQ.FT RANGE PER UNIT (AC)	TOTAL SF FOOTPRINT (GROSS)	TOTAL S.F. BUILDING (AC)
TYPICAL	6 UNITS - , 3 BDR, 2.5 BATH, 2 STORY	1,695 SQ FT	990 SQ FT	10,170 SQ FT
GRAND TOTAL	6 UNITS		5,940 SQ FT	10,170 SQ FT

PARKING CALCULATIONS			
TOWNHOME 2 PARKING PER UNIT PLUS 1 GUEST PARKING PER 5 UNITS	2 PARKING X 6 UNITS = 12 PARKING 6 UNITS/5 = 1.2 GUEST PARKING TOTAL = 13 PARKING SPACES	REQ. 13 PKNG	PROV. 13 PARKING

NEW TOWNHOUSE FOR:
CLEVELAND HOMES LLC.
1604-1606 CLEVELAND ST.
HOLLYWOOD, FL 33020

REVIEW SET
 PRELIMINARY
 NOT FOR CONSTRUCTION
 DRY RUN PERMIT SET
 PERMIT SET
 BID SET
 CONSTRUCTION SET
SUBMITTAL DATE: 04-17-17

DRAWN BY:
M.V.
CHECKED BY:
ARI SKLAR

COVER

Ao.O

PROJECT #: 16-017

DATE : 04-17-17



SE CORNER




NE CORNER



NW CORNER



N 16TH AVE FAÇADE



VIEW FROM WEST ELEVATION

NEW TOWNHOUSE FOR:
CLEVELAND HOMES LLC.
1604-1606 CLEVELAND ST,
HOLLYWOOD, FL 33020

REVIEW SET
 PRELIMINARY
 NOT FOR CONSTRUCTION
 DRY RUN PERMIT SET
 PERMIT SET
 BID SET
 CONSTRUCTION SET

SUBMITTAL DATE: 04-17-17



DRAWN BY:
M.V
CHECKED BY:
ARI SKLAR

RENDERINGS

Ao.6

PROJECT #: 16-017

DATE : 04-17-17



NEW TOWNHOUSE FOR:
CLEVELAND HOMES LLC.
1604-1606 CLEVELAND ST,
HOLLYWOOD, FL 33020

REVIEW SET
 PRELIMINARY
 NOT FOR CONSTRUCTION
 DRV RUN PERMIT SET
 PERMIT SET
 BID SET
 CONSTRUCTION SET

SUBMITTAL DATE: 04-17-17

DRAWN BY:
M.V.
CHECKED BY:
ARI SKLAR


STREET PROFILE

Ao.7

PROJECT #: 16-017

DATE : 04-17-17

SITE DATA			
LEGAL DESCRIPTION:			
LOT 5 TO 7, BLOCK 2 SUBDIVISION POINSETTA PARK ACCORDING TO THE PLAT THEREOF AS RECORDED UN PLAT BOOK 8 AT PAGE 35 OF THE PUBLIC RECORDS OF BROWARD COUNTY, FLORIDA.			
ID # 5142 10 20 0160		GENERAL	
REQ'D/ALLOWED		PROVIDED/REQUESTED	
ZONING: (MF) RM-12		12 UNITS/ACRE	
LAND USE: MULTIFAMILY		MULTIFAMILY	
NET : 16,809 SF		16,809 SF = 0.38 AC	
GROSS - W/ PORTION R.O.W.		23,126 SF	
23,126 = 0.53 ACRES			
DENSITY CALCULATIONS		=12 UNITS X 0.53 ACRES=6.36 =6 TOWNHouses ALLOWED	
OPEN SPACE:		MIN 40% Pervious Area 16,809 X 0.40 = 6,723.6 SF	
		GROUND 6,158 SF ROOF 600 SF TOTAL 6,758 SF (40.20%)	
MAX HEIGHT (ft.):		3 STORIES 35'-0" FT	
		2 STORIES 24'-0" FT	
MIN UNIT SIZE FOR TOWN HOUSE:		800 SF MIN.	
		1,695 MIN SF.	
SETBACKS REQUIREMENTS			
FRONT (N 16TH AVE):		20' FOR STRUCTURES. 5' AT GRADE.	
		20'-0"	
SIDE :		20% OF LOT WIDTH . 140" X.2 = 28"(THE SUM)	
		15' (NORTH SIDE) 13' (SOUTH SIDE) 28' BOTH SIDES	
SIDE STREET (CLEVELAND ST.) :		15' FOR STRUCTURES. 5' AT GRADE.	
		15'-0"	
REAR :		2 STORIES OR HIGHER. 15% OF THE LOT DEPTH 120' X 0.15 = 18'	
TOWNHOUSE UNIT BREAKDOWN			
UNIT	NUMBER OF DWELLING UNITS	SQ.FT RANGE PER UNIT (AC)	TOTAL S.F. FOOTPRINT BUILDING (GROSS)
TYPICAL	6 UNITS - , 3 BDR, 2.5 BATH, 2 STORY	1,695 SQ FT	990 SQ FT
GRAND TOTAL	6 UNITS		5,940 SQ FT
TOTAL S.F. BUILDING (AC)			
			10,170 SQ FT
PARKING CALCULATIONS			
TOWNHOME 2 PARKING X 6 UNITS = 12 PARKING PLUS 1 GUEST PARKING PER 5 UNITS	2 PARKING PER UNIT 6 UNITS/5 = 1.2 GUEST PARKING TOTAL = 13 PARKING SPACES	REQ. 13 PKNG	PROV. 13 PARKING
RESIDENTIAL GREEN BUILDING PRACTICES			
CHAPTER 151.158 LARGE DEVELOPMENT:			
1. RADIANT BARRIER - ENERGY STAR QUALIFIED - APPLIED TO ATTIC INSULATION.			
2. ENERGY STAR APPROVED ROOFING MATERIALS.			
3. PROGRAMMABLE THERMOSTATS.			
4. OCCUPANCY / VACANCY SENSORS.			
5. DUAL FLUSH TOILETS (LESS THAN 1 GALLON TO FLUSH LIQUID AND 1.6 GALLONS OR LESS FOR SOLIDS, PER USGBC).			
6. AT LEAST 80% OF PLANTS, TREES AND GRASSES PER THE SOUTH FLORIDA WATER MANAGEMENT DISTRICT RECOMMENDATIONS.			
7. LED LIGHTING AND LOW VOLTAGE LANDSCAPE LIGHTS THAN RUN ON A TIMER.			
8. ENERGY PERFORMANCE AT LEAST 10% MORE EFFICIENT THAN STANDARD ESTABLISHED BY ASHRAE (LATEST EDITION).			
9. INSULATED HOT WATER PIPES. ALL HOT WATER PIPES SHALL HAVE A MINIMUM OF 1/2" INSULATION, INCLUDING BURIED PIPES.			
10. MERV OF AIR FILTERS ON ALL AIR CONDITIONING UNITS AT LEAST 8 WITH ANTI-MICROBIAL AGENT.			
11. TANKLESS WATER HEATER IN LIEU OF A STANDARD TANK WATER HEATER. DOCUMENTATION OF ENERGY SAVINGS MUST BE PROVIDED.			



NEW TOWNHOUSE FOR:
CLEVELAND HOMES LLC.
1604-1606 CLEVELAND ST.
HOLLYWOOD, FL 33020

REVIEW SET
 PRELIMINARY
 NOT FOR CONSTRUCTION
 DRY RUN PERMIT SET
 PERMIT SET
 BID SET
 CONSTRUCTION SET
SUBMITTAL DATE: 04-17-17


DRAWN BY:
M.V.
CHECKED BY:
ARI SKLAR

PROPOSED SITE PLAN

A1.0

PROJECT #: 16-017


DATE : 04-17-17



1 DUMPSTER FRONT ELEVATION


1/2" = 1'-0"

1 CUBIC INCH OF STORAGE FOR EACH SQFT OF PROPERTY AREA.




4 CUTTER & DRAINAGE DETAIL

1" = 1'-0"




2 BOLLARD DETAIL

1/2" = 1'-0"




5 DUMPSTER WALL DETAIL

1/2" = 1'-0"



6 WALL SECTION AT PROPERTY LINE

1" = 1'-0"



3 CONCRETE PLANTER DETAIL

SCALE: N.T.S.

3 GREEN ROOF ASSEMBLY

1/8" = 1'-0"

NEW TOWNHOUSE FOR:
CLEVELAND HOMES LLC.
1604-1606 CLEVELAND ST.
HOLLYWOOD, FL 33020

REVIEW SET
 PRELIMINARY
 NOT FOR CONSTRUCTION
 DRY RUN PERMIT SET
 PERMIT SET
 BID SET
 CONSTRUCTION SET
SUBMITTAL DATE: 04-17-17

DRAWN BY:
M.V.
CHECKED BY:
ARI SKLAR

SITE PLAN DETAILS

A1.1

PROJECT #: 16-017

DATE : 04-17-17

REVISIONS

NEW TOWNHOUSE FOR:
CLEVELAND HOMES LLC.
1604-1606 CLEVELAND ST.

NEW TOWNHOUSE FOR:
CLEVELAND
1604-1606 CLEVELAND ST.,
HOLLYWOOD, FL 33020

- REVIEW SET
- PRELIMINARY
- NOT FOR CONSTRUCTION
- DRY RUN PERMIT SET
- PERMIT SET
- BID SET
- CONSTRUCTION SET

DRAWN BY:
M.V
CHECKED BY:
ARI SKLAR


SITE PLAN COLOR

A1.2



PROJECT #: 16-017

DATE : 04-17-17

—



REVISIONS



NEW TOWNHOUSE FOR:
CLEVELAND HOMES LLC.
1604-1606 CLEVELAND ST.
HOLLYWOOD, FL 33020

REVIEW SET
 PRELIMINARY
 NOT FOR CONSTRUCTION
 DRV RUN PERMIT SET
 PERMIT SET
 BID SET
 CONSTRUCTION SET
SUBMITTAL DATE: 04-17-17


DRAWN BY:
M.V.
CHECKED BY:
ARI SKLAR

1ST & 2ND FLOOR PLANS

A2.0

PROJECT #: 16-017

DATE : 04-17-17



1 ROOF PLAN
1/8" = 1'-0"



NEW TOWNHOUSE FOR:
CLEVELAND HOMES LLC.
1604-1606 CLEVELAND ST.,
HOLLYWOOD, FL 33020

REVIEW SET
 PRELIMINARY
 NOT FOR CONSTRUCTION
 DRY RUN PERMIT SET
 PERMIT SET
 BID SET
 CONSTRUCTION SET
SUBMITTAL DATE: 04-17-17




DRAWN BY:
M.V.
CHECKED BY:
ARI SKLAR


ROOF PLAN

A2.1

PROJECT #: 16-017


DATE : 04-17-17






1 TYPICAL UNIT A FIRST FLOOR PLAN

1/4" = 1'




3 TYPICAL UNIT B FIRST FLOOR PLAN

3 1/4" = 1'-0"



2 TYPICAL UNIT A SECOND FLOOR PLAN

1/4" = 1"



4 TYPICAL UNIT B SECOND FLOOR PLAN

1/4

NEW TOWNHOUSE FOR:
CLEVELAND HOMES LLC.
10000 CLEVELAND ST.

NEW TOWNHOUSE FOR:
CLEVELAND
TOWNHOMES CLEVELAND CT

- REVIEW SET
- PRELIMINARY
- NOT FOR CONSTRUCTION
- DRY RUN PERMIT SET
- PERMIT SET
- BID SET
- CONSTRUCTION SET

SUBMITTAL DATE: 04-17-17
DRAWN BY:
M.V
CHECKED BY:
ARI SKLAR

ENLARGED UP

A6.0

PROJECT #: 16

DATE : 04-17-17




1 VIEW FROM EAST



2 VIEW FROM WEST



3 NORTH-WEST



4 SOUTH-EAST

NEW TOWNHOUSE FOR:
CLEVELAND HOMES LLC.
1604-1606 CLEVELAND ST.
HOLLYWOOD, FL 33020

REVIEW SET
 PRELIMINARY
 NOT FOR CONSTRUCTION
 DRY RUN PERMIT SET
 PERMIT SET
 BID SET
 CONSTRUCTION SET

SUBMITTAL DATE: 04-17-17

DRAWN BY:
M.V.
CHECKED BY:
ARI SKLAR

3D VIEWS

A7.0

PROJECT #: 16-017


DATE : 04-17-17

CLEVELAND STREET TOWNHOMES
 SITE LIGHTING

Luminaire Schedule				LLF	Lum. Lumens
Symbol	Qty	Label	Description		
■	2	SA	VNTLEDM021004SNUIN510XXBLHO / WALL MTD AT 18' AFG	0.900	11901

Calculation Summary							
Label	CalcType	Units	Avg	Max	Min	Avg/Min	Max/Min
PARKING AREA	Illuminance	Fc	2.39	4.3	1.0	2.39	4.30
PROPERTY LINE	Illuminance	Fc	0.12	0.4	0.0	N.A.	N.A.

Filename: CST-Site-2017-05-04.AGI


 NEW TOWNHOUSE FOR:
CLEVELAND HOMES LLC.
 1604-1606 CLEVELAND ST.
 HOLLYWOOD, FL 33020

 REVIEW SET
 PRELIMINARY
 NOT FOR CONSTRUCTION
 DRY RUN PERMIT SET
 PERMIT SET
 BID SET
 CONSTRUCTION SET
 SUBMITTAL DATE: 04-17-17


 DRAWN BY:
 M.V.
 CHECKED BY:
 ARI SKLAR

PHOTOMETRIC PLAN

PH1.0


PROJECT #: 16-017

DATE : 04-17-17




IRRIGATION SCHEDULE

SYMBOL	MANUFACTURER/MODEL/DESCRIPTION	QTY	PSI	DETAIL
EST LCS RCS CST SST	Rain Bird 1804 15 Strip Series Turf Spray 4.0" Pop-Up Sprinkler with Co-Molded Wiper Seal. 1/2" NPT Female Threaded Inlet.	1	30	
Q H F	Rain Bird 1804 5 Series MPR Turf Spray 4.0" Pop-Up Sprinkler with Co-Molded Wiper Seal. 1/2" NPT Female Threaded Inlet.	25	30	
Q T H F	Rain Bird 1804 8 Series MPR Turf Spray 4.0" Pop-Up Sprinkler with Co-Molded Wiper Seal. 1/2" NPT Female Threaded Inlet.	37	30	
Q T H F	Rain Bird 1804 10 Series MPR Turf Spray 4.0" Pop-Up Sprinkler with Co-Molded Wiper Seal. 1/2" NPT Female Threaded Inlet.	47	30	
Q T H F	Rain Bird 1804 12 Series MPR Turf Spray 4.0" Pop-Up Sprinkler with Co-Molded Wiper Seal. 1/2" NPT Female Threaded Inlet.	25	30	
Q T H F	Rain Bird 1804 15 Series MPR Turf Spray 4.0" Pop-Up Sprinkler with Co-Molded Wiper Seal. 1/2" NPT Female Threaded Inlet.	4	30	
4V 6V 18V	Rain Bird 1804 ADJ Turf Spray 4.0" Pop-Up Sprinkler with Co-Molded Wiper Seal. 1/2" NPT Female Threaded Inlet.	4	30	
Ø8HE-VAN Ø12HE-VAN Ø10HE-VAN Ø15HE-VAN	Rain Bird 1804 ADJ Turf Spray 4.0" Pop-Up Sprinkler with Co-Molded Wiper Seal. 1/2" NPT Female Threaded Inlet.	1	30	
Q T H F	Rain Bird 1812 8 Series MPR Shrub Spray 12.0" Pop-Up Sprinkler with Co-Molded Wiper Seal. Side and Bottom Inlet. 1/2" NPT Female Threaded Inlet.	3	30	
Q T H F	Rain Bird 1812 10 Series MPR Shrub Spray 12.0" Pop-Up Sprinkler with Co-Molded Wiper Seal. Side and Bottom Inlet. 1/2" NPT Female Threaded Inlet.	17	30	
Q T H F	Rain Bird 1812 15 Series MPR Shrub Spray 12.0" Pop-Up Sprinkler with Co-Molded Wiper Seal. Side and Bottom Inlet. 1/2" NPT Female Threaded Inlet.	1	30	
	Area to Receive Dripine Rain Bird XFCV-09-12 (09) XFCV On-Surface Landscape Dripine with a Heavy-Duty 3.5 psi Check Valve. 0.96GPH emitters at 12.0" O.C. Dripine laterals spaced at 9.0" apart, with emitters offset for triangular pattern. Great for elevation change. Specify XF insert fittings.	157.6 s.f.		
	Rain Bird PGA Globe 1", 1-1/2", 2" Electric Remote Control Valve, Globe.	6		
BF	Watts 009 1" Reduced Pressure Backflow Preventer	1		
C	Rain Bird ESP4ME with (1) ESP-SMB 7 Station, Hybrid Modular Outdoor Controller. For Residential or Light Commercial Applications.	1		
RS	Rain Bird RSD-BEx Rain Sensor, with metal latching bracket, extension wire.	1		
M	Water Meter 1"	1		
	Irrigation Lateral Line: PVC Class 160 SDR 26 PVC Class 200 irrigation pipe.	1,638 l.f.		
	Irrigation Mainline: PVC Schedule 40 PVC Schedule 40 irrigation pipe.	198.3 l.f.		
	Pipe Sleeve: PVC Schedule 40 Valve Callout	92.7 l.f.		



IRRIGATION PLAN GROUND LEVEL



CLEVELAND HOMES LLC

1604-1606 CLEVELAND ST
HOLLYWOOD, FL 33020

Cortada
LANDSCAPING DESIGN

TEL: (305) 321.4350
design@landscapingmiami.com
91 NW 154 ST
MIAMI FL 33169

PROJECT TEAM:
LANDSTONE DESIGN INC
TEL: (818) 856.9556
info@landstonedesign.com


DERICK LANGEL, RLA, ISA
FLORIDA REG. NO. LA6667045

SCALE:	INDICATED
DRAWN BY:	
CHECKED BY:	
DATE	DESCRIPTION
03-09-17	
PROJECT NO.:	
SHEET NO.:	

IRR-1

CLEVELAND HOMES LLC

1604-1606 CLEVELAND ST
HOLLYWOOD, FL 33020



AFTER ESTABLISHED, THE PROPOSED
MUHLY GRASS DOES NOT NEED
IRRIGATION EXCEPT IN PROLONGED
PERIODS WITHOUT RAIN.

IRRIGATION PLAN
ROOF TOP



0 8 16 24 32 feet
1/8" = 1'-0"

SEAL
DERICK LANGEL, RLA, ISA
FLORIDA REG. NO. LA6667045

SCALE: INDICATED

DRAWN BY:

CHECKED BY:












DATE DESCRIPTION

03-09-17

PROJECT NO.

SHEET NO.

IRR-2



SEAL
DERICK LANGEL, RLA, ISA
FLORIDA REG. NO. LA6667045

SCALE: INDICATED
DRAWN BY:
CHECKED BY:

DATE DESCRIPTION
03-09-17

PROJECT NO.

SHEET NO.
LD-1

GENERAL LANDSCAPE NOTES:

A. SCOPE

- The locations of plants, as shown in these plans, are approximate. The final locations may be adjusted slightly to accommodate unforeseen field conditions. All other location adjustments to the layout are to be approved in advance in writing by the Landscape Architect and owner.

B. BIDDING

- See typical planting details sheet for additional planting details and notes
- Landscape contractor shall verify all estimated quantities of material shown on the drawings prior to submitting his bid. Planting plan to take precedence over plant list.
- Pre-inspections of site required prior to bidding.
- The plant list is intended only as an aid to bidding. Any discrepancies found between the quantities on the plan and plant list the quantities on the plan shall be held valid.
- All labor and material for soil amendments and fertilizer that is required to insure the successful establishment and survival of the proposed vegetation, as well as all the cost for the removal of unsuitable or excess backfill material, shall be included in the contractor's bid to perform the work represented in this plan set.
- Bid shall be itemized for possible value engineering.
- Sod shall include price per square foot.

C. GENERAL LANDSCAPE NOTES

- All landscaping shall be installed according to sound nursery practices. Plants grown in containers prior to installation shall be removed from their containers before they are planted in the ground. A layer of mulch to a minimum depth of three inches shall be installed in plant beds and around individual trees in turf areas.
- All screening shrubs shall be planted for proper operation of equipment being screened and/or per the requirements of the utility as necessary. All hedge material required for screening purposes shall be planted with branches touching. Adjust spacing as necessary and/or provide additional plants to provide an adequate screen.
- All ideas, designs and plans indicated or represented by this drawing are owned by and are the exclusive property of Cortada Landscape Design and may not be duplicated without authorization or used for other projects than the intended.
- Where there is a discrepancy either in quantities, plant names or specifications between the plan & plant list, the plan takes precedence.
- The Landscape Contractor shall exercise caution to protect all existing sod, electrical and irrigation. Any damage to the sod, electrical or irrigation shall be replaced or repaired to the original state by the Landscape Contractor at no additional cost to the owner.
- Tree, palm, accent and bed lines are to be located in the field and approved by the Landscape Architect / owner prior to installation.
- All trees must be pruned as per landscape architect's direction.
- Plant material shall not be planted in the root balls of any tree.

D. PERMITS & REGULATIONS

- Contractor(s) must obtain separate landscape, irrigation & tree relocation/removal permits from the city prior to the issuance of the first building permit for the project.
- Landscape contractor to call the city Landscape Inspector to schedule a pre-construction meeting prior to installation if required.

E. TREE REMOVAL

- Removal of any trees or palms will require a written "tree removal permit" from the local governing agency prior to removal. Non-native trees classified as "prohibited" trees may be exempt from the permit.

F. EXISTING TREES & RELOCATION

- Existing trees designated to remain shall be protected during all construction phases. Any trees or shrubs scarred or destroyed designated to remain will be replaced at the contractor's expense, with same species, size and quality.
- Existing plant material not shown on the plan and in conflict with new planting shall be evaluated at the time of new planting installation by the Landscape Architect. Trees & plant material indicated to be relocated with no new location provided in plans shall be moved to a location on site designated as a nursery holding area with the root ball protected from direct sunlight, maintained and irrigated until new location is determined.
- Prune trees to remove damaged branches, improve natural shape and thin out structure. Do not remove more than 15% of branches. Do not prune back terminal leader.
- Prune existing shrubs to remove damaged branches & improve natural shape.
- Existing trees to remain shall be trimmed per ANSI-A300 standards. Supervision of the trimming shall be performed by an ISA Certified Arborist to insure quality work.
- All existing trees shall be "lifted and thinned" to provide an 8' minimum clearance for sidewalks and pedestrian walkways and a 14' minimum clearance for roadways, driveways and all vehicular use areas.
- Prune trees as required / Indicated in walk-through to provide sunlight filtering.
- The plans call for relocation of several plants. High level of care should be exercised to assure that plants are not damaged or traumatized in the process and that they are promptly replanted upon being dug up.

G. SITE PREPARATION & GRADING

- Landscape contractor shall loosen & till compacted soils in all other planting areas of the project to provide for proper soil aeration for plant establishment.
- Planted areas shall be cleared of underground rocks, construction debris and other materials detrimental to the health of the plants. Lime rock base material shall be removed within planting pits and adjacent to pavement. Plant area soils shall be tested for pH before planting. Soils showing high (alkaline) pH (over 7.5) shall be removed and replaced with native soil having a pH range of 6.5 - 7.5, or modified as approved by Landscape Architect.
- Site preparation shall include the eradication & removal of any weeds, clean-up of any dead material, debris, and rubbish.
- General site and berm grading to +/- 1 inch (1") shall be provided by the general contractor. All finished site grading and final decorative berm shaping shall be provided by the Landscape Contractor.
- All planting beds shall be free of all rocks 1/2" or larger, sticks, and objectionable material including weeds, weed seeds. All lime rock shall be removed/cleaned down to the native soils.
- The Landscape contractor shall ensure the planting areas are at finish grade prior to installing plant materials. Grade shall be per plans, if not indicated, in any event drainage shall be directed away from structures U.O.N.
- Site preparation shall include the eradication and removal of any weeds, clean-up of any dead material and finish grading as per the specs.
- All trees and plant material to remain shall be protected during construction. Contractor shall install protective barriers such as "Tenax" orange safety fencing or similar, to be installed before the beginning of the project. Barriers shall be located to include the drip line of the trees, palms and plant material. The contractor shall take extra caution to prevent any damage to the trunk, root zones and grade.
- Final grade within planting areas to be 2" below adjacent paved areas or top of curb.
- All planting beds shall be shaped and sloped to provide proper drainage.

H. IRRIGATION

- The Landscape Contractor shall coordinate with the irrigation contractor if not the same and leave provisions for all individual trees in turf areas and all planting beds
- Landscape contractor to retro-fit automatic lawn irrigation system guaranteeing 100% coverage & maintain a 50% min. overlap to all landscaped areas. There shall be no over spray onto sidewalks.
- The contractor shall ensure that the irrigation system is operational and free of leaks prior to any planting. Plant material that is installed prior to the irrigation system being operational shall be watered by the contractor at his expense. Water for plant establishment should be included in the cost of the plant.
- All guidelines as outlined by the South Florida Water Management District (SWFMD) or water management district with jurisdiction shall be strictly adhered.
- Existing irrigation system shall be retrofitted to comply with those specifications as outlined above.

I. HARDCAPE & OTHER MATERIALS

- Face of trees and palms to be located a minimum of 2'-0" setback from all walkways, walls, and paved surfaces, unless otherwise indicated on the plans.

J. UTILITIES/CLEARANCES

- The contractor shall be responsible for determining the location of and avoid and protect utility lines, buried cables, and other utilities.
- Trees shall be placed a minimum of 5 ft. from underground utilities, unless otherwise approved in writing by Landscape architect and Owner.
- All shade trees to be planted min. of 15' from light poles. Unless otherwise approved in writing by Landscape architect and Owner.
- Landscape contractor shall contact the county, city and/or utility companies to locate all underground utilities or structures prior to digging. Landscape contractor shall repair all damage to underground utilities, and/or construction caused by utility damage, at no cost to the owner.
- All plant material symbols shown on landscape plan shall be considered diagrammatic and should be adjusted in the field by contractor to avoid all utilities, and all other obstructions.
- If / When digging in right of way needed: Two (2) full business days before digging, call toll free 1-800-432-4770, or 811, Sunshine State One Call of Florida, Inc. Notification Center. In addition, call the City's Utilities/Public Works Department. Contractors are responsible for coordinating with the owners and appropriate public agencies to assist in locating and verifying all underground utilities prior to excavation. All existing utilities shown on the plans are to be considered approximate and should be verified by the contractor prior to the start of work operations.
- Above & below ground utilities shall be verified & located in the field by the contractor prior to commencing work in the project area. The contractor shall examine available utility plans & confirm conflicts between indicated or located utilities & landscape work. The contractor shall then notify the Project Engineer of said conflicts & the Engineer will coordinate any necessary adjustments with the utility provider. Tree locations will be adjusted as necessary when in conflict with existing utilities.
- The final plant locations may be adjusted, as approved / directed by the Landscape Architect in writing, to accommodate utility compliance. Excavations within 5' of known utilities should be done by hand.
- Contractor shall familiarize himself with the location of and avoid and protect utility lines, buried cables, and all other utilities, noted or not, on plans.
- Root barriers shall be installed where required by local utility company or other regulating agencies.
- If / clearance and access shall be provided around all above ground or at grade meters and equipment.
- Landscape planting shall be in conformance with FPL guidelines for setbacks from overhead utility lines.
- Landscaping shall not interfere with light poles, fire hydrants, electrical/mechanical equipment access, signs, drainage structures, etc. Bring the attention of Landscape Architect any conflicts.

K. LANDSCAPE BACKFILL & SOIL AMENDMENT

- 6" top soil required around & beneath all root ball.
- All building construction material and foreign material shall be removed from the planting areas and void replaced with 50/50 mix fill soil or as per specifications on plans.
- Planting soil mix shall be delivered to the site in a clean loose and friable condition and is required around the root ball of all trees and palms, the top 6" of all shrubs and ground cover beds and top 2" of all sodded areas. This soil shall be tilled into the existing soil after the existing soil has been cleaned of all rocks, limestone and sticks. Recycled compost is encouraged as a soil amendment alternative.
- Planting soil to be weed free.

Groundcover planting beds: 4" depth planting soil spread in place - throughout.

Shrub and hedge planting areas: 6" depth planting soil spread in place - throughout.

Trees, palms, specimen plant material: 30" depth planting soil spread in place - or- to the depth of the root ball or container, whichever is greatest, throughout.

Building foundations shall be the same for a width of 36" from the building base.

Do not allow air pockets to form when backfilling. All trees shall be spiked in utilizing water and a tree bar.

L. PLANT SIZE & QUALITY

- Plant material shall conform to the standards for grade # 1 or better as given in the latest grades and standards for nursery plants, parts I and II by the Florida Department of Agriculture and consumer services or to the standards as given in the latest American Standard for Nursery Stock by the American National Standard Institute.
- All perimeter hedge material shall meet the minimum specified heights at the time of planting.
- All plant material must meet or exceed the minimum size requirements as specified on the plant list. Height specification governs over container size spread if both specifications given and cannot be met.
- All sizes shown for plant material on the plan are to be considered minimum. All plant material must meet or exceed these minimum requirements for both height and spread. Any other requirements for specific shape or effect as noted on the plan shall also be required for acceptance. All trees to be single trunked, unless otherwise noted on the plans.
- All trees designated as single trunk shall have a single, relatively straight, dominant leader, proper structural branching and even branch distribution. Trunks on palms shall be uniform in thickness for the entire length of the palm and shall not taper off to disproportionate thinness towards the crown. Trees with bark inclusion, tipped branches, and co-dominant trunks will not be accepted. Trees with girdling, circling and/or plugging roots will be rejected.
- Use nursery grown plant materials that complies with all required inspection, grading standards, and plant regulations in accordance with the latest edition of Florida Department of Agriculture, "Grade & Standards for Nursery Plants".
- All plant material must meet or exceed the minimum size requirements as specified on the plant list.
- All substitutions must be approved by the Architect and Owner.
- Trees, palms, shrubs, ground covers:

Plant species and sizes shall conform to those indicated on the drawings. All nursery stock shall be in accordance with grades and standards for nursery plants parts I & 2, latest edition published by the Florida Department of Agriculture and Consumer Services, unless specified otherwise. All plants shall be Florida grade number 1 or better as determined by the Florida Division of Plant Industry and tightly knotted, so trained or favored in its development that first appearance is unquestionable and it is outstandingly superior in form, number of branches, compactness and symmetry. All plants shall be freshly dug, sound, healthy, vigorous, well branched and free of disease and insect eggs and larvae and shall have adequate root systems. Trees and palms shall be uniform in size and shape. All materials shall be subject to approval by the landscape architect. The plants furnished shall be normal for the variety and Florida number 1. Plants shall be pruned prior to delivery only upon the approval of the Landscape Architect.

10. All containers grown material shall be healthy, vigorous, well-rooted plants and established in the container in which they are sold. The plants shall have tops of good quality and be in a healthy growing condition. An established container grown plant shall be transplanted into a container and grown in that container sufficiently long enough for the new fibrous roots to have developed so that the root mass will retain its shape and hold together when removed from the container.

11. Field grown trees and palms previously root pruned shall obtain a root ball with

sufficient roots for continued growth without resulting shock.

12. Root suckers on any tree are not acceptable and must be properly pruned.

13. Contractor shall coordinate with Landscape Architect and Owner to obtain prior approval for the selection of the specific specimens of all palms and any trees of more than 6 feet in height.

M. PLANTING NOTES

- All synthetic burlap, synthetic string or cords, or wire baskets shall be removed before any trees are planted. All synthetic tape (i.e. tagging tape, nursery tape) shall be removed from trunks, branches, etc. before inspection. The top 1/3 of any natural burlap shall be removed or tucked into the planting hole before the trees are back filled.
- All "groundcover" requires 75% coverage and 100% within 3 months of installation. Bring to the attention of Landscape Architect in writing before commencing if this is not achievable with the design.
- Set trees no deeper than it was in its original growing condition with the top of the root ball even with, or slightly higher (+/- 1") than the finished grade.
- All burlap, string, cords, wire baskets, plastic or metal containers shall be removed from the root balls before planting. Remove all bamboo and metal nursery stakes. Remove all tagging tape.
- All trees/palms shall be planted so the top of the root ball, root flare are slightly above final grade. Shrub material shall be planted such that the top of the plant ball is flush with the surrounding grade.
- All trees and palms shall be staked per accepted standards by the Florida Nurserymen & Growers Association (FNGA) Nailing into trees and palms for any reason is prohibited and the material will be rejected. Please refer to the planting details.
- The location of plants, as shown on the plans, is approximate. The final locations may be adjusted slightly to accommodate unforeseen field conditions, to comply with safety setback criteria, to avoid creating unsafe sight conditions, or as otherwise directed or approved by the Landscape Architect / owner in writing. All other location adjustments to the layout are to be approved in advance in writing by the Landscape Architect and owner.
- All trees, new or relocated, to be staked and guyed as detailed.
- Layout shrubs to create a continuous smooth front line and fill in behind.
- Excavate pit or trench to 1-1/2 times the diameter of the balls or containers or 1'-0" wider than the spread of roots and 3" deeper than required for positioning at proper height. Compact a layer of topsoil in bottom before placing plants. Backfill around plants with planting mixture, compacted to eliminate voids and air pockets. Form grade slightly dish and bermed at edges of excavation. Apply 3" of mulch.
- Groundcover and shrubs to be spaced in a uniform and consistent pattern.
- All mechanical equipment, irrigation pumps, FPL transformers, pool pumps, etc. shall be screened on a minimum of three sides by landscape shrubs.
- Contractor shall not mark or scar trunks in any fashion.

N. SOD

- All areas disturbed during construction shall be sodded with St. Augustine "Floratam" unless otherwise noted. Landscape Contractor to supply & install 2" soil layer 50/50 mix blanket for all new sod areas.
- All open areas not covered by trees, palms, shrubs, vines, ground covers or existing sod in good condition to remain, shall receive Sphagnum Secundatum, St. Augustine "Palmetto" sod, whether labeled on the plans or not, unless a different species is indicated on the planting plan. All s.t. if noted shall be approximate; it is the contractor's responsibility to do his take off and sod all open areas. It shall be the responsibility of the contractor to include in the bid, the repair of any existing sod which may be damaged during construction.
- Sod shall be of the species indicated on the plans (St. Augustine "Floratam") if not indicated, strongly rooted, free from weed, fungus, insects and disease. Contractor shall sod all areas as indicated on the plans or as directed. Contractor shall be paid by the total sodded area, x the unit price submitted (field verified).
- Sod type specified on plant list shall be machine stripped no more than 24 hours prior to laying.
- Lay sod strips with tight joints, do not overlap, stagger strips to offset joints in adjacent courses. Work sifted soil mix into minor cracks between pieces of sod and remove excess soil deposits from sodded areas. Sod on slopes greater than 3:1 shall be immediately staked after planting.

O. INSPECTION & ACCEPTANCE

- A mandatory inspection of the planting bed layout is required before planting.
- Onsite plant deliveries shall occur on Monday through Friday only unless otherwise directed by the Landscape Architect. The contractor shall ensure that plant material is delivered undamaged from transportation or digging operations. The Landscape Architect may reject material that has been damaged or rendered unacceptable due to relocation or transportation from the point of origin. All plant material shall be available for inspection & approval by the Landscape Architect prior to final installation.
- There shall be one final inspection for approval by each of the presiding governing agency, Landscape Architect and owner. Contractor shall insure that the plans, details, specifications and notes have been adhered to and that the landscape and irrigation installation is compliant to all items as directed on the plans prior to scheduling of the final inspection.
- Upon completion of the work, the Landscape Contractor shall notify the Landscape Architect and request a final inspection. Any items that are judged incomplete or unacceptable by the Landscape Architect or owner shall be promptly corrected by the Landscape Contractor.
- No substitution of plant material, type or sizes will be permitted without prior written authorization from the Landscape Architect and owner.
- To obtain final payment, Contractor must provide release of all mechanic's liens and material men's liens.

P. FERTILIZING

- All landscape materials shall be fertilized upon installation. See details sheet.
- Fertilizer in backfill mixture for all plants shall consist of Milorganite activated sludge mixed with the backfill at a rate of not less than 50 lbs. per cubic yard.
- Fertilizer for trees and shrubs may be tablet form or granular. Granular fertilizer shall be uniform in composition, dry and free-flowing. This fertilizer shall be delivered to the site in the original unopened bags, each bearing the manufacturer's statement of analysis, and shall meet the following minimum requirements: 16% nitrogen, 7% phosphorus, 12% potassium, plus iron. Tablet fertilizer (agriflorm or equal) in 21 gram size shall be applied at the following rates

Plant size	16-7-12	agriflorm tablets (21 grams)
1 gal.	1/4 lb.	1
3 gal.	1/3 lb.	3
7-15 gal.	1/2 lb.	6
1'-6" caliper	2 lbs. /1" caliper	2 per 1" caliper
6" and larger	3 lbs. /1" caliper	2 per 1" caliper

4. "Florida east coast palm special" shall be applied to all palms at installation at a rate of 1/2 lb. per inch of trunk unless otherwise specified.

Q. MULCH

- All planting beds shall be mulched to a depth of 3" with an organic mulch approved by Landscape Architect. No heavy metals, such as arsenic, etc. are to be contained in the mulch. The contractor shall provide certification if requested or proof that all mulch is free of heavy metals or similar environmental contaminants.
- Shredded approved organic mulch to be used beyond trunk in all directions & throughout all hedges & plant material.
- All trees in sodded areas shall have a clean cut 4" diameter mulch ring. Cypress, red, gold and green mulch is prohibited.
- All proposed trees located within graded areas shall have a minimum three foot mulch ring with a three inch separation from the trunk of the tree.

R. WATERING

- All plant material shall be watered in thoroughly at the time of planting.
- It is the sole responsibility of the Landscape Contractor to insure that all new plantings receive adequate water during the installation and until completion of contract. Deep watering of all new trees and palms and any supplemental watering that may be required to augment natural rainfall and site irrigation is mandatory to insure proper plant development and shall be provided by Contractor as a part of this contract.

S. CLEAN UP

- The Landscape Contractor is responsible for maintaining all landscape planting areas until final acceptance of the owner.
- The contractor is responsible for mowing the entire project during planting & establishment periods, based on mowing project once a month from October to April, & twice a month from April to October.
- Any excess soil, undesired stones or debris resulting from landscape operations shall be removed promptly, keeping the site clean as work progresses.
- The Landscape Contractor shall at all times keep the premises free from accumulation of waste materials or debris caused by his crews during the performance of the work. Upon completion of the work, the contractor shall promptly remove all waste materials, debris, unused plant material, empty plant containers, and all equipment from the project site.

T. MAINTENANCE

- Landscape Contractor to return to job site 12 months after tree bracing and remove all tree braces. Owner may choose to retain 5% of payment to ensure compliance.
- The Landscape Contractor shall water, mulch, weed, prune, and otherwise maintain all plants, including sod, until completion of contract or acceptance by landscape architect. Settled plants shall be reset to proper grade, planting saucers restored, and defective work corrected.
- Trees and shrubs shall be maintained to keep clearance of stop signs, safety clearance for visibility at intersection traffic.

U. GUARANTEE & REPLACEMENT

- By accepting the contract, the Contractor is thereby guaranteeing all plant materials and workmanship for a period of not less than ninety (90) days from the time of final acceptance by the owner. Contractor shall replace any plants which die or wither within such 90 days with healthy plants that meet specifications of the same species and size without additional cost to the owner unless such death or withering is due to Owner's failure to do ordinary maintenance on such plants after final acceptance in accordance with any maintenance instructions given by Landscape Architect for such plants. Any plant materials damaged by lightning, storms, freeze damage or other "acts of God" as well as plants damaged by vehicles, vandalism or neglect are not included in this replacement agreement. If requested, the Landscape Architect may act as a mediator between owner and Landscape Contractor on a time material basis. "Plants" includes all trees, palms, shrubs, grass and other plants provided or planted by Contractor.

T. MISCELLANEOUS

- Contractor shall be responsible for obtaining and cost of all permits.
- Contractor to have liability insurance including Owner and Landscaper as insured's in excess of \$10,000 as well as worker's insurance.
- All work to be done in a professional and workmanlike manner.
- Contractor understands that an important element of the design of this project is symmetry and shall use care and instruct the working crews accordingly. In the event of any doubt as to how to execute the plans, Contractor shall immediately consult with Architect and/or Owner.
- No change order shall be valid, due or paid unless it is approved by Owner in writing in advance.
- These notes shall be an integral part of the contract of Contractor and shall be deemed incorporated therein by reference. In the event of a conflict among the terms among the plans and these notes, the terms of this document shall control.

INDEX OF LANDSCAPE ARCHITECTURE PLANS		
#	NAME	DESCRIPTION
1. LN-1	COVER SHEET / NOTES / INDEX	
2. L-1	LANDSCAPE PLAN GROUND LEVEL	
3. L-2	LANDSCAPE PLAN ROOF TOP	
4. LD-1	LANDSCAPE DETAILS	
5. TD-1	TREE DISPOSITION PLAN	
6. TD-2	TREE DISPOSITION SCHEDULE/DETAILS	
7. IRR-1	IRRIGATION PLAN GROUND LEVEL	
8. IRR-2	IRRIGATION PLAN ROOF TOP	
9. IRR-3	IRRIGATION DETAILS	



CALL 811 BEFORE YOU DIG
F / WHEN DIGGING IN THE RIGHT-OF-WAY

CLEVELAND HOMES LLC
1604-1606 CLEVELAND ST
HOLLYWOOD, FL 33020

Cortada
LANDSCAPING DESIGN
TEL: (305) 321-4350
design@landscapingmiami.com
91 NW 154 ST
MIAMI FL 33169

PROJECT TEAM:
LANDSTONE DESIGN INC
TEL: (818) 856.9556
info@landstonedesign.com

DERRICK LANGEL, RLA, ISA
FLORIDA REG. NO. LA6667045

SCALE: INDICATED

DRAWN BY:

CHECKED BY:

DATE DESCRIPTION



3-09-17

PROJECT NO.
SHEET NO.

CLEVELAND HOMES LLC

1604-1606 CLEVELAND ST
HOLLYWOOD, FL 33020

LANDSCAPE PLAN GROUND LEVEL



PLANT SCHEDULE

TREES	CODE	QTY	BOTANICAL NAME / COMMON NAME	CONT	CAL	SIZE
BS	12	1	Bursera simaruba / Gumbo Limbo	B & B	2" Cal	12' HT, 6' Spr
CS	2	2	Conocarpus erectus 'Sericeus' / Silver Buttonwood	B & B	2" Cal	12' HT, 6' Spr
RE	2	2	Roxanea elata / Florida Royal Palm	Transplanted	15" Cal	50' HT, 15' Spr
CI	144	144	Chrysobalanus icaco Red Tip' / Red Tip Cocoplum	3 gal	24" HT, 24" O.C.	SPRD
HD	18	18	Helianthus debilis / Cucumberleaf Sunflower	1 gal	12" HT x 12" SPR, 12" O.C.	
MC	158	158	Muhlenbergia capillaris / Pink Muhy	3 gal	24" HT, 24" O.C.	
VO	58	58	Viburnum obovatum / Walter's Viburnum	3 gal	24" HT, 24" O.C.	
SHRUB AREAS	CODE	QTY	BOTANICAL NAME / COMMON NAME	CONT	HGT	SPRD
MC2	78	78	Muhlenbergia capillaris / Pink Muhy	3 gal		

SPECIFIED SIZES ARE MINIMUM REQUIREMENTS FOR MATERIAL. CONTAINER SIZE IS REFERENCE ONLY.
SOD = ST AUGUSTINE FLORATAM - VERIFY SQUARE FOOTAGE IN FIELD FOR FULL COVERAGE OF PROPERTY.

MISC MATERIALS
MULCH
QUANTITY BY CONTRACTOR TO PROVIDE COVERAGE PER PLANT NOTES AND DETAILS.

LANDSCAPE CODES FOR CITY OF HOLLYWOOD

ZONE: RM-12 DISTRICT
SITE CALCULATIONS
AREA: 16,699.5 SF.
TOTAL LOT AREA: 16,699.5 SF.
BUILDING FOOTPRINT: 1,0170.5 SF.
V.I.A DRIVEWAY / PARKING AREA: 2,287.49 SF.
TOTAL PERVIOUS AREA REQUIRED (LANDSCAPE 40%): 6,723.5 SF.
ROOF: 600 SF
GROUND: 6,158 SF
TOTAL PERVIOUS AREA PROVIDED: 6,758 SF

LANDSCAPE CODE CALCULATIONS

	REQUIRED	EXISTING / RELOCATED	NEW	TOTAL PROVIDED
PERIMETER LANDSCAPE & BUFFERS:				
1 STREET TREE / 50 LINEAL FEET OF STREET FRONTPAGE Cleveland St. 120 LF 50 = 3 SW 16th Avenue. 140 LF 50 = 3	3 TREES	3 TREES	3	3
A 5' LANDSCAPE BUFFER WITHIN REQ. SETBACK 1 TREE / 20 LF. OF RECL. BUFFER AREA.				
WHEN ABUTTING OR ACROSS ALLEY FROM RESIDENTIAL ZONING DISTRICT A PERIMETER LANDSCAPE BUFFER MUST BE INCLUDED WITHIN THE REQUIRED SETBACK AREA.	6 TREES	3 TREES	1	7
1 TREE / 20 LF. OF RECL. BUFFER AREA WEST 120 LF / 20 = 6 SOUTH 60 LF / 20 = 3				
INTERIOR LANDSCAPE FOR V.I.A. TERMINAL ISLAND AT THE END OF EACH ROW OF PARKING SPACES. EACH ISLAND SHALL CONTAIN 190 S.F. MIN. OF PERVIOUS AREA. 1 TREE PER ISLAND.	2 TREES	0	2	2
LOTS WITH A WIDTH OF MORE THAN 50'; 25% OF TOTAL SQUARE FOOTAGE OF V.I.A. SHALL BE LANDSCAPED	821.87 SF			821.87 SF
OPEN SPACE: ALL PERVIOUS AREAS MUST BE LANDSCAPED WITH GRASS, GROUD COVER AND/ OR SHRUBBRY				YES
A MINIMUM OF 1 TREE PER 1,000 S.F. OF PERVIOUS AREA OF PROPERTY 123 S.F. / 1,000 = 7 TREES	7 TREES	13	0	13
DESIGN REVIEW: ALL LANDSCAPE PROJECTS INCLUDING DECKS AND PATIOS THAT CONTAIN 10,000 S.F. OR MORE SHALL COMPLY WITH DESIGN REVIEW GUIDELINES FOR LANDSCAPING		Yes		Yes
IRRIGATION: PROVIDE 100% IRRIGATION COVERAGE OF AN AUTOMATIC SPRINKLER SYSTEM DESIGNED AND CONSTRUCTED IN ACCORDANCE WITH THE CITY OF HOLLYWOOD CODE REGULATION OF THE SOUTH FLORIDA WATER MANAGEMENT DISTRICT.		YES		YES
TOTAL	24 TREES	17	14	31 TREES

NATIVE SPECIES REQUIREMENT

60% Native Tree	PROPOSED NATIVE TREES
	TOTAL PROPOSED TREES = 94% NATIVE TREES PROVIDED
50% Shrubs	44% TOTAL PROPOSED SHRUBS
	45% PROPOSED NATIVE SHRUBS 100% NATIVE SHRUBS PROVIDED

SPECIES MIX

24 TREES = MINIMUM 4 SPECIES	4
Maximum 50% Palms to fulfill Requirement: 13 Trees / 11 Palms = 46% Palms	4

TOTAL ON-SITE TREES 31 TREES

Specimen Palms	15 Existing Royal Palms
Non-specimen Palms	7 Existing Adonidia Palms = 2 trees @ 3:1 ratio

DERICK LANGEL, RLA, ISA
FLORIDA REG. NO. LA6667045


SCALE: INDICATED

DRAWN BY:

CHECKED BY:

DATE: 03-09-17

DESCRIPTION:



AFTER ESTABLISHED, THE PROPOSED MUHLY GRASS DOES NOT NEED IRRIGATION EXCEPT IN PROLONGED PERIODS WITHOUT RAIN.

TREES		CODE	QTY	BOTANICAL NAME / COMMON NAME	CONT	CAL	SIZE
		BS	12	Bursera simaruba / Gumbo Limbo	B & B	2"Cal	12' HT, 6' Spr
		CS	2	Conocarpus erectus 'Sericeus' / Silver Buttonwood	B & B	2"Cal	12' HT, 6' Spr
		RE	2	Roystonea elata / Florida Royal Palm	Transplanted	15"Cal	50' HT, 15' SPR
SHRUBS		CODE	QTY	BOTANICAL NAME / COMMON NAME	CONT	HGT	SPRD
		CI	144	Chrysobalanus icaco 'Red Tip' / Red Tip Cocoplum	3 gal	24" HT, 24" O.C.	
		HD	18	Helianthus debilis / Cucumberleaf Sunflower	1 gal	12" HT X 12" SPR, 12" O.C.	
		MC	158	Muhlenbergia capillaris / Pink Muhy	3 gal	24" HT, 24" O.C.	
		VO	58	Viburnum obovatum / Walter's Viburnum	3 gal	24" HT, 24" O.C.	
SHRUB AREAS		CODE	QTY	BOTANICAL NAME / COMMON NAME	CONT	HGT	SPRD
		MC2	78	Muhlenbergia capillaris / Pink Muhy	3 gal		

SPECIFIED SIZES ARE MINIMUM REQUIREMENTS FOR MATERIAL. CONTAINER SIZE IS REFERENCE ONLY.
SOD - ST AUGUSTINE FLORATAM - VERIFY SQUARE FOOTAGE IN FIELD FOR FULL COVERAGE OF PROPERTY.

MISC MATERIALS
MULCH QUANTITY BY CONTRACTOR TO PROVIDE COVERAGE PER PLANT NOTES AND DETAILS.

CLEVELAND HOMES LLC

1604-1606 CLEVELAND ST
HOLLYWOOD, FL 33020

Cortada
LANDSCAPING DESIGN

TEL: (305) 321.4350
design@landscapingofmiami.com
91 NW 154 ST
MIAMI FL 33169

PROJECT TEAM:
LANDSTONE DESIGN INC
TEL: (818) 856.9556
info@landstonedesign.com

LANDSCAPE PLAN ROOF TOP

NORTH

0 8 16 24 32 feet
1/8" = 1'-0"

SEAL
DERICK LANGEL, RLA, ISA
FLORIDA REG. NO. LA6667045




SCALE: INDICATED
DRAWN BY:
CHECKED BY:
DATE DESCRIPTION
03-09-17

PROJECT NO.
SHEET NO.
L-2

PROJECT #:	PROJECT NAME: LOBA INVESTMENT GROUP									
	TREE #	TREE NAME	SCIENTIFIC NAME	DBH IN.	HT. FT.	CNPY. FT.	TREE CONDITION	DISPOSITION	DBH LOSS IN.	COMMENTS
001	ROYAL PALM	"Roystonea elata"	16	45	15	GOOD	REMAIN			REFER TO TREE PROTECTION DETAIL AND/OR RECOMMENDATIONS
002	ROYAL PALM	"Roystonea elata"	16	50	15	GOOD	REMAIN			REFER TO TREE PROTECTION DETAIL AND/OR RECOMMENDATIONS
003	ROYAL PALM	"Roystonea elata"	15	50	15	GOOD	REMAIN			REFER TO TREE PROTECTION DETAIL AND/OR RECOMMENDATIONS
004	ROYAL PALM	"Roystonea elata"	15	60	15	GOOD	REMAIN			REFER TO TREE PROTECTION DETAIL AND/OR RECOMMENDATIONS
005	ROYAL PALM	"Roystonea elata"	15	50	15	GOOD	RELOCATE			DOUBLE TRUNK REFER TO TREE RELOCATION DETAIL / NOTES
006	ROYAL PALM	"Roystonea elata"	16	55	15	GOOD	REMAIN			REFER TO TREE PROTECTION DETAIL AND/OR RECOMMENDATIONS
007	ROYAL PALM	"Roystonea elata"	16	55	15	GOOD	REMAIN			REFER TO TREE PROTECTION DETAIL AND/OR RECOMMENDATIONS
008	ROYAL PALM	"Roystonea elata"	16	55	15	GOOD	REMAIN			DOUBLE TRUNK REFER TO TREE PROTECTION DETAIL AND/OR RECOMMENDATIONS
009	ROYAL PALM	"Roystonea elata"	16	55	15	GOOD	REMAIN			MULTI TRUNK REFER TO TREE PROTECTION DETAIL AND/OR RECOMMENDATIONS
010	CHRISTMAS PALM	"Veitchia merrillii"	5	14	7	GOOD	REMAIN			REFER TO TREE PROTECTION DETAIL AND/OR RECOMMENDATIONS
011	SCHEFFLERA	"Schefflera actinophylla"	10	15	8	GOOD	REMOVE			INVASIVE MULTI TRUNK TREE NO MITIGATION REQUIRED
012	CHRISTMAS PALM	"Veitchia merrillii"	6	14	8	GOOD	REMAIN			REFER TO TREE PROTECTION DETAIL AND/OR RECOMMENDATIONS
013	SCHEFFLERA	"Schefflera actinophylla"	20	15	10	GOOD	REMOVE			INVASIVE MULTI TRUNK TREE NO MITIGATION REQUIRED
014	CHRISTMAS PALM	"Veitchia merrillii"	6	15	8	GOOD	REMAIN			DOUBLE TRUNK REFER TO TREE PROTECTION DETAIL AND/OR RECOMMENDATIONS
015	ROYAL PALM	"Roystonea elata"	16	55	15	GOOD	REMAIN			REFER TO TREE PROTECTION DETAIL AND/OR RECOMMENDATIONS
016	ROYAL PALM	"Roystonea elata"	16	55	15	GOOD	REMAIN			REFER TO TREE PROTECTION DETAIL AND/OR RECOMMENDATIONS
017	ROYAL PALM	"Roystonea elata"	16	45	15	GOOD	REMAIN			REFER TO TREE PROTECTION DETAIL AND/OR RECOMMENDATIONS
018	ROYAL PALM	"Roystonea elata"	16	45	15	GOOD	REMAIN			REFER TO TREE PROTECTION DETAIL AND/OR RECOMMENDATIONS
019	SCHEFFLERA	"Schefflera actinophylla"	18	16	12	GOOD	REMOVE			INVASIVE MULTI TRUNK TREE NO MITIGATION REQUIRED
020	CHRISTMAS PALM	"Veitchia merrillii"	5	14	7	GOOD	REMAIN			REFER TO TREE PROTECTION DETAIL AND/OR RECOMMENDATIONS
021	CHRISTMAS PALM	"Veitchia merrillii"	5	15	7	GOOD	REMAIN			REFER TO TREE PROTECTION DETAIL AND/OR RECOMMENDATIONS
022	CHRISTMAS PALM	"Veitchia merrillii"	5	15	7	GOOD	REMAIN			REFER TO TREE PROTECTION DETAIL AND/OR RECOMMENDATIONS
023	CHRISTMAS PALM	"Veitchia merrillii"	6	15	8	GOOD	REMAIN			REFER TO TREE PROTECTION DETAIL AND/OR RECOMMENDATIONS
024	ROYAL PALM	"Roystonea elata"	15	40	15	GOOD	RELOCATE			REFER TO TREE RELOCATION DETAIL / NOTES
025	ROYAL PALM	"Roystonea elata"	16	35	15	GOOD	REMAIN			REFER TO TREE PROTECTION DETAIL AND/OR RECOMMENDATIONS

CONDITION: Excellent = 90-100%, Good= 75-85 %, Fair= 60-70%, Poor= 40-60%, Very Poor= 10-35%

EXISTING TREE DISPOSITION LIST & TREE REPLACEMENT CHART



TREE PROTECTION ZONE (TPZ)
SCALE: NTS

CLEVELAND HOMES LLC
1604-1606 CLEVELAND ST
HOLLYWOOD, FL 33020

Cortada
LANDSCAPING DESIGN
TEL: (305) 321.4350
design@landscapingofmiami.com
91 NW 154 ST
MIAMI FL 33169

PROJECT TEAM:
LANDSTONE DESIGN INC
TEL: (818) 856.9556
info@landstonedesign.com

DERICK LANGEL, RLA, ISA
FLORIDA REG. NO. LA6667045

SEAL
SCALE: INDICATED
DRAWN BY:
CHECKED BY:
DATE DESCRIPTION
03-09-17
PROJECT NO.
SHEET NO.

TD-2




ALTA/ACSM LAND TITLE SURVEY

PAGE 1 OF 2

FOLIO: 5142-10-20-0160

1604-1606 CLEVELAND STREET
HOLLYWOOD FL 33020



VICINITY MAP

NOT TO SCALE




AERIAL MAP

NOT TO SCALE

OWNER: CLEVELAND HOMES LLC
PROPOSED INSURER: CLEVELAND HOMES LLC,
A LIMITED LIABILITY COMPANY
EFFECTIVE DATE - MAY 23, 2016 AT 11:00 PM
TITLE COMMITMENT / POLICY NO. / FUND FILE NO. / : 319515

INDEX OF DRAWINGS

1 OF 2 COVER SHEET / LOCATION
2 OF 2 ALTA/ACSM LAND TITLE SURVEY
SURVEYOR NOTES



ATTACHMENT B
Land Use & Zoning Map



DEVELOPMENT SERVICES
PLANNING

Legend

-  Subject Property
-  MRES

CLEVELAND ST

N 16TH AVE

RM-12

0 12.5 25 50 Feet

