



Address 5440 NW 33rd Avenue
Suite 108
Fort Lauderdale FL 33309
Phone 305.978.4232
Fax N/A
E-mail mario.bermudez@carrier.com

Contact Name Joshua Collazo
Account CITY OF HOLLYWOOD

Site Address 3000 North 69th Avenue
Hollywood, FL
33024

Estimate Date 02/19/2025
Valid through: 03/31/2025 or until 410a inventory lasts

Quote Number 01568759
01568771
01568753
01568777

Job Description City of Hollywood - Driftwood Park #2, 4, 5 w/ adder for #1 & #3



Carrier Contract No. 070121-CAR
HVAC Systems with Related Products and Services

Please note we are past the deadline to replenish these in stock R410A models so we are working on a first come first served basis. New low ozone depleting R-454b refrigerant units are also available with extended lead times and increased cost. Once the stock 410A units are sold, we will have to reprice to go with the 454B refrigerant models. This proposal is for units with 410A.

CU 2, 4, 5

- 460-3-60 - R410A
- Single Circuit
- 2-Stage Cooling
- Temp Sensor In Control Box
- Pre-Coated Al/Cu Condenser Coil
- Electro-Mechanical Control
- 1st Year Unit Parts Warranty
- 2nd – 5th Year Compressor Parts Warranty

FCU 2, 4 ,5

- 460/3/60 - R410A
- 2 Speed - Vane Axial Fan (AHU 2, 4)
- 2 Speed VDF Fan Controller (AHU 5)
- Electro-Mechanical Unit Control Board
- Electric Heater
- 1st Year Unit Parts Warranty

Scope:

- Isolate all energy sources and lock-out tag-out
- Set up any necessary rigging to safely perform the proposed work
- Disconnect, remove, and disposed of existing air handlers and condenser for A/C systems 2, 4 and 5
- Flush existing refrigerant lines with Rx11-flush so they can be reused with new refrigerant
- Receive and prepare new system for installation at our warehouse and deliver to jobsite
- Install new split systems using existing ducts as well as existing electrical and refrigerant lines
- Supply and install new auxiliary overflow safety switches
- Deliver and set new condensing units onto existing concrete pads
- Set new AHUs onto existing stands
- Insulate any new refrigerant piping with ¾" wall Armaflex
- All brazing will be done under nitrogen purge
- Cap existing refrigerant lines and pressurize with dry nitrogen to 350 psi to check for leaks
- Dehydrate refrigerant circuits to < 500 microns and charge with new refrigerant
- Start up to ensure proper operation of new systems
- Clean work area and check out with customer's approval

Exclusions / Clarifications:

This proposal includes wind-load, and mechanical permits processing and acquisition but not permit fees by the bldg. dept. Permit fees will be passed through at cost x1.35 or can be paid directly by the city. Fire alarm/smoke detector addition/integration or any other system controls integration is not included. Not included in this proposal is any code upgrades, painting, drywall patching, temporary cooling or fireproofing. Also not included in this proposal is any labor outside our normal business hours. In addition, any alterations or deviation from the above specifications involving extra cost, will be executed only upon written orders, and will become an extra charge over and above this proposal's price. If any leaks are found in the existing refrigerant lines, a separate proposal will be presented to address the required repairs. Customer's fire life safety vendor will need to be present for final inspection.

Total Quoted Price

SOURCEWELL Total Turkey Price Split Systems #2, #4, & #5:	\$100,880.00
+Adder for Extended 5yr Parts & Labor Warranty:	+\$12,210.00
+Adder for Turnkey Split Systems #1 & #3:	+\$31,750.00
There is no extended warranty options for #1 & #3	N/A

This proposal is valid for 30 days from the date of proposal. Carrier's terms and conditions will govern in lieu of any other terms and conditions contained in any resulting Purchase, Order, Contract, Agreement, etc. Carrier would like to thank you for the continuing opportunity to be of service.

Sincerely,

Mario John Bermudez

Carrier Commercial Service

Title

Customer Acceptance (signature)

Date

Purchase Order