PLANNING DIVISION



2600 Hollywood Boulevard Room 315

File No. (internal use only):

GENERAL APPLICATION



APPLICATION TYPE (CHECK ONE):	
□ Technical Advisory Committee □ Historic Preservation Board	
☐ City Commission ☐ Planning and Development Board	
Date of Application:	
Location Address: Southwest Corner SR 84 and SW 30th Avenue	
Lot(s): Parcel A Block(s): Subdivision: Port 95 Commerce Pa	rk
Folio Number(s): 5042 29 40 0010	
Zoning Classification: C-4 Commercial Land Use Classification: Commercial	
Existing Property Use: Vacant Sq Ft/Number of Units: 0/0	
Is the request the result of a violation notice? () Yes (X) No If yes, attach a copy of violation.	
Has this property been presented to the City before? If yes, check all that apply and provide File Number(s) and Resolution(s):	
☐ Economic Roundtable ☑ Technical Advisory Committee ☐ Historic Preservation Board ☐ City Commission ☐ Planning and Development	
Explanation of Request: Site plan approval for a proposed Cumberland Farms	
convenience store with fuel pumps and associated parking lot improvemen	ts
Number of units/rooms: Sq Ft: 6,425	
Value of Improvement: \$1,000,000 Estimated Date of Completion: 12/2018	
Will Project be Phased? () Yes (X)No If Phased, Estimated Completion of Each Phase	
Name of Current Property Owner: West Pond Associates LLC	
Address of Property Owner: 100 S. Pointe Drive, #TH3, Miami Beach, FL 33139	
Telephone: Fax: Email Address:	
Name of Consultant/Representative/Tenant (circle one): Address: Fort Lauderdale, FL 33334 Telephone: 954-202-7000 Telephone: 954-202-7000	
Address: Fort Lauderdale, FL 33334 Telephone: 954-202-7000	
Fax: 954-202-7070 Email Address: mtroxell@thomaseg.com	
Date of Purchase: Is there an option to purchase the Property? Yes () No ()	
If Yes, Attach Copy of the Contract.	
List Anyone Else Who Should Receive Notice of the Hearing:	
Address: Email Address:	
Liliali Address.	

CERTIFICATION OF COMPLIANCE WITH APPLICABLE REGULATIONS


The applicant/owner(s) signature certifies that he/she has been made aware of the criteria, regulations and guidelines applicable to the request. This information can be obtained in Room 315 of City Hall or on our website at www.hollywoodfl.org. The owner(s) further certifies that when required by applicable law, including but not limited to the City's Zoning and Land Development Regulations, they will post the site with a sign provided by the Office of Planning and Development Services. The owner(s) will photograph the sign the day of posting and submit photographs to the Office of Planning and Development Services as required by applicable law. Failure to post the sign will result in violation of State and Municipal Notification Requirements and Laws.


(I)(We) certify that (I) (we) understand and will comply with the provisions and regulations of the City's Zoning and Land Development Regulations, Design Guidelines, Design Guidelines for Historic Properties and City's Comprehensive Plan as they apply to this project. (I)(We) further certify that the above statements and drawings made on any paper or plans submitted herewith are true to the best of (my)(our) knowledge. (I)(We) understand that the application and attachments become part of the official public records of the City and are not returnable.

Signature of Current Owner:	Date: <u>9/30/201</u> 7
PRINT NAME: LOUIS Paolino	Date: 9/30/2017
Signature of Consultant/Representative:	Date: 10/4/2017
PRINT NAME: Michael Troxell/Thomas Engineering Group	Date: (0/4/2017
Signature of Tenant:	Date: 10/4/2017
PRINT NAME: Michael Troxell/ Authorized Representative, Cumberland Farm	s, Inc. Date: 10/4/2017
Current Owner Power of Attorney	
I am the current owner of the described real property and that I am aware of the site plan approval for the Cumberland Farms store to my property, which is hereby made by Michael Troxell / Thomas Engineering Group to be my legal representative before the Committee) relative to all matters concerning this application.	y me or I am hereby authorizing
ANDREW ROTH OF 116348 MY COMMISSION # FF 116348 EXPIRES: April 24, 2018	ture of Current Owner
Bonded Thru Budget Notary Services	<u>uis Paulino, manager</u> Name West PandAsso adtes U.C.
State of Florida April 24, 2018 My Commission Expires: (Check One) Personally known to me; OR Produce	


SITE DEVELOPMENT DRAWINGS FOR:







VICINITY\AERIAL MAP



LOCATION MAP

Red Carpet Inn Airport / Cruise Port COPYRIGHT 2010 MICROSOFT CORPORATION 2010 NAVTEO

SHEET INDEX

COVER SHEET	CFG01.0
BOUNDARY & TOPOGRAPHIC SURVEY	CFG02.0
SITE PLAN	CFG04.0
LANDSCAPE PLAN	CFG08.0
TREE DISPOSITION	CFG08.1
LANDSCAPE DETAILS	CFG08.2
LANDSCAPE GENERAL NOTES	CFG08.3
PLANS BY HARRISON FRENCH & ASSOCIATES	
GROUND FLOOR PLAN	A-101
EXTERIOR ELEVATIONS	A-200
EXTERIOR ELEVATIONS	A-201

PREPARED BY



LEGAL DESCRIPTION: PARCEL A, OF "PORT 95 COMMERCE PARK", ACCORDING TO THE PLAT THEREOF AS RECORDED IN **CUMBERLAND FARMS** STATE ROAD 84 & **SW 30TH AVENUE**

CUMBERLAND FARMS, INC.

CITY OF HOLLYWOOD **BROWARD COUNTY, FLORIDA**





1000 CORPORATE DRIVE, SUITE 250 FORT LAUDERDALE, FL 33334 PH: (954) 202-7000 FX: (954) 202-7070 www.ThomasEngineeringGroup.com

PROFESSIONAL ENGINEER FLORIDA LICENSE No. 50572 FLORIDA BUSINESS CERT. OF AUTH. No. 27520

COVER SHEET

CFG01.0





SINEERS - PROJECT MANAGERS - LAND PLANNING - LANDSCAPE ARCE-ORPORATE DR. 174450 W. KENNEDY BLVD. 1725 W INDIANTC 250 SUITE 600 SUITE 206 INDIANTC 250 SUITE 206 SUIT

REVISIONS:

REV: DATE: COMMENT: BY:

KNOW WHAT'S BELOW ALWAYS CALL 811 BEFORE YOU DIG It's fast. It's free. It's the law. www.callsunshine.com

PRELIMINARY TECHNICAL

10/02/2017

ADVISORY COMMITTEE

PROJECT No.: F160038
DRAWN BY: JFV

CHECKED BY: MAT
DATE: 10-02-2017
CAD I.D.: F160039 SITE PLAN
PROJECT:
CHIMPEDI AND FADMS

CUMBERLAND FARMS STATE ROAD 84 & SW 30TH AVENUE

CUMBERLAND

FARMS, INC.

CITY OF HOLLYWOOD BROWARD COUNTY, FLORIDA

RADICE III 1000 CORPORATE DRIVE, SUITE 250 FORT LAUDERDALE, FL 33334 PH: (954) 202-7000 FX: (954) 202-7070

www.ThomasEngineeringGroup.com


MICHAEL A. TROXELL


PROFESSIONAL ENGINEER
October 2, 2017
FLORIDA LICENSE No. 50572
FLORIDA BUSINESS CERT. OF AUTH. No. 27528

SHEET TITLE:

SITE PLAN

CFG04.0





CITY OF HOLLYWOOD FLORI	 DA		
CODE COMPLIANCE CHART C-4			
TY OF HOLLYWOOD LANDSCAPE MANUAL			
NET SITE AREA: 108,136 SF (.2.48 ACRES)			
SECTION 2.3: COMMERCIAL DISTRICTS (C-1 THROUGH C-5)		REQUIRED	PROVIDED
Perimeter Landscape Buffer	- 		
1 Swale Street Tree/50 If of Street Frontage	:		
1 Shrub/2 l.f.			
<u>SR 84:</u> 206.92 If	(*Includes 10 Exist. Cabbage Palms (Equals 3 Trees))	5 TREES	5 TREES*
		104 SHRUBS	104 SHRUBS
SW 30th Ave: 284.87 If	(**Includes 6 Existing Live Oak Trees)	6 TREES	6 TREES**
		143 SHRUBS	143 SHRUBS
Marina Road: 600.77 If		12 TREES	12 TREES
51		300 SHRUBS	300 SHRUBS
5' Landsacpe Buffer Included Within Required Setback		55 TREES	55 TREES***
("""Includes 16 Existi	ng Cabbage Palms (Equals 5 Trees) & 6 Live Oak Trees)		
Interior Landscaping for Vehicular Use Areas (50,074 S	.E/		
	al sf of Paved VUA shall be used for Landscaping:	12,518.50	42,165.2 SF
1 Tree/Required Parking Island:	(11 islands)	12,516.50 11 TREES	11 TREES
Each Island shall contain 190 sf Min. of Per	'	II IIILLO	Complies
Edon Island Shan Contain 100 St Will. Of 1 Ch	nous / ii cu		Complics
Open Space:			
1 Tree/1000 sf of Pervious Area in Addition	to Parking Areas: (47,628 sf/1000)	48 TREES	48 TREES
	, , ,		
	TOTALS	137 TREES	137TREES
Minimum Tree Sizes:		547 SHRUBS	1057SHRUBS
Trees: 8 1/2' height, 2" dbh			
Palms: 6' clear wood (50% Max.of code	requirements); 3:1		
Minimum 8 Species Required/9 Species Provided			
		native/required	native/provided
Native: 60% Trees		83/137TREES	113/137 TREES
			82.48%
50% Shrubs		274/547 SHRUBS	757/1057 SHRUBS
			71.62%
Drought Tolerant: 80% for all Materials per Ordinance 0-2011-	U6 Mandatory Green Building Practices	TREES	100.0%

LANDSCAPE NOTES:

- 1. Contractor responsible for locating and protecting all underground utilities prior to digging.
- 2. Contractor responsible for protecting existing trees from damage during construction as shown on plans. 3. General Contractor to install 6" minimum depth of clean, friable topsoil at all planting beds and lawn areas prior to
- fine grading. See Topsoil specification Sheet CFG08.3. 4. All shrub beds (existing and new) to be mulched with a 4-inch minimum layer of hardwood mulch (brown) as defined in the landscape specifications on Sheet CFG08.3.
- 5. Existing grass in proposed planting areas to be killed and removed and area to be hand raked to remove all rocks and debris larger than 1 inch in diameter prior to planting shrubs or laying sod. Landscape contractor to provide
- fine grading. See grading specification SheetCFG08.3. 6. Any existing grass disturbed during construction to be fully removed, re-graded and replaced. All tire marks and
- indentions to be repaired. No exceptions. 7. Soil to be tested to determine fertilizer and lime requirements and distributed prior to laying sod as directed by L.A.
- Provide results to L.A. and Cumberland Farms Project Manager. 8. Sod to be delivered fresh (Cut less than 24 hours prior to arriving on site), laid immediately, rolled, and watered thoroughly immediately after planting. Edge of sod adjacent to mulch beds to be shovel cut. All sod to be
- delivered in largest rolls available. There shall be no gaps between sod joints. 9. All changes to design or plant substitutions are to be authorized in writing by the Landscape Architect, City of
- 10. Planting Mix to be provided as specified in the landscape specifications Sheet CFG08.3. 11. All landscaping shall be installed in conformance with ANSI Z60.1 the "American Standard for Nursery Stock" and
- the accepted standards of the American Association of Nurserymen. 12. The Landscape Contractor shall guarantee all plants installed for one full year from date of acceptance. All plants
- not be responsible for acts of God or vandalism. 13. Any plant that is determined dead, in an unhealthy or unsightly condition, lost its shape due to dead branches or
- other symptoms of poor, non-vigorous growth, as determined by the Landscape Architect, shall be replaced by the Landscape Contractor at no cost to Cumberland Farms.
- 14. General Contractor to mound all parking islands 6" 10" with clean-screened topsoil. 15. Prior to installation, the Landscape Contractor shall inspect the subgrade, general site conditions, verify elevations,
- utility locations, irrigation, approve topsoil provided by General Contractor and observe the site conditions under which the work is to be done. Notify General Contractor of any unsatisfactory conditions, and work shall not proceed until such conditions have been corrected and are acceptable to the Landscape Architect, Landscape Contractor and Cumberland Farms Construction Manager.
- 16. Stake all evergreen and deciduous trees.
- 17. Remove all stakes and guying from all trees after one year from planting.
- 18. Water all plant material that are newly planted thoroughly twice in first 24 hours and apply mulch immediately. 19. Site to be 100% irrigated in all planting beds and grass area by an automatic underground irrigation system. See
- 20. All tree protection devices to be installed by General Contractor prior to the start of land disturbance, and
- maintained until final landscaping.
- 21. All tree protection areas to be protected from sedimentation.
- 22. All tree protection fencing to be inspected daily, and repaired or replaced as needed or as instructed by L.A. 23. Landscape Contractor shall provide a 1year maintenance period under separate contract following acceptance by the Landscape Architect and Cumberland Farms Construction Manager. Maintenance contract to be assigned through Cumberland Farms maintenance Department.

NOTE: THERE SHALL BE NO PLANT MATERIAL SUBSTITUTIONS WITHOUT APPROVAL OF THE LANDSCAPE ARCHITECT AND THE CITY OF HOLLYWOOD'S LANDSCAPE REVIEWER.

NOTE: ALL LANDSCAPE AREAS SHALL BE IRRIGATED AND SHALL HAVE 100% COVERAGE WITH A MINIMUM 50% OVERLAP.

PLEASE REFER TO SHEET CFG08.2 FOR LANDSCAPE PLANTING DETAILS, AND SHEET CFG08.3 FOR LANDSCAPE GENERAL NOTES.

NOTE: NO PLANT MATERIAL SHLL BE PLANTED OVER ROOT BALLS OF NEW TREES AND PALMS.



RADICE III 1000 CORPORATE DRIVE, SUITE 250 FORT LAUDERDALE, FL 33334 PH: (954) 202-7000 FX: (954) 202-7070 www.ThomasEngineeringGroup.com

It's fast. It's free. It's the law.

05-12-16 F160039 LANDSCAPE PLAN

www.callsunshine.com

STATE RD 84 &

SW 30 TH AVENUE

CUMBERLAND FARMS


HOLLYWOOD


FLORIDA


CHECKED BY:





LANDSCAPE PLAN
















(2" cal. and under) SMALL TREE PLANTING DETAIL





Woter/ Sewer Service Line or Egde of Povement

"Bio-Barrier" Is Manufactured By:
"Reemay, Inc." - 70 Old Hickory Blvd. - P.O.Box 511 Old Hickory, TN 37138 - Phone: 1-800-25-ROOTS

Applicable Use of Root Barriers:

If a Canopy Tree and/ or Palm Is To Be Installed Within Less Than (5') Five Feet Separation From A Water Main (or Service) and/ or Sewer Main (or Service). The Landscape Contractor Shall Install a Root Barrier Parallel To The Utility As Required and as per This Detail. The Contractor Shall Maintain A (5') Five Feet Minimum Horizontal Distance From Outside Edge of Rootball To The Utility or any Paved or Concrete Surface.

The Landscape Contractor Shall Verify The Existing Locations of The Applicable Water Utilities, In The Field, Prior To Any Tree Installations Requiring A Root Barrier.


Suggested Installation Method:

Dig A Vertical Trench Between The Root Source of The Tree and The Surface and/ or Utility Line To Be Protected. The Trench Must Be At Least 6'-0" In Length (Centered On Tree) and Must Be at Least 4'-0" In Depth Parallel To The Applicable Surface, Service and/ or Utility. Note: For New Tree installations, Trench May Be Dug At The Same Time as The Hole For The Applicable Tree and/ or Palm.


Using Impervious Gloves, Roll Out "Bio-Barrier" and Trim To Fit The Specific Application. Insert The Barrier Vertically Into The Trench, With The Top Edge of The Barrier (6") Six Inches Below The Soil Surface.

Tamp Backfill Firmly Into Trench With 'Bio-Barrier" Contained, Eliminating Air Pockets or Soil Voids Accordingly. Dissolve The Coating and Activate The Product By Saturating The Backfill and 'Bio-Barrier" With Water. After Completed, Smooth The Soil Surface To Finish

TYPICAL ROOT BARRIER
APPLICATION DETAIL



SHRUB / GROUNDCOVER SPACING / PLANTING DETAIL



SHRUB PLANTING DETAIL



IN THE PLANT LIST, AND AS HEREIN SPECIFIED. 2. WORK SHALL INCLUDE MAINTENANCE AND WATERING OF ALL PLANTING AREAS OF

THIS CONTRACT UNTIL CERTIFICATION OF ACCEPTABILITY BY THE OWNER.

B. PROTECTION OF EXISTING STRUCTURES

1. ALL EXISTING BUILDINGS, WALKS, WALLS, PAVING, PIPING, AND OTHER ITEMS OF CONSTRUCTION AND PLANTING ALREADY COMPLETED OR ESTABLISHED SHALL BE PROTECTED FROM DAMAGE BY THIS CONTRACTOR UNLESS OTHERWISE SPECIFIED. ALL DAMAGE RESULTING FROM NEGLIGENCE SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR TO THE SATISFACTION OF THE OWNER.

<u>. PROTECTION OF EXISTING PLANT MATERIALS OUTSIDE LIMIT OF</u>

1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL UNAUTHORIZED CUTTING OR DAMAGE TO TREES AND SHRUBS, EXISTING OR OTHERWISE, CAUSED BY CARELESS OPERATION OF EQUIPMENT, STOCKPILING OF MATERIALS, ETC. THIS SHALL INCLUDE COMPACTION BY DRIVING OR PARKING INSIDE THE DRIP—LINE OR THE SPILLING OF OIL, GASOLINE, OR OTHER DELETERIOUS MATERIALS WITHIN THE DRIP—LINE.

2. NO MATERIALS SHALL BE BURNED WHERE THE HEAT WILL DAMAGE ANY PLANT TREES KILLED OR DAMAGED SO THAT THEY ARE MISSHAPEN AND/OR UNSIGHTLY SHALL BE REPLACED AT THE COST TO THE CONTRACTOR OF ONE HUNDRED DOLLARS (\$100) PER CALIPER INCH ON AN ESCALATING SCALE WHICH ADDS AN ADDITIONAL TWENTY PERCENT (20%) PER INCH OVER FOUR INCHES (4") CALIPER AS FIXED AND AGREED LIQUIDATED DAMAGES, OR AS MAY BE REQUIRED BY THE REGULATING GOVERNMENT AGENCY, WHICHEVER IS GREATER. CALIPER SHALL BE MEASURED AT BREAST HEIGHT OR FOUR FEET (4') ABOVE SURROUNDING GROUND.

1. SUBMITTALS: GENERAL SAMPLES OF PLANTING MATERIALS AS LISTED BELOW SHALL BE SUBMITTED FOR APPROVAL, ON THE SITE OR AS OTHERWISE DETERMINED BY THE OWNER. UPON APPROVAL OF SAMPLES, DELIVERY OF MATERIALS MAY

TOPSOIL ONE (1) CUBIC FOOT PLANTS ONE (1) REPRESENTATIVE SAMPLE OF EACH VARIETY

a) GENERAL: PLANT SPECIES AND SIZE SHALL CONFORM TO THOSE INDICATED ON THE DRAWINGS. NOMENCLATURE SHALL CONFORM TO STANDARDIZED PLANT NAMES, 942 EDITION. ALL NURSERY STOCK SHALL BE IN ACCORDANCE WITH "GRADES AND STANDARDS FOR NURSERY PLANTS" PARTS I AND II, LATEST EDITION PUBLISHED BY THE FLORIDA DEPARTMENT OF AGRICULTURE AND CONSUMER SERVICES. ALL PLANTS SHALL BE FLORIDA NO. 1 AS AN ABSOLUTE MINIMUM UNLESS OTHERWISE SUPERCEDED BY A FLORIDA FANCY DESIGNATION. AS DETERMINED BY THE FLORIDA DIVISION OF PLANT INDUSTRY. ALL PLANTS SHALL BE FRESHLY DUG, SOUND. HEALTHY, VIGOROUS, WELL—BRANCHED AND FREE OF DISEASE AND INSECT INSECT EGGS AND LARVAE, AND SHALL HAVE ADEQUATE ROOT SYSTEMS. TREES FOR PLANTING IN ROWS SHALL BE UNIFORM IN SIZE AND SHAPE. ALL MATERIALS SHALL BE SUBJECT TO APPROVAL BY THE OWNER. WHERE ANY REQUIREMENTS ARE OMITTED FROM THE PLANT LIST, THE PLANTS FURNISHED SHALL BE NORMAL FOR THE VARIETY. PLANTS SHALL BE PRUNED PRIOR TO DELIVERY ONLY UPON THE

b) MEASUREMENTS: THE HEIGHT AND/OR WIDTH OF TREES SHALL BE MEASURED FROM THE TOP OF ROOTBALL (TRUNK FLARE) AND/OR ACROSS THE AVERAGE SPREAD OF BRANCHES WITH THE PLANTS IN THEIR NORMAL POSITION. THIS MEASUREMENT SHALL NOT INCLUDE THE IMMEDIATE TERMINAL GROWTH. PLANTS LARGER IN SIZE THAN THOSE SPECIFIED IN THE PLANT LIST MAY BE USED IF APPROVED BY THE OWNER. IF THE USE OF LARGER PLANTS IS APPROVED, THE BALL OF EARTH OR SPREAD OF ROOTS SHALL BE INCREASED IN PROPORTION TO

c) INSPECTION: PLANTS SHALL BE SUBJECT TO INSPECTION AND APPROVAL AT THE PLACE OF GROWTH, OR UPON DELIVERY TO THE SITE, AS DETERMINED BY THE OWNER, FOR QUALITY, SIZE, AND VARIETY; SUCH PRELIMINARY APPROVAL SHALL NOT SUPERCEDE THE RIGHT OF INSPECTION AND REJECTION AT THE SITE DURING ROGRESS OF THE WORK OR AFTER COMPLETION FOR SIZE AND CONDITION OF BALLS OR ROOTS, LATENT DEFECTS OR INJURIES, PRESENCE OF INSECTS, AND OTHER CONDITIONS THAT MAY HAVE OCCURRED SINCE THE NURSERY INSPECTION. REJECTED PLANTS SHALL BE REMOVED IMMEDIATELY FROM THE SITE. NOTICE REQUESTING INSPECTION SHALL BE SUBMITTED IN WRITING BY THE CONTRACTOR AT LEAST ONE (1) WEEK PRIOR TO ANTICIPATED DATE.

d) AMENDED PLANTING SOIL: PLANTING SOIL FOR USE IN BACK FILLING PLANTING HOLES SHALL BE FORTY PERCENT (40%) TOPSOIL AND SIXTY PERCENT (60%) SAND AND BE FERTILE, FRIABLE, AND OF À LOAMY CHARACTER, WITHOUT MIXTURÉ OF SUBSOIL MATERIALS, AND OBTAINED FROM A WELL-DRAINED, ARABLE SITE. IT SHALL CONTAIN THREE (3) TO FIVE (5) PERCENT DECOMPOSED ORGANIC MATTER AND SHALL BE FREE FROM HEAVY CLAY, COARSE SAND, STONES, LIME, LUMPS, PLANTS, ROOTS OR OTHER FOREIGN MATERIALS, OR NOXIOUS WEEDS, IT SHALL NOT CONTAIN TOXIC SUBSTANCES WHICH MAY BE HARMFUL TO PLANT GROWTH. PH RANGE SHALL BE 5.0 TO 7.0 INCLUSIVE

e) SAND SHALL BE CLEAN, WELL DRAINING NATIVE SAND. IF REQUESTED, CONTRACTOR SHALL AT ANY TIME AND AT NO COST TO OWNER SUBMIT RESULTS OF SOIL TESTS FOR TOPSOIL AND SAND PROPOSED FOR USE UNDER THIS CONTRACT FOR APPROVAL BY OWNER.

E. WATER

1. WATER NECESSARY FOR PLANTING AND MAINTENANCE SHALL BE OF SATISFACTORY QUALITY TO SUSTAIN AN ADEQUATE GROWTH OF PLANTS AND SHALL NOT CONTAIN HARMEUL NATURAL OR MAN—MADE ELEMENTS DETRIMENTAL TO PLANTS. WATER MEETING THE ABOVE STANDARD SHALL BE OBTAINED ON THE SITE FROM THE OWNER, IF AVAILABLE, AND THE CONTRACTOR SHALL BE RESPONSIBLE TO MAKE ARRANGEMENTS FOR ITS USE BY HIS TANKS, HOSES, SPRINKLERS, ETC. IF SUCH WATER IS NOT AVAILABLE AT THE SITE, THE CONTRACTOR SHALL PROVIDE SUCH SATISFACTORY WATER FROM SOURCES OFF THE SITE AT NO ADDITIONAL COST TO THE OWNER.

F. COMMERCIAL FERTILIZER

1. COMMERCIAL FERTILIZER SHALL BE A COMPLETE FORMULA: IT SHALL BE UNIFORM IN COMPOSITION, DRY AND FREE FLOWING. THIS FERTILIZER SHALL BE DELIVERED TO THE SITE IN THE ORIGINAL UNOPENED CONTAINERS, EACH BEARING THE MANUFACTURER'S GUARANTEED STATEMENT OF ANALYSIS.

FIFTY PERCENT (50%) OF THE NITROGEN SHALL BE DELIVERED FROM NATURAL ORGANIC SOURCES. THE FOLLOWING FERTILIZERS SHALL BE USED AND APPLIED AT RATES AS SUGGESTED BY MANUFACTURER'S SPECIFICATIONS

1. SHRUBS AND TREES — MILORGANITE, OR APPROVED EQUAL 2. ANNUALS AND GROUNDCOVERS — OSMOCOTE/SIERRA BLEND 14—14—14

IN ADDITION TO SURFACE APPLIED FERTILIZERS, ALL CONTAINER GROWN AND FIELD GROWN PLANT MATERIAL SHALL RECEIVE "AGRIFORM" PLANTING TABLETS 24-10-5 FORMULA, 21 GRAM OR EQUAL. THESE TABLETS SHALL BE PLACED AT THE RATE AND DEPTH SPECIFIED BY MANUFACTURER.

1. MULCH SHALL BE FROM SHREDDED WOOD DERIVED FROM MELALEUCA OR OTHER INVASIVE TREE SPECIES AND SHALL BE STERILIZED TO EFFECTIVELY ELIMINATE ALL SEEDS, SPORES, ETC. AND RENDER THEM BARREN

2. MULCH MATERIAL SHALL BE MOISTENED AT THE TIME OF APPLICATION TO PREVENT WIND DISPLACEMENT, AND APPLIED AT A DEPTH OF THREE INCHES (3"). 3. MULCH SHALL BE GRADE 'B' SHREDDED, AND SHALL BE APPLIED EVENLY AND

4. NO RED OR COLORED MULCH SHALL BE ACCEPTED UNLESS SPECIFIED

ACCORDINGLY. NO CYPRESS MULCH SHALL BE USED H. DIGGING AND HANDLING

1. PROTECT ROOT SYSTEMS OR ROOTBALLS OF PLANTS AT ALL TIMES FROM SUN AND DRYING WINDS, WATER EROSION, AND OTHER HARMFUL CRITERIA AS NECESSARY UNTIL PLANTING. PLANT MATERIALS SHALL BE ADEQUATELY PACKED TO PREVENT BREAKING AND DRYING OUT DURING LOADING, TRANSIT, AND UNLOADING/PLANTING. REES TRANSPORTED MORE THAN TEN (10) MILES OR WHICH ARE NOT PLANTED WITHIN THREE (3) DAYS OF DELIVERY TO SITE SHALL BE SPRAYED WITH AN

ANTITRANSPIRANT PRODUCT ("WILTPRUF" OR EQUAL) TO MINIMIZE TRANSPIRATIONAL

2, BALLED AND BURLAPPED PLANTS (B&B) SHALL BE DUG WITH FIRM, NATURAL BALLS OF SOIL OF SUFFICIENT SIZE TO ENCOMPASS THE FIBROUS AND FEEDING ROOTS OF THE PLANTS, AND IN ACCORDANCE WITH "GRADES AND STANDARDS FOR NURSERY PLANTS" FLORIDA PUBLICATION. NO PLANT WITH A ROOTBALL SHALL BE PLANTED IF THE BALL IS CRACKED OR BROKEN. PLANTS BALLED AND BURLAPPED OR CONTAINER GROWN SHALL NOT BE HANDLED BY STEMS.

3. PLANTS MARKED "BR" IN THE PLANT LIST SHALL BE DUG WITH BARE ROOTS. THE ROOTS SHALL NOT BE CUT WITHIN THE MINIMUM SPREAD SPECIFIED IN THE PLANT LIST. CARE SHALL BE EXERCISED THAT THE ROOTS DO NOT DRY OUT IN MOVING AND PRIOR TO PLANTING.

4. PROTECTION OF PALMS (IF APPLICABLE): ONLY A MINIMUM OF FRONDS SHALL BE REMOVED FROM THE CROWN OF THE PALM TREES TO FACILITATE MOVING AND HANDLING. CLEAR TRUNK (CT) SHALL BE AS BY "GRADES AND STANDARDS FOR NURSERY PLANTS" FLORIDA PUBLICATION. PRUNING PRACTICED OTHER THAN MINIMAL PRUNING OF FRONDS, PRIMARILY TO REACH A "CLEAR TRUNK" SPECIFICATION, MAY CONSTITUTE REJECTION, OR ALL PALMS SUBJECTED TO SUCH PRACTICE. LIKEWISE EXCESSIVE PRUNING OR "SHAVING" OF ROOTBALLS TO MEET "CLEAR TRUNK" CRITERIA MAY CONSTITUTE REJECTION ONSITE. ALL PALMS SHALL BE BRACED PER PALM PLANTING DETAIL ON THE PLANTING DETAILS SHEET.

5. EXCAVATION OF PLANTING HOLES SHALL BE DONE USING EXTREME CARE TO AVOID DAMAGE TO SURFACE AND SUBSURFACE ELEMENTS SUCH AS UTILITIES OR HARDSCAPE ELEMENTS, FOOTERS, AND PREPARED SUB—BASES.

I. CONTAINER GROWN STOCK

1. ALL CONTAINER GROWN MATERIAL SHALL BE HEALTHY, VIGOROUS, WELL—ROOTED PLANTS AND ESTABLISHED IN THE CONTAINER IN WHICH THEY ARE SOLD. THE PLANTS SHALL HAVE TOPS WHICH ARE OF GOOD QUALITY AND ARE IN A HEALTHY GROWING CONDITION, AND SHALL MEET MINIMUM SPECIFICATIONS IN THE PLANT LIST.

2. AN ESTABLISHED CONTAINER GROWN PLANT SHALL BE TRANSPLANTED INTO A CONTAINER AND GROWN IN THAT CONTAINER SUFFICIENTLY LONG FOR THE NEW FIBROUS ROOTS TO HAVE DEVELOPED SO THAT THE ROOT MASS WILL RETAIN ITS SHAPE AND HOLD TOGETHER WHEN REMOVED FROM THE CONTAINER. CONTAINER GROWN STOCK SHALL NOT BE HANDLED BY THEIR STEMS.

3, PLANT ROOTS BOUND IN CONTAINERS SHALL NOT BE ACCEPTABLE.

4. SUBSTITUTION OF NON—CONTAINER GROWN MATERIAL FOR MATERIAL EXPLICITLY SPECIFIED TO BE CONTAINER GROWN WILL NEED AUTHORIZATION FROM THE OWNER. J. COLLECTED STOCK

1. WHEN THE USE OF COLLECTED STOCK IS PERMITTED AS INDICATED ON THE PLANT LIST SCHEDULE. THE MINIMUM SIZES OF ROOT BALLS SHALL BE EQUAL TO THAT SPECIFIED FOR THE NEXT LARGER SIZE OF NURSERY GROWN STOCK OF THE SAME K. NATIVE STOCK

1. PLANTS COLLECTED FROM WILD OR NATIVE STANDS SHALL BE CONSIDERED GROWN WHEN THEY HAVE BEEN SUCCESSFULLY REESTABLISHED IN A NURSERY ROW AND GROWN UNDER REGULAR NURSERY CULTURAL PRACTICES FOR A MINIMUM OF TWO (2) GROWING SEASONS AND HAVE ATTAINED ADEQUATE ROOT AND TOP GROWTH TO INDICATE FULL RECOVERY FROM TRANSPLANTING INTO THE NURSERY

L. MATERIALS LIST

M. FINE GRADING

1. QUANTITIES NECESSARY TO COMPLETE THE WORK ON THE DRAWINGS SHALL BE FURNISHED. QUANTITY ESTIMATES HAVE BEEN MADE CAREFULLY, BUT THE LANDSCAPE ARCHITECT OR OWNER ASSUMES NO LIABILITY FOR OMISSIONS OR ERRORS. SHOULD A DISCREPANCY OCCUR BETWEEN A BIDDER'S TAKE OFF AND THE PLANT LIST QUANTITY, THE LANDSCAPE ARCHITECT SHALL BE NOTIFIED FOR CLARIFICATION PRIOR TO THE SUBMISSION OF BIDS. DRAWING SHALL TAKE PRECEDENCE. ALL DIMENSIONS AND/OR SIZES SPECIFIED SHALL BE THE MINIMUM ACCEPTABLE SIZE.

1. FINE GRADING UNDER THIS CONTRACT SHALL CONSIST OF FINAL FINISHED GRADING OF LAWN AND PLANTING AREAS THAT HAVE BEEN ROUGH GRADED BY OTHERS. BERMING AS SHOWN ON THE DRAWINGS SHALL BE THE RESPONSIBILITY OF THE LANDSCAPE CONTRACTOR, UNLESS OTHERWISE NOTED.

CONTRACTOR SHALL FINE GRADE THE LAWN AND PLANTING AREAS TO BRING THE ROUGH GRADE UP TO FINAL FINISHED GRADE ALLOWING FOR THICKNESS OF SOD AND/OR MULCH DEPTH. THIS CONTRACTOR SHALL FINE GRADE BY HAND AND/OR WITH ALL EQUIPMENT NECESSARY INCLUDING A GRADING TRACTOR WITH FRONT—END LOADER FOR TRANSPORTING SOIL WITHIN THE SITE.

3. ALL PLANTING AREAS SHALL BE GRADED AND MAINTAINED TO ALLOW FREE FLOW OF SURFACE WATER. AREAS ADJACENT TO BUILDINGS SHALL SLOPE AWAY FROM THE

N. PLANTING PROCEDURES

1 CLEANING UP BEFORE COMMENCING WORK: THE CONTRACTOR SHALL CLEAN UP WORK AND SURROUNDING AREAS OF ALL RUBBISH OR OBJECTIONABLE MATTER. ALL MORTAR, CEMENT, AND TOXIC MATERIAL SHALL BE COMPLETELY REMOVED FROM THE SITE. THESE MATERIALS SHALL NOT BE MIXED WITH THE SOIL. SHOULD THE CONTRACTOR FIND SUCH SOIL CONDITIONS BENEATH THE SOIL WHICH WILL IN ANY WAY AFFECT THAT VIABILITY OF THE PLANTS TO BE INSTALLED, HE/SHE SHALL IMMEDIA CALL IT TO THE ATTENTION OF THE OWNER'S CONSTRUCTION MANAGER OR DESIGNEE

2. VERIFY LOCATIONS OF ALL UTILITIES, CONDUITS, SUPPLY LINES AND CABLES. INCLUDING BUT NOT LIMITED TO: ELECTRIC, GAS (LINES AND TANKS), WATER SANITARY SEWER, STORM WATER LINES, CABLE AND TELEPHONE. PROPERLY MAINTAIN AND PROTECT EXISTING UTILITIES.

3. SUBGRADE EXCAVATION: CONTRACTOR IS RESPONSIBLE TO REMOVE ALL EXISTING AND IMPORTED LIMEROCK AND LIMEROCK SUB—BASE FROM ALL LANDSCAPE PLANTING AREAS TO MINIMUM DEPTH OF APPROXIMATELY 20% GREATER THAN RECOMMENDED PLANTING SOIL DEPTH. CONTRACTOR IS RESPONSIBLE TO BACKFILL THESE PLANTING AREAS TO ROUGH FINISHED GRADE WITH CLEAN TOPSOIL FROM AN ONSITE SOURCE OR AN IMPORTED SOURCE. IF LIMEROCK CONDITIONS OCCUR IN PLANTED AREAS AFTER 36" DEEP EXCAVATION BY CONTRACTOR, AND POSITIVE DRAINAGE CAN NOT BE ACHIEVED, CONTRACTOR SHALL UTILIZE PLANTING DETAIL THAT ADDRESSES POOR DRAINAGE OR CONTACT OWNER'S CONSTRUCTION MANAGER OR DESIGNEE FOR RESOLUTION.

4. FURNISH NURSERY'S CERTIFICATE OF COMPLIANCE WITH ALL REQUIREMENTS AS HEREIN SPECIFIED AND REQUIRED. INSPECT AND SELECT PLANT MATERIALS BEFORE

5. GENERAL: COMPLY WITH FEDERAL. STATE. COUNTY, AND LOCAL REGULATIONS GOVERNING LANDSCAPE MATERIALS AND WORK. CONFORM TO ACCEPTED HORTICULTURAL PRACTICES AS USED IN THE TRADE. PLANTS SHALL BE PROTECTED UPON ARRIVAL AT THE SITE BY BEING THOROUGHLY WATERED AND PROPERLY MAINTAINED UNTIL PLANTED. PLANTS SHALL NOT REMAIN UNPROTECTED FOR A PERIOD EXCEEDING TWENTY—FOUR (24) HOURS. AT ALL TIMES WORKMANLIKE METHODS CUSTOMARY IN GOOD HORTICULTURAL PRACTICES SHALL BE EXERCISED.

PLANTS ARE DUG AT NURSERY OR GROWING SITE.

6. THE WORK SHALL BE COORDINATED WITH OTHER TRADES TO PREVENT CONFLICTS. COORDINATE THE PLANTING WITH THE IRRIGATION WORK TO ASSURE AVAILABILITY OF WATER AND PROPER LOCATION OF IRRIGATION ITEMS AND PLANTS.

7. ALL PLANTING HOLES SHALL BE EXCAVATED TO SIZE AND DEPTH IN ACCORDANCE WITH THE USA STANDARD TO NURSERY STOCK Z60.1 UNLESS SHOWN OTHERWISE ON THE DRAWINGS, AND BACKFILLED WITH THE PREPARED PLANTING SOIL AS SPECIFIED HEREIN BEFORE (SEE MATERIALS, SECTION D). TEST ALL TREE PITS WITH WATER BEFORE PLANTING TO ASSURE PROPER DRAINAGE PERCOLATION IS AVAILABLE. NO ALLOWANCE WILL BE MADE FOR LOST PLANTS DUE TO IMPROPER DRAINAGE. IF POOR DRAINAGE EXISTS, UTILIZE PLANTING DETAIL THAT ADDRESSES THIS CONDITION. TREES SHALL BE SET PLUMB AND HELD IN POSITION UNTIL THE PLANTING MIXTURE HAS BEEN FLUSHED INTO PLACE WITH A SLOW. FULL HOSE STREAM. ALL PLANTING SHALL BE PERFORMED BY PERSONNEL FAMILIAR WITH PLANTING PROCEDURE AND UNDER THE SUPERVISION OF A QUALIFIED PLANTING FOREMAN. PROPER "JETTING IN" SHALL BE ASSURED TO ELIMINATE AIR POCKETS

8. TAKE ALL NECESSARY PRECAUTIONS TO AVOID DAMAGE TO BUILDINGS, CURBS, PAVING, AND OTHER HARDSCAPE MATERIALS WHILE INSTALLING TREES.

9. SOIL MIXTURE SHALL BE AS SPECIFIED IN SECTION D (MATERIALS) OF THESE SPECIFICATIONS. IN ADDITION, EACH PLANTING HOLE SHALL RECEIVE 21—GRAM "AGRIFORM" PLANTING TABLETS PER MANUFACTURER'S SPECIFICATIONS OR AS

- TWO (2) TABLETS PER 1 GAL. PLANT — THREE (3) TABLETS PER 3 GAL. PLANT

- FOUR (4) TABLETS PER 10 GAL. PLANT — TWO (2) TABLETS PER HALF INCH (1/2") OF TRUNK CALIPER

AROUND THE ROOTS. "JET STICK" OR EQUAL IS RECOMMENDED.

10. TREES AND SHRUBS SHALL BE SET STRAIGHT AND AT SUCH A LEVEL THAT AFTER SETTLEMENT, THE TOP OF THE ROOT SYSTEM (FOR SHRUBS AND GROUNDCOVER) OR TRUNK FLARE (TREES AND PALMS) WILL STAND ONE (1) TO TWO (2) INCHES ABOVÉ FINAL GRADE. EACH PLANT SHALL BE SET IN THE CENTER OF THE PLANTING HOLE PLANTING SOIL MIXTURE SHALL BE BACKFILLED AND THOROUGHLY TAMPED AROUND THE BALL AND SHALL BE SETTLED BY WATER AFTER TAMPING.

11. FILL HOLE WITH SOIL MIXTURE, MAKING CERTAIN ALL SOIL IS SATURATED. TO DO THIS, FILL HOLE WITH WATER AND ALLOW TO SOAK MINIMUM TWENTY (20) MINUTES TURNING SOIL IF NECESSARY TO GET SOIL THOROUGHLY WET. PACK LIGHTLY WITH FEET OR OTHER TAMPING DEVICE. ADD MORE WET SOIL MIXTURE. DO NOT COVER TOP OF BALL WITH SOIL MIXTURE, ONLY WITH MULCH. ALL BURLAP, ROPE, WIRES, ETC., SHALL BE PULLED FROM UNDERNEATH.

12. PRUNING: FOR DAMAGED OR BROKEN LIMBS, EACH TREE SHALL BE PRUNED TO PRESERVE THE NATURAL CHARACTER | OF THE SPECIES. ALL SUCKER GROWTH SHALL BE COMPLETELY REMOVED PRIOR TO DIGGING.

13. SHRUBS AND GROUNDCOVER PLANTS SHALL BE EVENLY SPACED IN ACCORDANCE WITH THE DRAWINGS AND AS INDICATED IN THE PLANT LIST. CULTIVATE ALL MASS PLANTING AREAS TO A MINIMUM DEPTH OF 6", REMOVE AND DISPOSED ALL DEBRIS, TILL 4" OF PLANTING SOIL MIX INTO THE NEWLY TILLED PLANTING BED FOR GENERAL NUTRIENT DISBURSEMENT. MASS PLANTING BED IS NOW READY TO RECEIVE HOLES FOR NEW PLANTS. THOROUGHLY WATER ALL PLANTS AFTER INSTALLATION.

14. TREE GUYING AND BRACING SHALL BE INSTALLED BY THE LANDSCAPE CONTRACTOR IN ACCORDANCE WITH THE PLANS TO INSURE STABILITY AND MAINTAIN TREES IN AN UPRIGHT POSITION. TREES SHALL USE ARBORTIE AS PER DETAIL SHEET PALMS SHALL USE WOOD BRACING PER DETAIL SHEET.

15. MULCHING: PROVIDE A THREE INCH (3") MINIMUM LAYER OF SPECIFIED MULCH OVER THE ENTIRE AREA OF EACH SHRUB BED, GROUNOCOVER AND VINE BED AND TREE PIT (FOR TREES AND PALMS, MIN. THREE INCH (3") FROM EDGE OF TRUNKS). -UNLESS OTHER REQUIRED BY LOCAL CODES AND SPECIFIED AS SUCH.

16. SYSTEMIC HERBICIDE WEED CONTROL ALL PLANT BEDS SHALL BE KEPT FREE OF NOXIOUS WEEDS UNTIL FINAL ACCEPTANCE OF WORK. IF DIRECTED BY THE OWNER OR THEIR DESIGNEE, A SYSTEMIC HERBICIDE SHALL BE APPLIED FOR WEED CONTROL BY QUALIFIED PERSONNEL TO ALL PLANTING AREAS IN SPOT APPLICATIONS PER MANUFACTURER'S PRECAUTIONS AND SPECIFICATIONS AFTER MUI CHIHAS BEEN APPLIED TO PLANTING BEDS AND TREE RINGS, TREAT ALL MULCHED AREAS WITH AN APPROVED PRE—EMERGENT HERBICIDE AT AN APPLICATION RATE RECOMMENDED

O. LAWN SODDING
STENOTAPHRUM SECUNDATUM, V. 'FLORITAM' UNLESS OTHERWISE NOTED. (ST. AUGUSTINE SOLID SOD). 1. THE WORK CONSISTS OF LAWN BED PREPARATION, SOIL PREPARATION, AND COMPLETE IN STRICT ACCORDANCE WITH THE SPECIFICATIONS AND THE APPLICABLE DRAWINGS TO PRODUCE A GRASS LAWN ACCEPTABLE TO THE OWNER AND

2. LAWN BED PREPARATION: ALL AREAS THAT ARE TO BE SODDED SHALL BE CLEARED OF ANY ROUGH GRASS, WEEDS, AND DEBRIS, AND THE SOIL BROUGHT TO AN EVEN PREPARED GRADE TO ALLOW FOR SOIL PREPARATION BELOW.

3. SOIL PREPARATION: PREPARE LOOSE BED FOUR INCHES (4") DEEP. APPLY FERTILIZER AT A RATE OF TWENTY (20) POUNDS PER ONE THOUSAND (1000) SQUARE FEET. APPLICATION SHALL BÉ UNIFORM, UTILIZING COMMERCIAL BROADCAST SPREADERS. MIX FERTILIZER THOROUGHLY WITH THE SOIL TO A DEPTH OF THREE INCHES (3"). HAND RAKE UNTIL ALL BUMPS AND DEPRESSIONS ARE REMOVED. WET PREPARED AREA THOROUGHLY TO PREPARE FOR SOD INSTALLATION.

4. SODDING: THE CONTRACTOR SHALL SOD ALL PERVIOUS AREAS THAT ARE NOT PAVED OR PLANTED AS DESIGNATED ON THE DRAWINGS WITHIN THE CONTRACT LIMITS TO CREATE A UNIFORM, NEW TURF BLANKET FOR THE SITE.

a) THE SOD SHALL BE CERTIFIED TO MEET FLORIDA STATE BOARD SPECIFICATIONS, ABSOLUTELY TRUE TO VARIETY TYPE, AND FREE FROM WEEDS, FUNGUS, INSECTS, AND DISEASE OF ANY KIND, SOD PANELS SHALL BE LAID TIGHTLY TOGETHER TO MAKE

b) SOD SHALL BE LAID IN ROWS. WITH EVERY OTHER ROW STAGGERED HALFWAY BETWEEN THE NEXT TO INSURE NO CONTINUOUS STACKED JOINTS. SEW JOINTS OF SOD TO INSURE A TIGHT FIT AT JOINTS.

c) SOD SHALL BE LAID UNIFORMLY AGAINST THE EDGES OF ALL CURBS AND OTHER HARDSCAPE ELEMENTS, PAVED AND PLANTED AREAS. ADJACENT TO BUILDINGS, A FOUR INCH (4") MULCH STRIP SHALL BE PROVIDED. IMMEDIATELY FOLLOWING SOD LAYING, THE LAWN AREAS SHALL BE ROLLED WITH A LAWN ROLLER CUSTOMARILY USED FOR SUCH PURPOSES, AND THEN THOROUGHLY IRRIGATED TO THOROUGHLY MOISTEN THE SOIL BENEATH. IF, IN THE OPINION OF THE OWNER, TOP—DRESSING IS NECESSARY AFTER ROLLING TO FILL THE VOIDS BETWEEN THE SOD PANELS AND TO EVEN OUT INCONSISTENCIES IN THE SOD, CLEAN SAND AS APPROVED BY THE LANDSCAPE ARCHITECT OR OWNER SHALL BE UNIFORMLY SPREAD OVER THE ENTIRE SURFACE OF THE SOD AND THOROUGHLY WATERED IN.

5. DURING DELIVERY, PRIOR TO AND DURING THE PLANTING OF THE LAWN AREAS, THE SOD PANELS SHALL AT ALL TIMES BE PROTECTED FROM EXCESSIVE DRYING AND UNNECESSARY EXPOSURE OF THE ROOTS TO THE SUN. ALL SOD SHALL BE INSTALLED DURING THE DAY OF ITS ARRIVAL.

a) WITHIN THE SITE, THE CONTRACTOR SHALL PRODUCE A DENSE, WELL ESTABLISHED LAWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REPAIR AND RE—SODDING OF ALL ERODED, SUNKEN OR BARE SPOTS UNTIL CERTIFICATION OF ACCEPTABILITY BY OWNER OR AS IN THE ORIGINAL WORK SCOPE AND PROCESS (INCLUDING REGRADING, IF NECESSARY)

b) WATER EVERY DAY FOR FOURTEEN (14) SUCCESSIVE DAYS, THEN WATER THREE (3) TIMES PER WEEK (AT EVEN INTERVALS) UNTIL FULLY ESTABLISHED OR UNTIL AUTOMATIC IRRIGATION SYSTEM IS FULLY OPERATIONAL AND PROGRAMMED ACCORDINGLY. COORDINATE WATERING SCHEDULE WITH NATURAL RAINFALL RAINFALL EVENTS IN DURATION OF TWENTY (20) MINUTES OR MORE THAT PRODUCE MORE THAN A HALF INCH (1/2") OF PRECIPITATION WILL NEGATE THE NEED FOR WATERING THE FOLLOWING DAY IF PREVIOUSLY SCHEDULED. ALL WATERING SHALL BE OF SUFFICIENT QUANTITY TO WET OR RESTORE WATER TO A DEPTH OF FOUR INCHES (4").

P. CLEANUP

6. LAWN MAINTENANCE:

1. UPON COMPLETION OF ALL PLANTING WORK AND BEFORE FINAL ACCEPTANCE, THE CONTRACTOR SHALL REMOVE ALL MATERIAL, EQUIPMENT, AND DEBRIS RESULTING FROM HIS WORK. ALL PAVED AREAS SHALL BE BROOM CLEANED AND THE SITE LEFT IN A NEAT AND ACCEPTABLE CONDITION AS APPROVED BY THE OWNER'S AUTHORIZED REPRESENTATIVE.

Q. PLANT MATERIAL MAINTENANCE

1. ALL PLANTS AND PLANTING MATERIALS INCLUDED UNDER THIS CONTRACT SHALL BE MAINTAINED BY WATERING, CULTIVATING, SPRAYING, AND ALL OTHER OPERATIONS (SUCH AS RE—STAKING OR REPAIRING GUY SUPPORTS) NECESSARY TO INSURE A HEALTHY CONDITION BY THE CONTRACTOR UNTIL CERTIFICATION OF ACCEPTABILITY BY THE OWNER OR OWNER'S DESIGNEE. MAINTENANCE AFTER THE CERTIFICATION OF ACCEPTABILITY SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS IN THIS SECTION. CONTRACTORS ARE REQUESTED TO PROVIDE A BID ESTIMATE TO COVE LANDSCAPE AND IRRIGATION MAINTENANCE FOR A PERIOD OF NINETY (90) CALENDAR DAYS COMMENCING AFTER ACCEPTANCE (SEE NEXT SECTION).

R. MAINTENANCE (ALTERNATE BID ITEM)

1. CONTRACTORS ARE REQUESTED TO PROVIDE A BID ESTIMATE FOR LANDSCAPE AND IRRIGATION MAINTENANCE FOLLOWING THE INITIAL 90—DAY MAINTENANCE PERIOD ON A COST PER MONTH BASIS.

S. GUARANTEE

1. THE LIFE AND SATISFACTORY CONDITION OF ALL PLANT MATERIAL INSTALLED BY CONTRACTOR SHALL BE GUARANTEED BY THE CONTRACTOR FOR A MINIMUM OF ONE (1) CALENDAR YEAR COMMENCING AT THE TIME OF CERTIFICATION OF ACCEPTABILITY BY THE OWNER OR OWNER'S DESIGNEE.

2. THE LIFE AND SATISFACTORY CONDITION OF ALL SOD INSTALLED BY THE CONTRACTOR SHALL BE GUARANTEED BY THE CONTRACTOR FOR A MINIMUM OF NINETY (90) CALENDAR DAYS, COMMENCING AT THE TIME OF CERTIFICATION OF ACCÉPTABILITY BY THE OWNERS OR OWNER'S DESIGNEE.

3. REPLACEMENT: ANY PLANT NOT IN A HEALTHY. THRIVING GROWING CONDITION SHALL BE REMOVED FROM THE SITE AND REPLACED AS SOON AS WEATHER CONDITIONS PERMIT. SHOULD THE OWNER ELECT, TREES AND PALMS MAY BE GIVEN A PERIOD OF NINETY (90) DAYS BEFORE REMOVAL TO ALLOW THE CONTRACTOR TO RESURRECT THE TREE OR PALM IN QUESTION AND BRING IT TO A THRIVING, HEALTHY CONDITION. ALL REPLACEMENTS SHALL BE PLANTS OF LIKE KIND, CONDITION AND SIZE AS SPECIFIED IN THE PLANT LIST. THEY SHALL BE FURNISHED, PLANTED. AND MULCHED AS SPECIFIED WITHIN THESE SPECIFICATIONS, AT NO ADDITIONAL COST TO THE OWNER. ANY REPAIRS FROM THIS REPLACEMENT MATERIAL SHALL BE SOLELY THE CONTRACTOR'S RESPONSIBILITY. REPLACEMENT MATERIAL SHALL BE GUARANTEED TO A ONE (1) YEAR PERIOD FROM THE DAY OF REPLACEMENT ACCEPTANCE BY THE OWNER SHOULD REPLACEMENT MATERIAL FAIL WITHIN THE GUARANTEE PERIOD. OWNER MAY OPT FOR A CREDIT OF THE MONETARY AMOUNT FOR THE REPLACEMENT

MATERIALS, AT A RATE OF THE ORIGINAL CONTRACT BID RATE, IN LIEU OF AN ADDITIONAL REPLACEMENT.

4. IN THE EVENT THE OWNER ELECTS NOT TO CONTRACT WITH THE CONTRACTOR FOR LANDSCAPE (AND IRRIGATION) MAINTENANCE, THE CONTRACTOR IS ENCOURAGED TO VISIT THE PROJECT SITE PERIODICALLY DURING THE ONE (1) YEAR WARRANTY PERIOD TO EVALUATE MAINTENANCE PROCEDURES BEING PERFORMED BY THE OWNER OR THEIR DESIGNEE, AND SHALL NOTIFY THE OWNER IN WRITING OF MAINTENANCE PROCEDURES OR CONDITIONS WHICH THREATEN VIGOROUS AND HEALTHY PLANT GROWTH OF ITEMS UNDER REPLACEMENT WARRANTY. IT IS SUGGESTED SUCH SITE VISITS SHALL BE CONDUCTED A MINIMUM OF ONCE PER MONTH FOR A PERIOD OF TWELVE (12) MONTHS FROM THE DATE OF ACCEPTANCE

T. FINAL INSPECTION AND ACCEPTANCE OF WORK

1. FINAL INSPECTION BY OWNER OR THEIR DESIGNEE AT THE END OF THE GUARANTEE PERIOD SHALL INCLUDE PLANTING, CONSTRUCTION AND ALL OTHER INCIDENTAL WORK PERTAINING TO THIS CONTRACT. ANY PLANTS NOT MEETING THE CRITERIA OF HEALTHY, VIGOROUS, AND THRIVING AT THIS TIME, AND THAT HAVE NOT ALREADY BEEN REPLACED PREVIOUSLY UNDER SAID WARRANTY, SHALL BE SUBJECT TO THE SAME ONE (1) YEAR GUARANTEE (OR AS SPECIFIED BY THE OWNER IN WRITING) BEGINNING WITH THE TIME OF REPLACEMENT AND ENDING WITH THE SAME INSPECTION AND ACCEPTANCE HEREIN DESCRIBED.

U. GRADING & DRAINAGE NOTES

1. PRIOR TO COMMENCING ANY EXCAVATION WORK, THE CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES IN ACCORDANCE WITH THE "DIG SAFE" NOTIFICATION PROCEDURES PROMOTED BY THE RESPECTIVE UTILITY COMPANIES IN FLORIDA, CALL FLORIDA SUNSHINE AT 811.

2. CONTRACTOR SHALL BLEND NEW EARTHWORK SMOOTHLY INTO EXISTING PROVIDING VERTICAL CURVES OR ROUNDINGS AT ALL TOP AND BOTTOM OF SLOPES. 3. PITCH EVENLY BETWEEN SPOT GRADES. ALL PAVED AREAS MUST PITCH TO DRAIN AT A MINIMUM SLOPE OF ONE—EIGHTH INCH (1/8") PER FOOT. ANY DISCREPANCIES NOT ALLOWING THIS TO OCCUR SHALL BE REPORTED TO THE OWNER PRIOR TO

4. WHERE NEW PAVING OR EARTHWORK MEETS EXISTING PAVING OR EARTHWORK. SMOOTHLY BLEND LINE AND GRADE OF EXISTING WITH NEW, WHERE EXISTING VEGETATION IS TO REMAIN, MEET EXISTING GRADES; DO NOT FILL ABOVE BASAL FLARE OF EXISTING TREES.

V. UTILITY PLAN NOTES

1. CONTRACTOR SHALL INSTALL SCHEDULE 40 PVC CONDUIT (SLEEVES) FOR ALL IRRIGATION PIPING UNDER ALL PAVEMENT AREAS TO CONNECT ALL LANDSCAPE

W. SITE PREPARATION

1. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL MEET THE OWNER AND IDENTIFY TREES AND SHRUBS WHICH ARE TO BE PROTECTED AS WELL AS THOSE WHICH ARE TO BE REMOVED. DO NO CLEARING WITHOUT A CLEAR UNDERSTANDING OF EXISTING CONDITIONS TO BE PRESERVED.

2. TREES AND SHRUBS TO REMAIN SHALL BE PROTECTED BY THE INSTALLATION OF FENCING AT THE DRIP LINE OR AS DIRECTED BY THE OWNER (SEE LANDSCAPE DETAIL SHEET). PROTECTIVE FENCING SHALL BE INSTALLED PRIOR TO CONSTRUCTION, PROTECTIVE FENCING SHALL BE SUFFICIENT TO PREVENT CONSTRUCTION EQUIPMENT FROM COMPACTING SOIL AT THE ROOT ZONE AND DAMAGING TRUNKS AND BRANCHES.

3. IF, IN ORDER TO PERFORM EXCAVATION WORK, IT SHOULD BECOME NECESSARY

TO CUT ROOTS OF PLANTS TO BE SAVED, SUCH ROOTS SHOULD BE CUT NEATLY WITH A SMOOTH CLEAN CUT BY A SHARP SAW, COVERED WITH BURLAP, AND KEPT MOIST UNTIL ROOTS ARE BACK FILLED. TEARS OR JAGGED CUTS TO ROOTS ARE UNACCEPTABLE. 4. TREE AND SHRUB REMOVAL SHALL INCLUDE THE FILLING, CUTTING, GRUBBING OUT

OF ENTIRE ROOT SYSTEMS AND SATISFACTORY OFF—SITE DISPOSAL OF ALL TREES, SHRUBS, STUMPS, VEGETATIVE AND EXTRANEOUS DEBRIS PRODUCED BY THE

5. CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE INSIDE AND OUTSIDE THE LIMITS OF CONSTRUCTION DUE TO HIS CONTRACT OPERATIONS.

6. ALL REFUSE, DEBRIS, UNSUITABLE MATERIALS AND MISCELLANEOUS MATERIALS TO BE REMOVED SHALL BE LEGALLY DISPOSED OF OFF—SITE BY CONTRACTOR. 7. ALL INVASIVE EXOTIC VEGETATION SHALL BE DISPOSED OF OR TREATED AS PER THE LOCAL OR REGIONAL GOVERNING AUTHORITIES, REQUIREMENTS OR

X. ROOT CONTROL BARRIER

1. ROOT CONTROL PRODUCT SHALL BE A BIOLOGICAL BARRIER PRODUCT. PRODUCT SHALL BE 810—BARRIER ROOT CONTROL SYSTEM, AS MANUFACTURED BY BBA FIBERWEB/REEMAY, INC. AND DISTRIBUTED BY HORT ENTERPRISES, INC. HORT ENTERPRISES, INC.

POMPANO BEACH, FL 33061 1-800-966-4678

RECOMMENDATIONS.

2. PRODUCT SHALL BE A BIOLOGICAL BARRIER UTILIZING LIME—RELEASE CAPSULES INTEGRATED INTO A GEOTEXTILE FABRIC. ACTIVE HERBICIDE SHALL BE TRIFLURALIN, AND MINIMUM TIME RELEASE OF EFFECTIVE PRODUCT SHALL BE 1—5 YEARS IN THE

MOST ADVERSE CONDITIONS FOR SUCH A PRODUCT 3. PRODUCT SHALL BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS AND INSTRUCTIONS FOR ROOT CONTROL SYSTEMS.

4. USE PRODUCT WHERE TREES ARE WITHIN EIGHT FEET (8') OR LESS OF HARDSCAPE SURFACES INCLUDING CURBS, SIDEWALKS, STEPS, AND ROADWAYS. 5. SPECIFY 1 9.5" WIDTH OPTION.

6. WHERE CONDITIONS REQUIRE PRODUCT AS SET FORTH IN NO. 4 ABOVE, USE PRODUCT AT LEAST TEN FEET (10') IN EITHER DIRECTION FROM THE CENTER OF TRUNK ALONG LINEAR FEATURES SUCH AS CURBS, WALKWAYS, ETC. THE INTENT OF THIS SPECIFICATION IS TO PROVIDE A ROOT CONTROL SYSTEM WHERE ROOTS WOULD LIKELY CAUSE PHYSICAL DAMAGE TO ADJACENT HARDSCAPE SURFACES. FOUNDATIONS, OR OTHER ELEMENTS THAT MAY RECEIVE DAMAGE FROM ROOT

7. SEE WWW.BIOBARRIER.COM FOR ADDITIONAL INFORMATION AND PRODUCT SPECIFICATION.

Y. IRRIGATION

1. CONTRACTOR TO PROVIDE AN IRRIGATION DESIGN FOR BOTH LAWN AND BED AREAS. DESIGN TO BE SUBMITTED TO PROJECT LANDSCAPE ARCHITECT FOR REVIEW AND APPROVAL. CONTRACTOR TO VERIFY STATIC PRESSURE PRIOR TO DESIGN. CONTRACTOR IS RESPONSIBLE FOR ANY PRESSURE REDUCING DEVICES REQUIRED TO MEET PRESSURE REQUIREMENTS. SYSTEM DESIGN TO SHOW ALL VALVES, PIPING HEADS, BACKFLOW PREVENTION, METERS, AND CONTROLLERS, ALL SLEEVES IN PAVEMENT AREAS MUST BE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR BACKFLOW PREVENTION DEVICE INSTALLATION AND PERMITTING. CONTRACTOR SHALL NOT INSTALL IRRIGATION IN RIGHT—OF—WAY UNLESS REQUIRED BY CITY. NETAFIM DRIP IRRIGATION TO BE INSTALLED IMMEDIATELY AROUND BUILDING TO PREVENT WATER SPRAY ON BUILDING, WALKS, AND WINDOWS. NETAFIM PIPING TO BE BURIED JUST BENEATH SOIL SURFACE AND COVERED INSTALLED BY AN OWNER

2. DESIGNED SYSTEM SHALL CONSIST OF AN AUTOMATIC, UNDERGROUND IRRIGATION SYSTEM PROVIDING 100% COVERAGE WITH 100% OVERLAP, AND CONTAINING A RAIN SENSOR INSTALLED BY AN OWNER APPROVED CONTACTOR. THIS SYSTEM SHALL BE INSTALLED AND OPERATIONAL WITHIN TEN (10) DAYS OF THE INITIAL LANDSCAPE

1. CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS IN THE FIELD AND REPORT ANY DISCREPANCIES IN THE SITE SURVEY TO THE OWNER PRIOR TO STARTING WORK.

1. THE CONTRACTOR SHALL SUPPLY ALL PLANT MATERIALS IN QUANTITIES

2. ALL BIODEGRADABLE BURLAP SHALL BE UNTIED AND PULLED DOWN TO EXPOSE THE TOP 1/3 OF THE BALL. WIRE BASKETS AND OTHER NON—BIODEGRADABLE MATERIALS ATTACHED TO PLANTS SHALL BE REMOVED PRIOR TO PLANTING. CARE SHALL BE TAKEN NOT TO BREAK OR DISTURB ROOT BALL OF PLANTS.

4. PLANTS SHALL BE GUARANTEED TO A PERIOD OF ONE (1) YEAR AFTER ACCEPTANCE OF THE PROJECT AND SHALL BE VIGOROUS AND THRIVING AT THE END

5 CONTRACTOR SHALL LOCATE AND VERIFY ALL EXISTING UTILITY LINES PRIOR TO PLANTING AND SHALL REPORT ANY CONFLICTS TO THE OWNER.

SEVEN (7) CALENDAR DAYS OF NOTICE TO PROCEED.

PROCEED OF ANY DISCREPANCIES.

9. CONTRACTOR SHALL TAG AND NUMBER ALL PLANT MATERIAL TO BE RELOCATED. THE CONTRACTOR SHALL FULLY ASSIST AND COORDINATE THIS WORK WITH THE OWNER'S DESIGNEE PRIOR TO INITIATING FIELD DIGGING THE TREES.

BY THE OWNER'S DESIGNEE ON SITE. 11. THE CONTRACTOR SHALL BEAR ALL COSTS OF TESTING SOILS, AMENDMENTS, ETC. ASSOCIATED WITH THE WORK AND INCLUDED IN THE SPECIFICATIONS. 12. TYPICALLY, SHRUB AND GROUNDCOVER PLANTINGS ARE SHOWN IN MASS PLANTING BEDS. PLANTS SHALL BE PLACED ON A LINEAR SPACING CONFIGURATION

13. CONTRACTOR SHALL FIELD STAKE THE LOCATIONS OF ALL PLANT MATERIAL PRIOR

DRAWINGS. EXACT LOCATIONS OF RELOCATED PLANT MATERIAL WILL BE CLARIFIED

14. CONTRACTOR SHALL FIELD ADJUST LOCATION OF PLANT MATERIAL AS NECESSARY TO AVOID DAMAGE TO ALL EXISTING UNDERGROUND UTILITIES AND/OR EXISTING ABOVE GROUND ELEMENTS. ALL CHANGES REQUIRED SHALL BE COMPLETED AT THE CONTRACTOR'S EXPENSE AND SHALL BE COORDINATED WITH

15. ALL PLANTING AREAS, UNLESS OTHERWISE NOTED, SHALL INCLUDE THREE INCH (3") LAYER OF MULCH AS PER THE SPECIFICATIONS.

17. ALL EXISTING TREES TO REMAIN IN LAWN AREA SHALL RECEIVE A MULCH RING TWO FEET (2') OUT FROM EDGE OF TRUNK OR TO THE LIMIT OF THE ADJACENT LAWN AREA AT A DÉPTH OF THREE INCHES (3") AS PER THE SPECIFICATIONS,

OWNER'S DESIGNEE BEFORE PLANTING CAN BEGIN. 19. PLANT LIST QUANTITIES ARE PROVIDED FOR CONVENIENCE ONLY. IN THE EVENT OF QUANTITY DISCREPANCIES, THE DRAWING SHALL TAKE PRECEDENCE. ANY

DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE LANDSCAPE

AND COMPLETE INSTRUCTIONS. 21. ALL UTLITY BOXES, CLEANOUTS, ETC., SHALL BE PAINTED GREEN IF IN GRASS AREAS AND

PROPER ISA HORTICULTURAL PROCEDURES ARE FOLLOWED REGARDING THE TRIMMING, PRUNING, TRANSPLANTING, ETC. OF THESE TREES.

SITE NOTES

GENERAL PLANTING NOTES

SUFFICIENT TO COMPLETE THE PLANTING SHOWN ON THIS DRAWING.

3. ALL PLANTS SHALL BE WATERED BY HAND IN SUFFICIENT QUANTITIES TO THOROUGHLY WET ENTIRE ROOT SYSTEM IMMEDIATELY AFTER PLANTING.

OF THE GUARANTEE PERIOD SEE SECTIONS S, GUARANTEE FOR MORE DETAILS.

6. CONTRACTOR SHALL FAMILIARIZE HIM/HER SELF WITH THE LIMITS OF WORK AND EXISTING CONDITIONS AND VERIFY ALL INFORMATION. IF DISCREPANCIES EXIST, CONTRACTOR SHALL NOTIFY OWNER OR OWNER'S DESIGNEE IN WRITING WITHIN

7. CONTRACTOR SHALL VERIFY LOCATIONS OF ALL UNDERGROUND UTILITIES AND OBTAIN AS—BUILT INFORMATION. DRAWINGS WERE PREPARED ACCORDING TO THE BEST INFORMATION AVAILABLE AT THE TIME. CONTRACTOR SHALL NOTIFY OWNER'S REPRESENTATIVE IN WRITING WITHIN SEVEN (7) CALENDAR DAYS OF NOTICE TO

8. CONTRACTOR SHALL NOTIFY ALL NECESSARY UTILITY COMPANIES FORTY—EIGHT (48) HOURS MINIMUM PRIOR TO DIGGING FOR VERIFICATION OF ALL UNDERGROUND UTILITIES AND OTHER OBSTRUCTIONS AND COORDINATE WITH OWNER'S DESIGNEE IN WRITING PRIOR TO INITIATING OPERATIONS.

10. LOCATIONS OF RELOCATED PLANT MATERIAL ARE APPROXIMATED ON THE

AROUND BUILDING FOUNDATION AS SHOWN ON DRAWING. PLANT CENTER TO CENTER DIMENSIONS (O.C.) ARE LISTED ON THE PLANT LIST. FOR PERIMETER AND PARKING ISLAND SPACING, USE THE TRIANGULAR SPACING METHOD.

TO INITIATING INSTALLATION FOR THE REVIEW AND APPROVAL OF THE OWNER'S

THE OWNER'S DESIGNEE.


16. ALL TREES PLANTED IN LAWN AREA SHALL RECEIVE A THREE FOOT DIAMETER (3') MULCH RING AT DEPTH OF THREE INCHES (3^*) .

18. ANY SUBSTITUTIONS IN SIZE AND/OR PLANT MATERIAL MUST BE APPROVED BY THE OWNER'S DESIGNEE IN WRITING. ALL PLANTS WILL BE SUBJECT TO APPROVAL BY

20. CONTRACTOR SHALL REFER TO THE LANDSCAPE PLANTING DETAILS, PLANT LIST, GENERAL NOTES AND THE PROJECT MANUAL AND SPECIFICATIONS FOR FURTHER

BROWN IF IN MULCH AREAS. 22. THIS SITE MAY CONTAIN EXISTING TREES WHICH REQUIRE TRIMMING AND/OR PRUNING. THE LANDSCAPE COMPANY/CONTRACTOR MUST HAVE A CERTIFIED ARBORIST ON STAFF TO ENSURE

REVISIONS COMMENT



F160039 LANDSCAPE PLAN

ROJECT

STATE RD 84 &

SW 30 TH AVENUE

PROJECT No

CHECKED BY

DRAWN BY

CUMBERLAND FARMS

HOLLYWOOD FLORIDA

RADICE III 1000 CORPORATE DRIVE, SUITE 250 FORT LAUDERDALE, FL 33334 PH: (954) 202-7000 FX: (954) 202-7070


www.ThomasEngineeringGroup.com



LANDSCAPE GENERAL

NOTES

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MICHAEL D. GROSSWIRTH, LA6666871 ON 2017-10-02



Creative Solutions
Meaningful Places

HARRISON FRENCH
& ASSOCIATES, LTD

t 508.528.0770


31 Hayward Street Franklin, Massachusetts 02038 www.hfa-ae.com


THIS DRAWING WAS PREPARED FOR USE ON A SPECIFIC SITE AT HOLLYWOOD, FL. CONTEMPORARANEOUSLY WITH ITS ISSUEDATE ON 08/28/17, AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSEDA RCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.



CHECKED BY: DT
DRAWN BY: ENV


ISSUE BLOCK






GROUND FLOOR PLAN

A-101





3/16" = 1'-0" RIDGE VENT FIBER CEMENT SHINGLES (FC-2) INTERNALLY ILLUMINATED SYNTHETIC WOOD RIDGE 32' - 9" SIGNAGE TRIM(SW-1) T.O. CANOPY 30' - 6" FIBER CEMENT SHINGLES (FC-2) ALUM. GUTTER & DOWNSPOUT (GU-1) VINYL-CLAD DOUBLE HUNG WINDOW, TYP. STANDING SEAM -METAL ROOF METAL FLASHING - @ ALL DORMERS, TYP. ALUM. GUTTER & DOWNSPOUT (GU-1) EMERGENCY B.O. FASCIA (LOW) 13' - 10 1/4" LIGHT FIXTURE SYNTHETIC WOOD TRIM PATIO FURNITURE BY OWNER -SYNTHETIC WOOD TRIM FIBER CEMENT SIDING (FC-1) ALCOHOLD STATE OF THE PARTY OF CULTURED STONE
— WATERTABLE T.O. STONE CAP 3' - 0" ----- 3'-6" HIGH METAL RAILING ALUM. CURTAINWALL - CONC. SIDEWALK CULTURED STONE PRE MANUF. FIBERGLASS


LEFT SIDE ELEVATION - SD

-SYSTEM (WHITE)

COLUMN SHROUD, TYP


-(WHITE)-

Meaningful Places HARRISON FRENCH & ASSOCIATES, LT t 508.528.0770 31 Hayward Street Franklin, Massachusetts 02038 www.hfa-ae.com



ISSUE BLOCK

CHECKED BY: DOCUMENT DATE: 08/28/1




EXTERIOR ELEVATIONS

A-200

FRONT ELEVATION - SD

3/16" = 1'-0"



Creative Solutions
Meaningful Places

HARRISON FRENCH
& ASSOCIATES, LTD

t 508.528.0770

31 Hayward Street
Franklin, Massachusetts 02038
www.hfa-ae.com

THIS DRAWING WAS PREPARED FOR USE ON A SPECIFIC SITE AT HOLLYWOOD, FL.
CONTEMPORARANEOUSLY WITH ITS ISSUEDATE ON 08/28/17, AND IT IS NOT SUTABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSEDA RCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.



ISSUE BLOCK

DRAWN BY: ENV

DOCUMENT DATE: 08/28/17



EXTERIOR ELEVATIONS

A-201