



THOMPSON
ARCHITECTURAL PRODUCTS

DIVISION OF
AMERICAN MADE
AWNINGS OF HOLLYWOOD

5828 Washington Street - Hollywood - FL 33023

RE: Awning Quote nov 20 2017 REV 6/10 /19 rev 6/29/20

AMERICAN LEGION POST 92

211 N 21 AVE

HOLLYWOOD FL

ATTN. RM SNYDER -610-703-0666 em=rmsnyder1019@gmail.com

Build and install new awning with leantoo awnings attached on the left it will be 11'6" wide x12' projection with a round top in the center over the door 14' wide and on the west side another leantoo awning 14' wide we will also provide a rendering for support of this retail price=\$23,700.00

Special pricing=\$16,300.00

Recover front round top plus build 2 new leantoo awnings 5' wide x4' over side doors=\$2400

Fixed awning frames, fabricated by us, are certified by an engineer to comply with the latest building code release. The framework is designed to withstand winds in excess of 174 miles per hour with the cover removed. With the cover on, it is certified to take sustained winds of up to 75 miles per hour and up to 120 mile per hour three second gusts. After nearly 40 years in business we can proudly say that our frames are built to last for decades.

Framing Product for Fixed Awnings

- Frame will be manufactured with Gatorshield steel; a very durable, American made steel that weighs approximately 32% less than schedule 40 steel out of China and has about 4 times the inherent corrosion resistance.
- All metal will be 50/55 Gatorshield by Allied Tubing unless otherwise specified. This cold rolled tubing is zinc coated (galvanized) on both the inside and outside walls with 99.99% pure zinc making the galvanizing layer virtually lead-free. There is also a conversion coating and a clear polymer top coat to further assist the zinc with corrosion inhibition.
- All structural pipe 1.75" round and legs 3" SQUARE
- All framing members to be joined by mig welding (wire feed) by a certified welder.
- Each framing member and all pipe ends are to be mitered or coped appropriately to provide a tight clean fit.
- Welds that interface with the vinyl shall be ground smooth and deburred.
- Each framing member will be primed with a zinc and epoxy based primer at the junctions (in effect, re-galvanizing the welds) and have an even coat of paint over the entire frame.
- No smashed pipe ends or open pipe ends allowed.
- Frame will be sprayed with Sherwin Williams electrostatic paint in a (**choice**) color.

Vinyl Application

- Choice of Color and fabric.
- Vinyl fabric will be used 18 oz. with a UV top coat.
- Vinyl will be installed tight and free of wrinkles, sagging, or puckers. All panels will be equal intension and quality.
- Vinyl will be installed with a lace on process in which the awning is attached with a nylon rope assembly through brass grommets around the tubular construction.
- All sewing connections will have a color coordinated stitching warranty is available with an upgrade to Tenara thread.
- We will also give you the Fire Certification cards for the fire marshal.
- All sewn seams will be sewn with a U V 132 thread system.
- Curtain will be made of fine mess screen it will stop the rain and still breath.
- All fabric or vinyl products shall be warranted for a period of five (5) years from the date of installation, provided covers are removed as required by the Florida Building Code in the unlikely event of a hurricane.
- Warranty covers excessive fading, cracking, or discoloration.

Installation

- Installations shall be structurally sound, level, and comply with drawings and manufacturer's recommendations.
- After installation of framing we will touch up any damaged finish on frame to match color as specified.
- All work will be monitored and supervised at all times, all member will have no less than 10 years experience in awning erection.

Terms and conditions

WE HEREBY PROPOSE TO FURNISH THE ABOVE-MENTIONED LABOR AND MATERIAL FOR THE SUM OF AS FOLLOWS

City of Hollywood building fees with zoning and fire should be approx. 900 or so
Processing fees are =\$75 per hour and for noc fees but the legion has agreed to process it there selves
Engineering and cad=\$1000
Total=\$20,600
Deposit of 50% upon approval prior to permitting balance on completetion

REGARDS
JERRY THOMPSON/AWNINGS OF HOLLYWOOD

A+ CONCRETE RESTORATION
 1855 Banks Rd
 Margate, FL 33063
 OFFICE: (954)757-9099
 FAX: (954)575-1532

aplusconcreterestoration@gmail.com



AGREEMENT

aplusconcreterestoration.com

Estimate No.	Date
20180681	07/02/20

Name/Address
American Legion Post #92 211 NW 21st Ave Hollywood, FL 33020

Ship To
Veterans Association REVISED FROM 6/12/2019

Email
rmsnyder1019@gmail.com

Phone	Terms
610-703-0666	10+45+45

Description	Total
We hereby propose to furnish the material and professionally perform the labor for the completion of: Front concrete slab 36'x15'	
1. Remove all existing and haul away to dump.	
2. Excavate, dig, grade, form, tamp/compact with footers and rebar where required, per city codes. 8"x8" footer per city codes if required.	
3. Supply, place, and finish with 4" of 3000 psi fibermesh concrete with a light broom finish to complete.	
4. Sidewalks broken up to 50'x5' and 31'x3.6" to be removed, prep, formed, compacted, per city codes.	7,170.00
5. Supply place and finish with new 3000 psi fibercrete concrete.	
Permit Application, drawings and runner fees, to contractor, with city and county permitting fees, ALL INCLUSIVE. A SITE PLAN and a BOUNDARY SURVEY WILL BE NEEDED FOR THE CITY PERMITTING	695.00
Contractor is responsible for project area to be left clean of all construction debris.	
Contractor is responsible for all inspections. Area landscaping/sod replacement/sprinklers is customers responsibility	
Mobilization to start Job included	
Prompt payments as follows 50%- at start of job. Balance upon completion.	
TERMS AND CONDITIONS ATTACHED.	

Fully licensed+ insured. #02-10318CP/CGC-05-8923 Reference Lists available.

\$7,865.00

PLEASE note-cash or checks only. Online oayments require surcharge.

The above stated scope of work, and the attached Terms and Conditions are hereby accepted, you are authorized to do the work as specified.

X _____ PRINT X _____ DATED X _____

GIBBS LAND SURVEYORS

2131 HOLLYWOOD BOULEVARD SUITE 204 HOLLYWOOD, FLORIDA 33020

PHONE: 954-923-7666 FAX: 954-923-7668

SSEELEY@GIBBSLANDSURVEYORS.COM

July 6, 2020

Lisa Liotta
Hollywood Community Redevelopment Agency
1948 Harrison Street
Hollywood Fl 33020

Attn: American Legion 92

RE: American Legion Post 92 – 211 N 21 Avenue, Hollywood, FL

We are pleased to submit the following proposal for Professional Land Surveying services on the above referenced project.

LIMITS OF WORK

Lots 4,5 and 6, Block 10 of "Town of Hollywood"


BASE SCOPE OF WORK

Boundary Survey – an updated survey to show all above ground improvements.

Deliverables: 5 signed & sealed surveys. CAD file for architect, upon request.

Lump sum fee: \$600.00

Sincerely,



Stephen K. Seeley, PSM
President